SPECIFICATIONS

FOR

REBID:

SENSORY TRAIL IMPROVEMENTS
WATCHUNG RESERVATION
BOROUGH OF MOUNTAINSIDE
COUNTY OF UNION, NEW JERSEY

BA#5-2017; UNION COUNTY ENGINEERING PROJECT #2016-006

JANUARY 2017

UNION COUNTY OFFICIALS BOARD OF CHOSEN FREEHOLDERS

Bruce H. Bergen, Chairman Sergio Granados, Vice Chairman Linda Carter, Freeholder Angel G. Estrada, Freeholder Christopher Hudak, Freeholder Mohamed S. Jalloh, Freeholder Bette Jane Kowalski, Freeholder Alexander Mirabella, Freeholder Vernell Wright, Freeholder

CLERK OF THE BOARD

James E. Pellettiere, RMC

COUNTY MANAGER

Alfred J. Faella

DEPARTMENT OF ENGINEERING, PUBLIC WORKS AND FACILITIES MANAGEMENT

Joseph A. Graziano, Sr., CPWM
Director, Department of Engineering, Public Works and
Facilities Management

COUNTY ENGINEER DIVISION OF ENGINEERING

Thomas O. Mineo, P.E. 2325 South Avenue Scotch Plains, New Jersey 07076 Telephone: (908) 789-3675 Fax: (908) 789-3674

PREPARED BY: CME ASSOCIATES

Consulting & Municipal Engineers 1460 Route 9 South Howell, New Jersey 07731 T: 732-462-7400

F: 732-409-0756

COUNTY OF UNION NOTICE TO BIDDERS

Sealed bids will be received by the director of the Division of Purchasing, or her designee, at the County of Union, New Jersey on January 31, 2017 at 10:30 a.m., prevailing time, in the 3rd Floor Conference Room, U.C. Administration Building, 10 Elizabethtown Plaza, Elizabeth, New Jersey for:

REBID: SENSORY TRAIL IMPROVEMENTS – WATCHUNG RESERVATION BOROUGH OF MOUNTAINSIDE, COUNTY OF UNION, NEW JERSEY BA#5-2017; UNION COUNTY ENGINEERING PROJECT #2016-006

Bid Packages may be obtained at no charge by registering and downloading at http://ucnj.org/bid-specs. Bid Packages may also be obtained in person from the Division of Engineering at 2325 South Avenue, Scotch Plains, New Jersey 07076 between 8:30 a.m. and 4:00 p.m. weekdays upon payment of a non-refundable money order or bank check in the amount of \$275.00 made payable to the County of Union. No Personal / Company checks will be accepted. Requests for mailing of specifications will not be honored. For further information please call 908-789-3675.

The County reserves the right to reject any and all bids and to waive any and all informalities in the bid.

Bids shall be submitted in a sealed envelope and clearly marked with the subject of the bid, name and address of the bidder, phone & fax number, and date of the bid opening. Each bid must be delivered to reach the Division of Purchasing prior to the stated time of the opening of the bids. The County will not be responsible for late delivery by the U.S. Mail or any other carrier. If hand delivered, please note that parking and security access at the County Complex may cause delays and bidders should take them into consideration in order to submit a timely bid. **No** late bids will be accepted.

Bidders are required to comply with the requirements of N.J.S.A. 10:5-31 et seq. and N.J.S.A.C. 17:27.

LAURA M. SCUTARI, QPA, MPA, DIRECTOR OF PURCHASING

UNION COUNTY BOARD OF CHOSEN FREEHOLDERS

We're Connected to You!

NB-1

Revised: 01/13/16

REBID: SENSORY TRAIL IMPROVEMENTS – WATCHUNG RESERVATION BOROUGH OF MOUNTAINSIDE, COUNTY OF UNION, NEW JERSEY

BA#5-2017; Union County Engineering Project #2016-006

TABLE OF CONTENTS

Cover Sheet: County Officials NB-1: Notice to Bidders

GENERAL SPECIFICATIONS

Definitions

Section	1:	BID	F	ORM
---------	----	-----	---	-----

Section 2: WITHDRAWAL OF BID DUE TO MISTAKE

Section 3: QUALIFICATIONS OF BIDDERS AND REQUIRED SUBMISSIONS

Section 4: INTERPRETATIONS AND ADDENDA

Section 5: OBLIGATION OF BIDDER TO INSPECT SITE AND CONTRACT DOCUMENTS

Section 6: BID AND PERFORMANCE GUARANTEE Section 7: COMMENCEMENT AND COMPLETION

Section 8: BIDDER AFFIDAVIT Section 9: BID SECURITY

Section 10: LABOR AND MATERIALS Section 11: INSURANCE REQUIREMENTS

Section 12: INDEMNIFICATION REQUIREMENTS

Section 13: ROYALTIES AND PATENTS Section 14: PLANS AND SPECIFICATIONS

Section 15: GUARANTEE AGAINST DEFECTIVE WORK Section 16: TRAFFIC AND STREET MAINTENANCE

Section 17: CONTRACTOR'S EMPLOYEES

Section 18: OWNERSHIP DISCLOSURES REQUIRED

Section 19: NON-COLLUSION AFFIDAVIT

Section 20: EQUAL EMPLOYMENT OPPORTUNITY COMPLIANCES
Section 21: COMPLIANCE WITH NEW JERSEY PREVAILING WAGE ACT

Section 22: BRAND NAME OR EQUAL Section 23: LINES AND GRADES

Section 24: NUMBER OF WORKING DAYS

Section 25: PROMPT PAYMENT OF CONSTRUCTION CONTRACTS (NJ Prompt Payment Act)

Section 26: STOPPING WORK ON ACCOUNT OF BAD WEATHER

Section 27: ACCESS FOR OTHER CONTRACTORS Section 28: CONDEMNED MATERIALS AND WORK

Section 29: STORAGE

Section 30: FINAL CLEAN UP

Section 31: SUB-LETTING OF WORK

Section 32: SAFETY

Section 33: QUALITY, SAFETY AND PERFORMANCE STANDARDS Section 34: MATTERS NOT MENTIONED IN CONTRACT DOCUMENTS

Section 35: PERMITS

Section 36: CONTRACTOR TO PROVIDE PROOF OF PAYMENT

Section 37: CHANGE ORDERS
Section 38: SUPPLEMENTAL WORK
Section 39: FORM OF CONTRACT
Section 40: PROGRESS PAYMENTS

Section 41: INSPECTION Section 42: DAMAGES

Section 43: LIQUIDATED DAMAGES

Section 44: AFFIRMATIVE ACTION REQUIREMENTS Section 45: INVESTMENT ACTIVITES WITH IRAN

TOC-1 Revised: 2016.08.30

GENERAL SPECIFICATIONS CONTINUED

Section 46: COMPLIANCE WITH THE PUBLIC WORKS CONTRACTOR REGISTRATION ACT

(N.J.S.A. 34:11-56.48 et seq)

Section 47: UTILITIES

Section 48: MATERIAL COMPLIANCE AND SHOP DRAWINGS

Section 49: PRECONSTRUCTION

Section 50: DISPUTES UNDER THE CONTRACT

Section 51: CONTRACTOR BUSINESS REGISTRATION CERTIFICATE

(New Mandatory Requirement – Effective 1/18/2010

Section 52: BID PROTEST - LEGAL FEES AND COSTS

Section 53: AMERICAN GOODS AND PRODUCTS WHERE POSSIBLE

Section 54: NEW JERSEY PAY-TO-PLAY REQUIREMENTS

Section 55: STATEMENT OF EQUIPMENT TO BE USED IN CONSTRUCTION

Section 56: NEW JERSEY SALES AND USE TAX REQUIREMENTS

BIDDING DOCUMENTS

Bid Document Submission Checklist

Bidding Documents

Bid Form

Consent of Surety

Bidder Signature Page

Bidder Disclosure Statement

Subcontractor Identification Statement: List of Subcontractors

Subcontractor Identification Certification

Acknowledgement of Addendum

Contractor Business Registration Certificate

Affirmative Action Requirement

Experience Statement

Certificate of Bidder Showing Ability to Perform Contract

Non-Collusion Affidavit

Contractor Registration Advisement

Americans with Disabilities Act

Statement of Bidder's Qualifications

Contractor Performance Record

Affidavit Regarding List of Disbarred, Suspended or Disqualified Bidders

Prior Negative Experience Questionnaire-Certification

Contractor's Certification of Compliance - New Jersey Prevailing Wage Act

Uncompleted Contracts Affidavit

Certificate of Insurance Statement

Collection of Use Tax on Sales to Local Governments Statement

Time of Completion

Disclosure of Investment Activities in Iran

STANDARD SPECIFICATION FORM - SS-1

NEW JERSEY PREVAILING WAGE DETERMINATION DOCUMENTS

PROJECT TECHNICAL SPECIFICATIONS

Revised: 2016.08.30

TOC-2

UNION COUNTY BOARD OF CHOSEN FREEHOLDERS INSTRUCTIONS TO BIDDERS AND FORMS

DEFINITIONS

Wherever reference is made to the County, Title of Project, Bidder, or Vendor/Contractor they shall be as follows:

OWNER/COUNTY:

Union County Board of Chosen Freeholders UC Administration Building, 6th Floor 10 Elizabethtown Plaza Elizabeth, New Jersey 07207

ADDRESS BIDS AND SUBMIT TO:

Union County Division of Purchasing UC Administration Building, 3rd Floor 10 Elizabethtown Plaza Elizabeth, NJ 07207

Attn: Laura M. Scutari, QPA, MPA, Director, Division of Purchasing

Telephone: 908-527-4130 Facsimile: 908-558-2548

TITLE OF PROJECT: Rebid: Sensory Trail Improvements – Watchung Reservation

Borough of Mountainside, County of Union, New Jersey

BA#5-2017; UC Engineering Project #2016-006

BIDDER: Bidder shall be a single overall contract bidder

ENGINEER: CME Associates, Consulting & Municipal Engineers

1460 Route 9, South Howell, New Jersey 07731

COUNTY ENGINEER AND/OR CONSTRUCTION MANAGER (as applicable):

COUNTY ENGINEER:

Thomas O. Mineo, P.E. Union County Division of Engineering 2325 South Avenue Scotch Plains, NJ 07076

Office: (908) 789-3675 Facsimile: (908) 789-3674 Email: tmineo@ucnj.org

CONSTRUCTION MANAGER:

GENERAL SPECIFICATIONS

1. BID FORM

Bids for this Work will be enclosed in a sealed envelope addressed to the Purchasing Division, County of Union, New Jersey, Union County Administration Building, 10 Elizabethtown Plaza, Elizabeth, New Jersey 07207, with the full name of the Project clearly marked on the outside. Refer to the sheet marked "Notice of Bid (Advertisement)" for the correct name of the Project. Bidders must submit their bids on the attached pricing sheet (Bid Form), in a sealed envelope addressed to the County and bearing on the outside: the name of the Bidder, Bidder's business address, and the title of the Project.

The Division of Purchasing will receive the bids for this Work at the Union County Administration Building, 10 Elizabethtown Plaza, Elizabeth, New Jersey on the date and time noted on the sheet marked "**Notice of Bid (Advertisement)**".

The County will not assume responsibility for bids forwarded by mail. It is the individual's responsibility to see that the bids are presented to the Purchasing Division at the time and at the place designated.

Bids will be accepted only on the Bid Form supplied. Bids on forms other than the original supplied herein will be rejected. The "complete" Bid Documents includes the Bid Bond, Bid Form, Bidder's Checklist, Consent of Surety, Ownership Disclosure Certification, Non-Collusion Affidavit, and any other documents noted in these Instructions to Bidders or Contract Document to be submitted with this Bid.

The bidder will state in the bidding sheet the price per unit of measure for each scheduled Item of Work for which he will agree to carry out the Work, and the Total Bid Price for the construction of the Project.

The prices in the Bid Form shall be typed or written in pen and ink. Erasures or alterations must be initialed by the bidder in ink.

The bidding sheet for this Project may include a fixed amount as a Bid Allowance. If applicable, all bidders are required to add this fixed amount to their base bid and to include this additional amount in their Bid Bond. This sum will be included in the Contract as well as the performance, labor and materials bond. Payment by the County will be made to the Contractor from these funds only upon the completion of extra Work pursuant to a written Change Order(s) signed by the County's Engineer or his designee and the Contractor, prior to the commencement of such Work. Work commenced prior to written approval by the County shall be done at Contactor's risk. Such payment will only be in the amount agreed to by the parties, in writing in the Change Order(s). See Section 37, Change Orders, of these general specifications for further details.

Refer to Bid Document Submission Checklist for all required documents.

In the event there is a discrepancy between the unit price given and the extended total, the unit price will govern. Any discrepancies will be mathematically adjusted.

Insert applicable alternates, if any have been specified, applicable to the Bidder's Work. All alternates MUST be bid upon. Any Bidder's failure to do so will be deemed a material, non-waivable defect and shall render the bid nonresponsive. The Bidder shall clearly designate whether the change in price is an addition or subtraction, by using either a "+" sign or the word "addition", or in the alternative, a "-"sign or the word "minus". If there is no other change in price, the Bidder shall insert "NC" or "No Charge".

When two or more low bids are equal in all respects, awards will be made according to the provisions of N.J.S.A. 40A:11-6.1(d).

Where unit prices have already been established by the Contract Documents, the Bidder agrees that such unit prices shall prevail. All unit prices, whether filled in by the Bidder or established by the Contract Documents, shall become part of the Contract. No bid will be considered or award made, unless applicable unit prices, as required, are filled in.

The County reserves the right to reject any or all bids and also reserves the right to waive any informality in the bids received so long as said waiver is not of a response which is considered to be material and non-waivable pursuant to law.

The County of Union has the right to reject any and all bids from any bidder that is in, or contemplates bankruptcy of any chapter of nature. Said bidder shall notify the County, in writing, of any condition or knowledge of the same.

Conditional bids will not be accepted. Bids may be withdrawn prior to the advertised time for the opening of bids or authorized postponement thereof or in accordance with the provisions of N.J.S.A. 40A:11-23.3 discussed below. Bids received after the advertised time shall not be considered. Bidders shall be solely responsible for premature opening or late delivery of bids not properly marked, addressed, or directed.

2. WITHDRAWAL OF BID DUE TO MISTAKE

N.J.S.A. 40A:11-23.3 authorizes a bidder to request withdrawal of a public works bid due to a mistake on the part of the bidder. A mistake is defined by N.J.S.A. 40A:11-2(42) as a clerical error that is an unintentional and substantial computational error or an unintentional omission of a substantial quantity of labor, material, or both, from the final bid computation.

A bidder claiming a mistake under N.J.S.A. 40A:11-23.3 must submit a request for withdrawal, **in writing**, by certified or registered mail to Michael M. Yuska, QPA,

G-3

Director, Division of Purchasing, County of Union, New Jersey, Union County Administration Building, 10 Elizabethtown Plaza, Elizabeth, New Jersey 07207. The bidder must request withdrawal of a bid due to a mistake, as defined by the law, within five business days after the receipt and opening of the bids. Since the bid withdrawal request shall be effective as of the postmark of the certified or registered mailing, Michael M. Yuska, QPA, Director of the Division of Purchasing or his designee may contact all bidders, after bids are opened, to ascertain if any bidders wish to, or already have exercised a request to withdraw their bid pursuant to N.J.S.A. 40A:11-23.3.

A bidder's request to withdraw the bid **shall** contain evidence, including any pertinent documents, demonstrating that a mistake was made. Such documents and relevant written information shall be reviewed and evaluated by the County's designated staff pursuant to the statutory criteria of N.J.S.A. 40A:11-23.3.

The County will not consider any written request for a bid withdrawal for a mistake, as defined by N.J.S.A. 40A:11-2(42), by a bidder in the preparation of a bid proposal unless the postmark of the certified or registered mailing is within the five business days following the opening of bids.

3. QUALIFICATIONS OF BIDDERS AND REQUIRED SUBMISSIONS

The County may make such investigation as it deems necessary to determine the ability of the Bidders to perform the Work, which includes investigation of any and all subcontractors listed with the bid. The Bidder shall furnish any information and data for this purpose as the County may request.

4. INTERPRETATIONS AND ADDENDA

Any explanation desired by a bidder regarding the meaning or interpretation of the Contract Documents must be requested in writing to the County Engineer or Design Professional as the case may be and with reasonable time allowed for a reply to reach bidders before submission of their bids. Any interpretation or instruction made by the County Engineer will be in the form of an addendum to the Contract Documents or clarification and will be furnished to all prospective bidders. Oral explanations or instructions given before the award of the Contract will not be binding. Bidders are required to bring to the attention of the County Engineer, the discovery of any apparent ambiguity, inconsistency, error, discrepancy, omission in the Contract Documents for interpretation and correction at least ten (10) working days before opening of bids with the exception of Saturdays, Sundays and holidays.

All Addenda issued through the Offices of the County Engineer are amendments to the Contract Documents and shall be considered in preparing bids. Same shall become part of the Contract Documents.

Addenda take precedence over all earlier documents and over each other according to the latest date. Addenda unless themselves interpretive remain subject to interpretation the same as any other document incorporated in the Contract.

Addenda may be issued by the County Engineer up to seven (7) working days prior to the opening of bids. Failure of any bidder to receive an addendum shall not relieve such bidder from the obligation imposed by such addendum. Bidders are to keep themselves currently acquainted with the Contract Documents during the entire bidding period and make inquiry on their own initiative as to issuance of any Addenda. Receipts of all Addenda shall be acknowledged on the "Acknowledgement of Receipt of Changes" included in the bid package and must be submitted with the bid.

5. OBLIGATION OF BIDDER TO INSPECT SITE AND CONTRACT DOCUMENTS

At the time of the opening of bids, each Bidder will be presumed to have inspected the site(s) and to have read, and be thoroughly familiar with the Contract Documents. The failure or neglect of any Bidder to receive or examine any form, instrument, or document shall in no way relieve any Bidder from any obligation in respect to its bid.

The Bidder shall examine the contents of the Project Manual and the set of Drawings and assure itself that all pages of the Specifications, Drawings, and other Contract Documents are included in the documents obtained for bidding purposes. Should the Specifications, Drawings, and other Contract Documents be incomplete, the Bidder shall notify the County Engineer in writing, who will supply the Bidder with any missing pages of Specifications, Drawings, or other Contract Documents. The lack of such written notification by the Bidder will be construed as evidence that the Specifications, Drawings, or other Contract Documents supplied it for bidding purposes are full and complete and as a waiver of any subsequent claim to the contrary.

6. BID AND PERFORMANCE GUARANTEE

Each bidder must furnish a Bid Bond, Certified Check or Bank Cashier's Check in the amount of ten percent (10%) of the Bid. Checks shall be drawn to the order of the County of Union, New Jersey, not to exceed \$20,000.

Each bidder must furnish with the bid a certificate from a Surety Company, i.e. Consent of Surety, stating that in the event of the contract being awarded to said bidder, such Surety Company will provide the Contractor with Bonds guaranteeing the faithful performance of the Work in accordance with the plans and specifications, and the payment for labor, materials, and all other indebtedness which may accrue on the account of this Work. A Performance, Labor and Materials bond will be furnished by the Contractor upon an award of Contract, and will be in the amount of 100% of the contract price.

G-5 Revised: 2016.12.13 A one-year Maintenance Bond will be required upon acceptance of the Project by the County in the amount as stated in Section 15 of the General Specifications. Bonds will be written by a firm authorized to issue the bonds under the laws of the State of New Jersey and be in a form acceptable to the County Counsel.

N.J.S.A. 40A:11-1.1 et. seq. allows the prime Contractor to furnish the Performance Security for his Subcontractors. The County of Union requires Performance Security to be furnished by the prime contractor for the entire job in the total amount of the contract.

The County of Union shall award the contract or reject all bids within sixty (60) days; except that the bids of any bidders who consent thereto may, at the request of the County be held for consideration for such longer periods as may be agreed.

The County will return all certified checks or cashier's checks after the proposals have been opened, read, tabulated and checked except those of the three (3) bidders who have bid the lowest total price for carrying out the Project. The County will return the checks of these bidders when a contract is awarded to the successful bidder within ten (10) days after the award of the contract.

If the successful bidder refuses or neglects to sign the said Agreement and furnish the required bonds, the Bid Bond will be held and used by the County to offset any damages for such refusal or neglect.

7. COMMENCEMENT AND COMPLETION

Work will not commence until a Notice to Proceed is received from the County Engineer.

Upon substantial completion of the Project, the Contractor must request a joint inspection with the County Engineer. Upon completion of this inspection, the County Engineer will prepare a list of incomplete or incorrect items (punch list) and have Contractor initial and date same. The Contractor shall rectify all deficiencies noted on the punch list within 30 calendar days of receipt of the list. The County Engineer may approve extensions for extenuating circumstances.

8. BIDDER AFFIDAVIT

All Bidders are required to complete, sign, and submit with their Bid, the attached "Affidavit Regarding List of Debarred, Suspended or Disqualified Bidders". (See form enclosed)

9. BID SECURITY

All Bidders are required to submit a form of Bid Security with their bids. (Bid Bond or Certified Funds)

The Bid Security shall be in the amount of ten percent (10%) of the Bid, but not in excess of Twenty Thousand Dollars (\$20,000.00), and payable to the order of the "County of Union."

10. LABOR AND MATERIALS

The prices will cover all costs of any nature incident to and growing out of the Work, including all labor, material, equipment, transportation, loss by damage or destruction of the Project, settlement of damages, and for replacement of defective work or materials. N.J.S.A. 54:32B-1 et seq. exempts all materials sold to the County of Union from sales or use taxes and should not be included in the prices provided on the Bidding Sheet.

11. INSURANCE REQUIREMENTS

The County of Union requires all contractors to be able to comply with the following insurance requirements. In the event a bid is accepted by the County, the contractor must accept the applicable insurance requirements, as set forth below, as part of any contract awarded to it by the County.

Contractor shall carry and maintain at all times while the contract is in full force and effect, the following insurance coverage with an insurance company or companies acceptable to the County, with limits not less than those shown below. A Certificate of Insurance shall be filed with the County <u>prior</u> to commencement of any Work indicating the following:

- a) Commercial General Liability (CGL): Coverage for all operations including, but not limited to, contractual, products and completed operations, and personal injury with limits no less than \$5,000,000 per occurrence/\$10,000,000 aggregate. The County of Union, its Board of Chosen Freeholders, officers, employees, agents and servants shall be included as an additional insured. Coverage is provided on a primary and non-contributory basis to the County of Union, et al.
- b) Automobile Liability: Coverage for all owned, non-owned and hired vehicles with limits not less than \$5,000,000 per occurrence, combined single limits (CSL) or its equivalent.
- c) Workers Compensation: As required by the State of New Jersey and Employers Liability with limits not less than \$1,000,000 per accident for bodily injury or disease.
- d) Professional Liability (if design/build): Coverage with limits not less than \$1,000,000 per occurrence or claim, \$2,000,000 aggregate

- e) Contractor's Pollution Legal Liability and/or Asbestos Legal Liability and/or Errors & Omissions (if project involves environmental hazards): Coverage with limits no less than \$1,000,000 per occurrence or claim/\$2,000,000 aggregate.
- f) Builders Risk (for major renovations): During the course of construction utilizing an "All Risk" coverage form with limits equal to the completed value of the project and no coinsurance penalty provisions.

Where applicable, a waiver of subrogation in favor of the County of Union, its Board of Chosen Freeholders, officers, employees, agents, servants and the State of New Jersey is to be included in those policies of insurance where permitted by law.

Notice of Cancellation: Each insurance policy required above shall provide that coverage shall not be canceled, except with notice to the Entity.

Special Risks or Circumstances: The County reserves the right to modify these requirements, including limits, based on the nature of the risk, prior experience, insurer, coverage, or other special circumstances.

12. INDEMNIFICATION REQUIREMENTS

The County of Union requires all bidders to accept the following indemnification requirements in the event the County accepts their bid. The Contract awarded by the County to the successful bidder will contain the following provision:

"To the fullest extent permitted by law the Contractor shall indemnify and hold harmless the owner and the owner's consultants, agents, representatives, and employees from and against any and all claims, damages, losses, costs, and expenses, including, but not limited to attorneys' fees, legal costs and legal expenses arising out of or resulting from the performance of the Contractor's work under this contract, provided that such claim, damage, loss, cost, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the work itself) caused or alleged to be caused by the negligent acts, negligent omissions, and/or fault of the Contractor, anyone directly or indirectly employed or retained by the Contractor, or anyone for whose acts the Contractor may be liable regardless of whether caused in part by the negligent act or omission of a party indemnified hereunder provided it is not caused by the sole negligence of a party indemnified hereunder. Contractor shall further indemnify and hold harmless the County and the County's consultants, agents, representative, and employees from and against any and all claims, damages, losses, costs, and expenses, including, but not limited to attorneys' fees, legal costs and legal expenses, arising out of or resulting from performance of the work, provided that such claim, damage, loss, cost, or expense is attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property (other than the work itself) caused or alleged to be caused by the negligent acts, negligent omissions, and/or fault of

> G-8 Revised: 2016.12.13

the County or the County's consultants, agents, representatives, or employees and arises out of this project and provided such claim, damage, loss, cost, or expense is not caused by the sole negligence of a party indemnified hereunder."

13. ROYALTIES AND PATENTS

The Contractor shall pay all royalties and license fees. He shall defend all suits or claims for infringement of any patent rights and shall hold the County harmless from loss on account thereof.

14. PLANS AND SPECIFICATIONS

In carrying out the Work, the plan(s) and the specifications will be followed by the Contractor. Minor alterations in the plan may be made or permitted by the County Engineer from time to time and, if no additional Work is necessary, there will be no additional charge for carrying out such minor alterations.

The Contractor shall provide the County Engineer a set of reproducible as-built drawings upon completion of the Project. The Contractor shall maintain an updated construction progress plan in the Project field office at all times.

When applicable, The New Jersey Department of Transportation Standard Specifications for Road and Bridge Construction, as amended, and Supplemental Specifications for State Aid Projects, herein after referred to as the "Standard Specifications", are made a part of these specifications and contract for the improvements, and will govern the construction of this Project, the material used and the execution of this Project, except as revised and modified herein. The references to these specifications are given herein for the purpose of aiding in the rapid location of the description of the various items herein specified. The entire Work must be carried on and completed to the satisfaction of the County. The Standard Specifications are amended as follows:

"Any reference to the Commissioner, Department, Department Laboratory, Engineer or Inspector should be redefined to be the County of Union".

15. GUARANTEE AGAINST DEFECTIVE WORK

Prior to final payment being made or before the release of the performance security required by Section 3 above, the Contractor and Surety shall execute and deliver to the County an original Maintenance Bond with an original signature and seal having a penal sum equal to:

A) One hundred percent (100%) of the final adjusted Contract amount, if such amount is \$50,000.00 or less;

G-9 Revised: 2016.12.13

- B) Fifty percent (50%) of the final adjusted Contract amount, if such amount be greater than \$50,000.00 but less than \$250,000.00; and,
- C) Twenty-five percent (25%) of the final adjusted contract amount, if such amount is \$250,000.00 or more.

The Bond and Surety shall be satisfactory to the Union County Counsel. The Surety shall hold a Certificate of Authorization to do business in the State of New Jersey and shall conform to P.L. 1995 c.384, codified as N.J.S.A. 2A:44-143, 144. The Surety Disclosure Statement and Certification required by N.J.S.A. 2A: 44-143, 144, shall be attached to the Bond. Such Maintenance Bond shall remain in full force and effect for a period of one (1) year from the date of Final Completion. Such Maintenance Bond shall also provide that the Contractor and the Surety guarantee to replace for the said period of one (1) year from the date of Final Completion, all Work performed and/or all materials furnished that were not performed or were not furnished in accordance to the terms and performance requirements of the Contract Documents, and will make good any defects thereof which become apparent before the expiration of one (1) year. If, during that period, any part of the Project, in the judgment of the Engineer, is found defective, the Contractor will repair or replace same within five (5) days of receipt of notice from the County Engineer. If the Contractor refuses or neglects to do such Work in the time specified, the County Engineer may have the Work done by others and the Contractor or his Surety thereof will pay the cost.

The Contractor will furnish the County a Maintenance Bond for a percentage of the final adjusted contract price, as stated above. The one (1) year period will start the day of Final Completion of Project by the County. Final payment is conditional on the receipt of a maintenance bond in a form acceptable to County Counsel.

16. TRAFFIC AND STREET MAINTENANCE

The Work must be started and performed by the Contractor in such a manner as to minimize delays to the traveling public. It must be completed in a timely fashion, with little or no inconvenience to traffic and pedestrians, where such inconvenience may be avoided.

All municipal, county, and state roadways shall remain open to traffic unless otherwise provided for in the technical specifications.

If modified traffic patterns are authorized in order to provide a safe working or traveling environment, the Contractor is responsible for providing all equipment, barrels, cones, signs, and barricades to implement the work zone and detours, unless otherwise specified in the technical specifications. All work zones and detours shall be established in accordance with the technical plans and specifications if provided or in strict compliance with the current version of the Manual for Uniform Traffic Control Devices (MUTCD). The Contractor shall obtain approval for these work zones and

detour plans from the Municipal Police or applicable police agency and the Union County Bureau of Traffic Maintenance prior to implementation.

All traffic control plans shall provide for safe movement of vehicular, bicycle, and pedestrian traffic. Particular attention shall be given to requirements of the Americans with Disabilities Act.

No portion of any street or alleyway may be used for the storage of any materials or equipment without the approval of the Municipal Police or other applicable police agency. Sidewalks, gutters, drains, fire hydrants and private drives shall be maintained for their intended use unless specifically approved by the County Engineer.

Upon suspension of Work, at the end of the day or for protracted periods, the Contractor shall remove all rubbish and materials from the Work site to the approved storage/staging location. All road cuts, saw cuts, and trenches that may pose hazard to vehicular, pedestrian, or bicycle traffic, to include handicapped users, shall be filled to the surface of the roadway or sidewalk. At no time will steel plates or settled trenches be allowed at the daily suspension of Work, unless specifically approved by the County Engineer.

Use of Traffic Control Officers shall be determined by the County in accordance with the provisions of N.J.S.A. 40A:11-23.1(c). If applicable to the Project, the County shall have provided an allowance for same as set forth in the Bid Form.

With respect to pedestrian traffic, the Contractor shall install signs restricting access of the general public and, as necessary, Union County employees to the area of construction. The Contractor shall provide safe access to required areas and place physical barriers to restricted areas. These barriers may range from caution tape to actual barriers, at the direction of the County Engineer.

17. CONTRACTOR'S EMPLOYEES

The Contractor must employ only suitable and competent labor in the Work, and must remove from the Work any incompetent, unsuitable, or disorderly person upon complaint from the County Engineer.

The parties to any contract resulting from this proposal do hereby agree that the provisions of N.J.S.A. 10:2-1 through 10:2-4 (discrimination in employment on public works contracts): 34:11-56.25 et seq. (payment of prevailing rate of wages determined pursuant to N.J.S.A. 34:11-56.30 by the Commissioner), and the Rules and Regulations promulgated pursuant thereto, are hereby made a part of any contract and are binding upon them.

There will be no discrimination against any employee who is employed in the Work to be covered by any contract resulting from this bid because of age, race, creed, color, national origin, ancestry, marital status or sex.

Any person, firm, or corporation violating the provisions of this Section will be deemed and judged a disorderly person.

18. OWNERSHIP DISCLOSURES REQUIRED

Pursuant to P.L. 1977, N.J.S.A. 52:25-24.2, the Bidder shall submit with its Bid, or prior to receipt of bids, a statement setting forth the names and addresses of all stockholders in the corporation or partnership bidding who own ten percent (10%) or greater interest therein. (See forms attached)

19. NON-COLLUSION AFFIDAVIT

The Bidder shall submit with its bid either the attached completed "Non-Collusion Affidavit" or a statement of non-collusion with verbiage similar to same.

20. EQUAL EMPLOYMENT OPPORTUNITY COMPLIANCES

The successful bidder shall be required to complete and submit an Initial Project Workforce Report, New Jersey Department of Treasury Form AA-201, upon notification of award. Failure to submit this completed form may result in the Contract being terminated.

The successful bidder shall also be required to submit a copy of its Monthly Project Workforce Report, New Jersey Department of Treasury Form AA-202, to the New Jersey Department of Treasury's Division of Public Contracts Equal Employment Opportunity Compliance and to the Board.

21. COMPLIANCE WITH NEW JERSEY PREVAILING WAGE ACT

The County of Union, in order to fulfill the requirements of N.J.S.A. 34:11-56a.25 et seq, requires that the following additional conditions be strictly followed. The bidders represent that he is not listed or is not on record in the Office of the Commissioner or the Department of Labor and Industry as one who failed to pay prevailing wages in accordance with the provisions of this Act. The bidder agrees to the inclusion of a contract provision upon award which specifically requires said Contractor to fully comply with each and all of the requirements of the aforesaid Act as it relates to prevailing rates of wages on public contracts as set forth in the New Jersey Prevailing Wage Act, P.L. 1963, Chapter 150 and P.L. 1974, Chapter 64.

A Copy of the Prevailing Wage Rates is attached for your reference. Applicable rates are those wages and fringe benefit rates in effect on the date the contract is awarded. All predetermined rate increases listed at the time the contract award must also be paid, beginning on the dates specified. Rates may change between the time of issuance of this determination and the award of the public works contract. Therefore, prior to the award of the contract, verification must be made with the Public Contracts section, to insure that the rates contained in this determination are still prevailing.

The Contractor agrees to abide and be bound by each and all of the said statutory provisions with respect to the payment of prevailing rates of wages, and acknowledges that the County reserves the right to terminate the Contractor's (or his subcontractors') right to proceed with the scope of Work, or such portion thereof that relates to the failure to pay prevailing rates of wages. In such event or under the terms of N.J.S.A. 34:11-56.27, the Contractor and his surety will be liable to the County of Union for any excess costs occasioned by such a violation.

The Contractor or subcontractors for this Project will post the Prevailing Wage Rates for each craft and classification involved as determined by the Commissioner of Labor and Industry, including the effective date of any changes thereof, in prominent and easily accessible places at the site of the Work or at such place or places as are used by them to pay workmen their wages.

The County of Union requires a copy of payroll records from the Contractor and subcontractors. Payroll records shall be submitted with each voucher request for payment. Prevailing wage rates may be obtained from the New Jersey Labor, Division of Workplace Standards, Public Contracts Section, (609-292-2259).

In addition to compliance with the New Jersey Prevailing Wage Act, the County requires compliance with procedures established by Resolution No. 2014-0408 adopted by the Union County Board of Chosen Freeholders on May 8, 2014. The resolution is furnished in Section 51 of these General Specifications.

UNION LABOR IS PREFERRED ON ALL COUNTY WORK

The foregoing reference to specific laws will not be deemed to be a limitation of obligation of the Contractor to perform his obligations in full compliance with the provisions and requirements of all federal and state statues and local ordinances applicable to the Work to be done under the contract.

It is agreed and understood that any contracts and/or orders placed as a result of this proposal will be governed and construed and the rights and obligations of the parties hereto will be determined in accordance with the laws of the State of New Jersey. Upon completion of the Work, the Contractor will furnish a Certification of Compliance with the New Jersey Prevailing Wage Act. The certificate in a form acceptable to County Counsel is a condition of the final payment. (See form attached)

22. BRAND NAME OR EQUAL

When the Specifications, Forms, and other Contract Documents use "brand name or equivalent" or similar language, the listed brand name shall serve as a reference or point of comparison for the functional or operational characteristic desired for the goods or services being requested. Where a bidder attempts to submit an equivalent product for a brand name, it shall be the responsibility of the bidder to fully describe and document the product to be provided with the bid in order to establish the equivalence claim.

- A. If the Bidder proposes to offer substitute goods as an equal to those specified herein, the bidder shall so indicate with the Bid Proposal. For the purposes of this paragraph, a proposed item shall be considered equal to goods specified herein if:
 - 1. The County, in its sole discretion, determines that: (i) the goods conform substantially, even with deviations, to the brand name goods specified herein; (ii) the goods are equal to or greater than the brand name goods specified herein in terms of quality, durability, functionality, appearance, strength and design; (iii) the goods are capable, at least as well as the brand name goods specified herein, or performing with existing equipment; and (iv) the goods do not cost the County more than the brand name goods specified herein costs the County.
- B. To offer substitute goods as an equal to those specified herein, it is necessary that:
 - The Bidder submits sufficient information with its bid to permit the County to determine that the goods are equivalent to the brand name goods specified herein, including, but not necessarily limited to the brand, catalog number and specifications/data sheets;
 - 2. The Bidder fully identifies and describes the variations of the goods from the brand name goods specified herein on a separate sheet that is to be submitted with the bid proposal. Bidder's literature WILL NOT suffice in explaining exceptions to these specifications.

G-14 Revised: 2016.12.13

- 3. The Bidder certifies that the goods (i) are similar in substance to the brand name goods specified, and (ii) are suited to the same use as the item specified;
- C. The County shall be allowed a reasonable time within which to evaluate the Bidder's proposal to offer substitute goods as an equal to those specified herein. The County shall be the sole judge of acceptability. No "or-equal" goods shall be ordered, delivered, assembled, set-up or utilized until the County's evaluation is complete. The County's determination as to equivalency shall be deemed final and absolute.

In the event the Bidder does not provide sufficient supporting documentation with the bid, it will be presumed and required that the brand name goods and services as described in the specifications will be provided.

23. LINES AND GRADES

Normally, horizontal and vertical control points will be provided in the technical specifications. All other surveying will be the responsibility of the Contractor unless otherwise noted.

24. NUMBER OF WORKING DAYS

In accordance with NJSA 40A:11-17, the Work for the within Project shall be completed as specified on the Time of Completion Form. See form attached

There shall be taken a deduction from the contract price, or any wages paid by the County, to any inspector(s) necessarily employed by it on the Work, for any number of days in excess of the number allowed in the specifications.

25. PROMPT PAYMENT OF CONSTRUCTION CONTRACTS (NJ Prompt Payment Act)

Pursuant to NJSA 2A:30A-1 et. seq., payment to the Contractor, other than for Work done pursuant to a contact allowance, where applicable, shall be processed and paid as follows:

1. All contractor bills shall be either approved for payment, or notice provided as to why the bill or any portion of it will not be approved by the representative(s) of the governing body no later than the public meeting following 20 calendar days of the billing date as defined in the statute.

G-15 Revised: 2016.12.13 2. If the billing is approved, said bill shall be paid in the payment cycle following the meeting.

26. STOPPING WORK ON ACCOUNT OF BAD WEATHER

Work must only be performed in weather suitable for the type of construction planned or underway. Extremes in temperature, humidity, precipitation, evaporation, etc. can detrimentally affect the constructed product. Refer to the Standard and Technical Specifications for specific items.

27. ACCESS FOR OTHER CONTRACTORS

The Contractor for this Work will give proper access to other contractors who may be employed upon the Project and must not hinder or delay unnecessarily any Work that may be progressing under other contracts.

28. CONDEMNED MATERIALS AND WORK

Any materials and or part of the Work that may be condemned by the County Engineer will be removed and replaced by the Contractor or otherwise rectified, as may be directed by the County Engineer. No payment will be made upon the Work until such faulty work has been made good as may be directed. In the event the Contractor refuses or neglects to make good such faulty work, he will be deemed to have abandoned the contract and proceedings may be taken against him as provided herein.

29. STORAGE

In the event that it is necessary for the Contractor to stockpile or store materials or equipment on the job site, the Contractor shall inform the County of such necessity and the County may offer available space, if any, for storage of such materials or equipment. The Contractor shall use said space only for such purpose. Any and all materials which may be stored in such space or which may be brought onto the job site at any time by the Contractor will be at the Contractor's sole risk. The County will not be responsible for loss of or damage to said materials or equipment for any cause whatsoever. The Contractor shall take necessary measures to protect any such storage area and shall be responsible for any and all damages.

30. FINAL CLEAN UP

Upon completion of the Work, the Contractor will remove all equipment, unused materials, rubbish, etc., and will repair, or replace in an a manner acceptable to the County Engineer, all areas that may have been damaged in the prosecution of the Work. Same shall be a condition precedent to final payment. Should said Contractor

fail to comply with this requirement, the County shall undertake the clean-up with its own forces and charge the cost of same against the Contractor's contract balance.

31. SUB-LETTING OF WORK

Except for the List of Subcontractors, pursuant to NJSA 40A:11-16 (See form attached), no portion of the Work will be sublet by the Contractor to any other entities, except with the consent of the County Engineer. A complete list of subcontractors must be submitted to the County Engineer at the preconstruction meeting. If the job does not warrant a preconstruction meeting, the Contractor must submit such list prior to the start of Work.

All Subcontractors will be subject to NJSA 34:11-56 et al.

N.J.S.A. 40A:11-16 requires the bidder to list in the bid sheets the name or names of all subcontractors involved in the following types of Work: plumbing and gas fitting and all kindred work, steam and hot water heating, ventilating apparatus, steam power plants and kindred work, electrical work, ornamental iron work, and structural steel. In addition, the County may require the identification of specific additional subcontractors. If these trades are expected to be part of the contract, such subcontractors should be listed on the "Subcontractor Identification Statement List of Subcontractors" and Bidder shall certify same on the accompanying sheet titled "Subcontractor Identification Certification". (See forms attached) **Bidder's failure to submit these two forms shall be considered a material defect and result in rejection of Bidder's bid.** Substitutions of any listed subcontractors pursuant to NJSA 40A:11-16 will not be permitted except with the consent of the County Engineer.

32. SAFETY

The Contractor shall observe all rules and regulations of the Federal, State, and local health officials. Attention is directed to Federal, State, and local laws, rules, and regulations concerning construction safety and health standards. The Contractor shall not require any worker to work in surroundings or under conditions that are unsanitary, hazardous, or dangerous to the worker's health or safety.

The Contractor shall admit to the site, without delay and without the presentation of an inspection warrant, any inspector of OSHA or other legally responsible agency involved in safety and health administration upon presentation of proper credentials.

The Contractor shall make available to the Contractor's employees, subcontractors, the County Engineer, and the public, all information pursuant to OSHA 29 CFR Part 1926.59 of The Hazard Communication Standard 29 CFR 1910.1200, and shall also maintain a file on each job site containing all Material Safety Data Sheets (MSDS) for products in use at the Project. These Material Safety Data Sheets shall be made available to the Engineer upon request.

The Contractor shall at all times conduct the Work to provide for the safety and convenience of the general public and protection of persons and property. The safety provisions of applicable laws, OSHA regulations, building and construction codes, and the rules and regulations of the New Jersey Department of Labor and Commerce shall be observed.

33. QUALITY, SAFETY AND PERFORMANCE STANDARDS

All goods and services must be constructed and provided with the highest quality materials and workmanship. It is the intent of these specifications that only equipment equal to, or exceeding, the standard specified will be acceptable in order to protect the safety of the occupants of the Building.

34. MATTERS NOT MENTIONED IN CONTRACT DOCUMENTS

Any Work, material, or method, not specifically described in these specifications, but shown upon the plans of the Work, will be carried out as shown on said plan.

35. PERMITS

The Contractor will obtain all necessary permits required by law and provide the County with necessary approvals prior to commencement of permitted Work.

36. CONTRACTOR TO PROVIDE PROOF OF PAYMENT

Upon the completion of the Work, the Contractor will furnish a General Release as proof that all claims for labor, materials, etc., have been settled by the Contractor. The General Release, in a form acceptable to County Counsel, is a condition of final payment.

37. CHANGE ORDERS

Change Order Procedures shall comply with *N.J.A.C.* 5:30-11.1 *et seq.*, "Change Orders and Open End Contracts" and subsequent provisions of the New Jersey Administrative Code.

38. SUPPLEMENTAL WORK

In case any supplemental work is necessary, it will be performed by the Contractor at a price fixed by agreement between the Contractor and the County Engineer and approved by the County as specified in Section 36. The Contractor will do no supplemental work on any character, for which the Contractor will demand pay, except upon the written order of the County.

39. FORM OF CONTRACT

The Contract will be subject to all statutory provisions on the matter of Public Works, Public Contracts, The Law Against Discrimination, the Laws Governing Affirmative Action and Prevailing Rates of Wages under the laws of New Jersey.

The Agreements shall be executed by both parties not later than twenty-one (21) days from the date of the award by the County (Sundays and holidays excluded); however, such time frame may be extended by agreement of the parties.

40. PROGRESS PAYMENTS

Monthly progress payments will be made based on the value of labor and materials incorporated in the Work and of materials suitably stored at the site. An itemized schedule of values shall be submitted with each Application for Payment.

(Refer to the Owner/Contractor Agreement for Retainage and other conditions pertaining to payment and the application of NJSA 2A:30A-1 et. seq.)

All Applications for Payment shall be accompanied by paid invoices for materials incorporated in the Work and for materials suitably stored at the site, and affidavit(s) by Subcontractors whose Work was included in the next to the last application to the effect such Work and such materials have been paid for.

No payment shall be made without Contractor having provided all submittals set forth in this Section, and the approval of same by the County.

For contracts exceeding \$100,000.00, monthly payments will be made on the Work to the extent of 98% of the value of the Work done which is considered to be retainage.

For contracts less than \$100,000.00, monthly payments will be on the Work to the extent of 90% of the value of the Work done. In lieu of the retainage, the Contractor will, at his option, deposit with the County Counsel negotiable bearer bonds of the State of New Jersey or any political subdivision thereof, equal to the amount otherwise withheld as retainage.

When the Project is completed, the final cost of the Project will be based on actual quantities of authorized Work done under each item scheduled in the bidding sheet and approved Change Orders, if any. The money due to the Contractor as determined by said final certificate after deduction of previous monthly payments on account, will be paid to the Contractor in accordance with the terms of the contract dealing with Prompt Payment, providing, however that before such final payment is made, all outstanding claims against the Contractor must be satisfied. Before final

payment is released, the Contractor must furnish: a) Maintenance Bond (see Section 6 of these general specifications); b) Certification of Compliance, New Jersey Prevailing Wage Act (see Sections 21 and 51); and c) General Release (see Section 36) in a form satisfactory to County Counsel; d) complete set of as-built plans in the latest AutoCad on compact disc; and e) a complete set of in-progress photos in jpg, jpeg, or bmp digital format on a compact disc.

41. INSPECTION

The Work must be done in accordance with the plans and specifications, and will be inspected by the County Engineer. An inspector may be placed upon the Work at any time by the County Engineer to see that the plans, specifications, and instructions of the County Engineer are carried out. In connection herewith, bidders are referred to N.J.S.A. 40A:11-17.

42. DAMAGES

The Contractor will be held responsible for all damages that may occur to Work, or to persons or property by reason of the nature of the Work or from the elements, or by reason of inadequate protection of the Work, or from any carelessness or negligence on his part or on the part of his employees. The County will withhold payments on the Work until all suits or claims for damages sustained on, or by reason of, this Work will have been settled by the Contractor.

The construction and final completion of this Work will be guaranteed by the Contractor. Any damages that may be done to the Work or any part thereof, by the elements or otherwise, during its construction, will be made good by the Contractor.

43. LIQUIDATED DAMAGES

If the Project is not completed within the time specified herein or within such further time as may have been granted by the County Engineer, then the Contractor hereby agrees to pay to the County as liquidated damages, but not as a penalty, \$1,000.00 per day for each and every calendar day that he is in default on time to complete the Work. The said sum will be deducted from moneys due the Contractor and if the damages exceed this amount, then the Contractor or his Surety Company will pay the excess. These damages may be waived at the option of the County.

44. AFFIRMATIVE ACTION REQUIREMENTS

EXHIBIT B (Revised 4/10)

MANDATORY EQUAL EMPLOYMENT OPPORTUNITY LANGUAGE N.J.S.A. 10:5-31 et seq. (P.L. 1975, C. 127) N.J.A.C. 17:27

CONSTRUCTION CONTRACTS

During the performance of this contract, the contractor agrees as follows:

The contractor or subcontractor, where applicable, will not discriminate against any employee or applicant for employment because of age, race, creed, color, national origin, ancestry, marital status, affectional or sexual orientation, gender identity or expression, disability, nationality or sex. Except with respect to affectional or sexual orientation and gender identity or expression, the contractor will ensure that equal employment opportunity is afforded to such applicants in recruitment and employment, and that employees are treated during employment, without regard to their age, race, creed, color, national origin, ancestry, marital status, affectional or sexual orientation, gender identity or expression, disability, nationality or sex. Such equal employment opportunity shall include, but not be limited to the following: employment, up-grading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship. The contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided by the Public Agency Compliance Officer setting forth provisions of this nondiscrimination clause.

The contractor or subcontractor, where applicable will, in all solicitations or advertisements for employees placed by or on behalf of the contractor, state that all qualified applicants will receive consideration for employment without regard to age, race, creed, color, national origin, ancestry, marital status, affectional or sexual orientation, gender identity or expression, disability, nationality or sex.

The contractor or subcontractor will send to each labor union, with which it has a collective bargaining agreement, a notice, to be provided by the agency contracting officer, advising the labor union or workers' representative of the contractor's commitments under this act and shall post copies of the notice in conspicuous places available to employees and applicants for employment.

The contractor or subcontractor, where applicable, agrees to comply with any regulations promulgated by the Treasurer, pursuant to N.J.S.A. 10:5-31 et seq., as amended and supplemented from time to time and the Americans with Disabilities Act.

When hiring or scheduling workers in each construction trade, the contractor or subcontractor agrees to make good faith efforts to employ minority and women workers in each construction trade consistent with the targeted employment goal prescribed by N.J.A.C. I7:27-7.2; provided, however, that the Division may, in its discretion, exempt a contractor or subcontractor from

Revised: 2016.12.13

compliance with the good faith procedures prescribed by the following provisions, A, B and C, as long as the Division is satisfied that the contractor or subcontractor is employing workers provided by a union which provides evidence, in accordance with standards prescribed by the Division, that its percentage of active "card carrying" members who are minority and women workers is equal to or greater than the targeted employment goal established in accordance with N.J.A.C. I7:27-7.2. The contractor or subcontractor agrees that a good faith effort shall include compliance with the following procedures:

- If the contractor or subcontractor has a referral agreement or arrangement with a union for a construction trade, the contractor or subcontractor shall, within three business days of the contract award, seek assurances from the union that it will cooperate with the contractor or subcontractor as it fulfills its affirmative action obligations under this contract and in accordance with the rules promulgated by the Treasurer pursuant to N.J.S.A. 10:5-31 et. seg., as supplemented and amended from time to time and the Americans with Disabilities Act. If the contractor or subcontractor is unable to obtain said assurances from the construction trade union at least five business days prior to the commencement of construction work, the contractor or subcontractor agrees to afford equal employment opportunities minority and women workers directly, consistent with this chapter. If the contractor's or subcontractor's prior experience with a construction trade union, regardless of whether the union has provided said assurances, indicates a significant possibility that the trade union will not refer sufficient minority and women workers consistent with affording equal employment opportunities as specified in this chapter, the contractor or subcontractor agrees to be prepared to provide such opportunities to minority and women workers directly, consistent with this chapter, by complying with the hiring or scheduling procedures prescribed under (B) below; and the contractor or subcontractor further agrees to take said action immediately if it determines that the union is not referring minority and women workers consistent with the equal employment opportunity goals set forth in this chapter.
- (B) If good faith efforts to meet targeted employment goals have not or cannot be met for each construction trade by adhering to the procedures of (A) above, or if the contractor does not have a referral agreement or arrangement with a union for a construction trade, the contractor or subcontractor agrees to take the following actions:
- (I) To notify the public agency compliance officer, the Division, and minority and women referral organizations listed by the Division pursuant to N.J.A.C. 17:27-5.3, of its workforce needs, and request referral of minority and women workers;
- (2) To notify any minority and women workers who have been listed with it as awaiting available vacancies;
- (3) Prior to commencement of work, to request that the local construction trade union refer minority and women workers to fill job openings, provided the contractor or subcontractor has a referral agreement or arrangement with a union for the construction trade;
- (4) To leave standing requests for additional referral to minority and women workers with the local construction trade union, provided the contractor or subcontractor has a referral agreement or arrangement with a union for the construction trade, the State Training and Employment Service and other approved referral sources in the area;

- (5) If it is necessary to lay off some of the workers in a given trade on the construction site, layoffs shall be conducted in compliance with the equal employment opportunity and non-discrimination standards set forth in this regulation, as well as with applicable Federal and State court decisions;
- (6) To adhere to the following procedure when minority and women workers apply or are referred to the contractor or subcontractor:
- (i) The contactor or subcontractor shall interview the referred minority or women worker.
- (ii) If said individuals have never previously received any document or certification signifying a level of qualification lower than that required in order to perform the work of the construction trade, the contractor or subcontractor shall in good faith determine the qualifications of such individuals. The contractor or subcontractor shall hire or schedule those individuals who satisfy appropriate qualification standards in conformity with the equal employment opportunity and non-discrimination principles set forth in this chapter. However, a contractor or subcontractor shall determine that the individual at least possesses the requisite skills, and experience recognized by a union, apprentice program or a referral agency, provided the referral agency is acceptable to the Division. If necessary, the contractor or subcontractor shall hire or schedule minority and women workers who qualify as trainees pursuant to these rules. All of the requirements, however, are limited by the provisions of (C) below.
- (iii) The name of any interested women or minority individual shall be maintained on a waiting list, and shall be considered for employment as described in (i) above, whenever vacancies occur. At the request of the Division, the contractor or subcontractor shall provide evidence of its good faith efforts to employ women and minorities from the list to fill vacancies.
- (iv) If, for any reason, said contractor or subcontractor determines that a minority individual or a woman is not qualified or if the individual qualifies as an advanced trainee or apprentice, the contractor or subcontractor shall inform the individual in writing of the reasons for the determination, maintain a copy of the determination in its files, and send a copy to the public agency compliance officer and to the Division.
- (7) To keep a complete and accurate record of all requests made for the referral of workers in any trade covered by the contract, on forms made available by the Division and submitted promptly to the Division upon request.
- (C) The contractor or subcontractor agrees that nothing contained in (B) above shall preclude the contractor or subcontractor from complying with the union hiring hall or apprenticeship policies in any applicable collective bargaining agreement or union hiring hall arrangement, and, where required by custom or agreement, it shall send journeymen and trainees to the union for referral, or to the apprenticeship program for admission, pursuant to such agreement or arrangement. However, where the practices of a union or apprenticeship program will result in the exclusion of minorities and women or the failure to refer minorities and women consistent with the targeted county employment goal, the contractor or subcontractor shall consider for employment persons referred pursuant to (B) above without regard to such agreement or arrangement; provided further, however, that the contractor or subcontractor shall

not be required to employ women and minority advanced trainees and trainees in numbers which result in the employment of advanced trainees and trainees as a percentage of the total workforce for the construction trade, which percentage significantly exceeds the apprentice to journey worker ratio specified in the applicable collective bargaining agreement, or in the absence of a collective bargaining agreement, exceeds the ratio established by practice in the area for said construction trade. Also, the contractor or subcontractor agrees that, in implementing the procedures of (B) above, it shall, where applicable, employ minority and women workers residing within the geographical jurisdiction of the union.

After notification of award, but prior to signing a construction contract, the contractor shall submit to the public agency compliance officer and the Division an initial project workforce report (Form AA 201) electronically provided to the public agency by the Division, through its website, for distribution to and completion by the contractor, in accordance with N.J.A.C. 17:27-7. The contractor also agrees to submit a copy of the Monthly Project Workforce Report once a month thereafter for the duration of this contract to the Division and to the public agency compliance officer.

The contractor agrees to cooperate with the public agency in the payment of budgeted funds, as is necessary, for on-the-job and/or off-the-job programs for outreach and training of minorities and women.

(D) The contractor and its subcontractors shall furnish such reports or other documents to the Division of Public Contracts Equal Employment Opportunity Compliance as may be requested by the Division from time to time in order to carry out the purposes of these regulations, and public agencies shall furnish such information as may be requested by the Division of Public Contracts Equal Employment Opportunity Compliance for conducting a compliance investigation pursuant to Subchapter IO of the Administrative Code (NJAC 17:27).

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

45. INVESTMENT ACTIVITIES IN IRAN

Pursuant to P.L. 2012, c.25, codified as NJSA 2:32-55 *et seq*, prohibits State and local public contracts with persons or entities engaging in certain investment activities in energy or finance sectors of Iran.

46. COMPLIANCE WITH THE PUBLIC WORKS CONTRACTOR REGISTRATION ACT - (NJSA 34:11-56.48 et. seq.)

Pursuant to the above-referenced law, Bidders are required to be registered with the New Jersey Department of Labor and to possess a current certificate by said Department indicating compliance with the Act prior to the time and date that bids are received. Bidders are notified of this requirement of their compliance. Such certificates or applications shall also be provided for each Subcontractor furnishing plumbing and gas fitting, steam and hot water heating and ventilating apparatus, and all kindred work, steam power plants and kindred work, electrical work, structural steel and ornamental iron work, and such other subcontractors as the specifications require relative to prior identification.

47. UTILITIES

Attention of the bidder is directed to the fact that the approximate locations of known utility structures and facilities that may be encountered within and adjacent to the limits of the Work are shown on the plans and described herein. The accuracy and completeness of this information is not guaranteed by the County Engineer and the bidder is advised to ascertain for himself all the facts concerning the location of these and other utilities.

The Contractor will not proceed with his Work until he has made diligent inquiries of all public utility and municipal officials to determine the exact location of all-underground structures and pipes within the site of the Project. The Contractor will notify utility owners not less than ten (10) days in advance of the time he proposes to perform any Work that will endanger or affect their facilities in compliance with **New Jersey One-Call.** In excavating in any part of the Work, care must be taken not to remove or damage any gas, water, sewer, or other pipe, conduit, or structure, - public or private - without the concurrence of the owner and the County Engineer. The Contractor will, at his own expense, shore up, secure and maintain a continuous flow in such structures, and will keep them in repair until final acceptance of the Work.

When pipes or other structures are encountered or when the removal, relocation or protection of these utilities are necessary in carrying out the Project as planned, the Contractor will cooperate with the owner of said utilities and will permit the owners or their agents access to the site of the Work in order to relocate or protect their facilities

G-25 Revised: 2016.12.13 and not hinder or delay unnecessarily the Work of the owners in moving same. No extra allowance of payment will be made to the Contractor for the use of any materials, equipment, etc., or for the performance of any Work in connection with the moving of said structures unless the Contractor is specifically ordered by the County Engineer to furnish such materials, equipment, or services. If directed by the County Engineer to do any Work or furnish any materials or equipment, payment will be allowed the Contractor in accordance with the unit prices bid for such Work, or, if such items are not scheduled in the proposal, such Work shall be allowed "Supplemental Work" as provided in Section 39 of these general specifications. The corporations, companies, agencies or municipalities owning or controlling the utilities, and the name, and telephone numbers are listed in the beginning of the Technical Specifications.

48. MATERIAL COMPLIANCE AND SHOP DRAWINGS

The Contractor will require the manufacturer or supplier to furnish three (3) copies of Certification of Compliance with each delivery of materials, components and manufactured items for the Project. Two (2) copies will be furnished to the County Engineer; one copy will be retained by the Contractor. Certificates of Compliance will contain the following information:

- 1. Project to which material is consigned;
- 2. Name of the Contractor to which the material is supplied;
- 3. Kind of material supplied;
- 4. Quantity of material represented by the Certificate;
- 5. Means of identifying the consignment, such as label marking, seal number, etc.;
- 6. Date and method of shipment;
- 7. That the material is in conformity with the pertinent specifications stated in the certificate; and
- 8. Signature of a person having legal authority to bind the supplier.

The Contractor will submit to the County Engineer for his approval five (5) copies of complete and fully detailed shop or working drawings for those items listed in the beginning of the technical specifications.

Each drawing will identify the name of the job, location and Contractor.

All drawings will be approved in accordance with the standard specifications. Refer to the Technical Specifications for specific items.

All materials or articles used in the Work will be of American manufacture, insofar as same are available, in conformance with N.J.S.A. 40A:11-18.

49. PRECONSTRUCTION

In order to provide full coordination of this Project among the parties concerned, the County Engineer will arrange for a preconstruction meeting between the Contractor, County Engineer and other interested parties as soon as possible after the contract is executed. At this meeting the Contractor will present his proposed schedule of Work which shall be subject to review and approval of the County through its designated representatives.

50. DISPUTES UNDER THE CONTRACT

A dispute arising under the Contract shall be submitted in writing to the County Engineer with all facts and supporting data. The County Engineer will review the dispute and issue his decision or request additional facts or documentation after which he will render his decision.

In the event the dispute is not then resolved, the matter shall, pursuant to law, be submitted to mediation before being submitted to a court of competent jurisdiction venued in Union County.

The County Engineer will notify the County Counsel when a matter is to be submitted to mediation. The County Counsel will communicate with the parties and inform them of the procedures to be followed in making such a submission.

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

51. CONTRACTOR BUSINESS REGISTRATION CERTIFICATE New Mandatory Requirement -Effective 1/18/2010

The recently enacted **P.L. 2009, c.315**, requires that effective January 18, 2010; a contracting agency must receive proof of the bidder's business registration prior to the award of a contract. However, the proof must show that the bidder was in fact registered with the State of New Jersey Department of the Treasury, Division of Revenue and obtained the business registration prior to the receipt of bids.

If subcontractors are named on the bid, proof of the business registration for each subcontractor must be provided prior to the award of bid. Similarly to the bidder, the proof must show that each subcontractor was registered with the State of New Jersey Department of the Treasury, Division of Revenue and obtained the business registration prior to the receipt of bids.

Proof of business registration shall be ☐ A copy of a Business Registration Certificate issued by the Department of the Treasury, Division of Revenue; or ☐ A copy of the web version provided by the NJ Division of Revenue, or
Register online at http://www.state.nj.us/treasury/revenue/busregcert.htm . Click the "online" link and then select "Register for Tax and Employer Purposes or call the Division at 609-292-1730.

Note: A NJ Certificate of Authority is <u>not</u> acceptable.

FAILURE to submit proof of registration of the bidder or any subcontractor named on the bid prior to the award of contract shall be cause to reject the bid.

FAILURE of the bidder or any subcontractor named on the bid to be <u>registered</u> prior to the receipt of bids is cause for a **MANDATORY REJECTION** of bids. (A NON-WAIVABLE DEFECT). This covers construction Work as well as non-construction bids.

IN ADDITION:

N.J.S.A. 52:32-44 imposes the following requirements on Contractors and all subcontractors that knowingly provide goods or perform services for a Contractor fulfilling this contract:

- 1) the Contractor shall provide written notice to its subcontractors and suppliers to submit proof of business registration to the Contractor;
- 2) subcontractors through all tiers of a project must provide written notice to their subcontractors and suppliers to submit proof of business registration and subcontractors shall collect such proofs of business registration and maintain them on file:

- 3) prior to receipt of final payment from a contracting agency, the Contractor must submit to the contacting agency an accurate list of all subcontractors and suppliers or attest that none was used; and,
- 4) during the term of this contract, the Contractor and its affiliates shall collect and remit, and shall notify all subcontractors and their affiliates that they must collect and remit, to the Director, New Jersey Division of Taxation, the use tax due pursuant to the Sales and Use Tax Act, (*N.J.S.A.* 54:32B-1 *et seq.*) on all sales of tangible personal property delivered into this State.

A Contractor, subcontractor or supplier who fails to provide proof of business registration or provides false business registration information shall be liable to a penalty of \$25 for each day of violation, not to exceed \$50,000 for each business registration copy not properly provided or maintained under a contract with a contracting agency. Information on the law and its requirements are available by calling (609) 292-9292.

[REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]

G-29 Revised: 2016.12.13

52. BID PROTEST – LEGAL FEES AND COSTS

In the event a Bidder unsuccessfully challenges a Bid Submission by filing an action in a court of law concerning same, said Bidder shall be responsible for payment of reasonable legal costs and fees incurred by the County relating to said protest.

53. AMERICAN GOODS AND PRODUCTS WHERE POSSIBLE

Bidder shall comply with the requirements of NJSA 40A:11-18 and use only manufactured and farm products of the United States, wherever available, for the Project.

54. NEW JERSEY PAY-TO-PLAY REQUIREMENTS

This Contract is required by law to be publicly advertised for bids. As such, lists of political contributions pursuant to NJSA 19A:44A-1 et. seq. are NOT REQUIRED to be provided with the bids.

55. STATEMENT OF EQUIPMENT TO BE USED IN CONSTRUCTION

Pursuant to NJSA 40A:11-20 entitled Certificate of Bidder Showing Ability to Perform Contract, the County requires a Certification from all bidders submitting a bid showing that the Bidder owns, leases, or controls all necessary equipment required by the Project Plans and Specifications. All bidders shall provide this information at the time of the bid opening using the attached form entitled, "CERTIFICATE OF BIDDER SHOWING ABILITY TO PERFORM CONTRACT".

If the Bidder is not the actual owner of the equipment, it shall state the source from which the equipment will be obtained and shall attach a certificate from the owner or person in control of the equipment demonstrating that the equipment owner has granted the Bidder control of the requisite equipment during such time as may be necessary for completion of the portion of the contract for which the equipment is necessary.

56. NEW JERSEY SALES AND USE TAX REQUIREMENTS,

Contractors are required to comply with the following:

New Jersey Sales and Use Tax Requirements: All contractors with subcontractors, or any of their affiliates, who enter into contracts for the provision of goods or services with or for New Jersey local government entities, are required to collect and remit to the New Jersey Director of Taxation in the Department of the Treasury the use tax due on all of their sales of tangible personal property delivered into the State of New Jersey pursuant to the "Sales and Use Tax Act," (NJSA 54:32B-1 et, seq.),

G-30 Revised: 2016.12.13 regardless of whether the tangible personal property is intended for a contract with the contracting agency. This tax shall be remitted for the term of the Contract.

For purposes herein "affiliate" shall mean any entity that: (a) directly, indirectly, or constructively controls another entity, (b) is directly, indirectly, or constructively controlled by another entity, or (c) is subject to the control of a common entity. For purposes of the immediately preceding sentence, an entity controls another entity if it owns, directly or indirectly, more than fifty percent (50%) of the ownership interest in that entity. NJSA 52:32-44(g)(3).

LAURA M. SCUTARI, QPA, MPA DIRECTOR / DIVISION OF PURCHASING

BID DOCUMENT SUBMISSION CHECKLIST

ALL SIGNATURES AND SEALS SHALL BE ORIGINALS UNLESS OTHERWISE SPECIFIED BID SHEETS SHOULD NOT BE SUBMITED DOUBLE SIDED PAGES, (SINGLE SIDE ONLY)

	BIDDER SHOULD COMPLETE THIS FORM AND INITIAL EACH ENTRY. COMPLETED:			
PLEASE SUBMIT BID DOCUMENTS ON SINGLE SIDED PAPER ONLY, WITH THE EXCEPTION OF THE SURETY AND BID BOND DOCUMENTS.				
IN ACCORDANCE WITH THE BID SPECIFICATIONS I HAVE REVIEWED, COMPLETED / EXECUTED AND INCLUDED THE FOLLOWING FORMS:				
	Bid Form Page (Signed, Dated and Bid on all alternatives applicable to the Work).			
	Security in the form of: Bid bond in an amount equal to 10% of the total amount of this bid not to exceed \$20,000.00; or Certified check or cashier's check in the amount of 10% of this bid not to exceed \$20,000.00			
	Consent of Surety form signed by a Surety Company if the total amount of your Bid is over \$36,000.00. If your bid is accepted, the Surety Company that provided the Consent shall be required to furnish a Performance, Labor and Materials Bond in the amount of 100% of the award of the contract. The County of Union has provided its Consent of Surety form for your use. The use of this form by your Surety Company will expedite the bid review process and eliminate the possibility of having your bid rejected. If, however, you should need to use another form, please use language similar to that used or the Union County form and avoid making any additions or deletions to the Union County form language. In lieu of the Consent of Surety you may submit a Certified Check in the full amount of the bid.			
	STATEMENT OF BIDDER OWNERSHIP. Pursuant to N.J.S.A. 52:25-24.2, which includes BOTH of the following documents:			
	 Bidder Signature Page Bidder Disclosure Statement (Fill out 2 pages completely) 			
	SUBCONTRACTOR IDENTIFICATION. Pursuant to N.J.S.A. 40A:11-16, which includes BOTH of the following documents:			
	 Subcontractor Identification Statement: List of Subcontractors (only for certain types of work) Subcontractor Identification Certification 			
	Acknowledgement of Addendum form: (This form is to be used only when an addendum has been added to the specifications).			
	A copy of the State of New Jersey Department of the Treasury, Division of Revenue, Business Registration Certificate ("BRC") should be included with the bids as it must be received by the County prior to the award of the contract. The BRC provided <u>must show</u> that the Bidder was registered at the time of receipt of bids or the bid will be rejected.			
	A copy of the State of New Jersey Department of the Treasury, Division of Revenue, Business Registration Certificate ("BRC") of all named or listed subcontractors (List of Subcontractors) in a Construction bid should be included with the bid as the BRC(s) must be received by the County prior to the award of the contract. Each subcontractor's certificate provided <u>must show</u> that the subcontractor was registered at the time of the receipt of bids or the bid will be rejected.			

	_ Affirmative Action Requirement
	Experience Statement
	Certificate of Bidder showing ability to perform Contract
	Non-Collusion Affidavit – Fill out completely and notarize
	Certificates from New Jersey Department of Labor – Public Works Contractor Registration Act. (Only for certain types of work)
	Federal Attachments (If applicable)
	NJDPMC Certificate / Notice of Classification (If applicable)
	Americans with Disabilities Act
	Statement of Bidder's Qualifications
	Contractor Performance Record
	Affidavit Regarding List of Debarred, Suspended or Disqualified Bidders
	Prior Negative Experience Questionnaire
	Contractor's Certification of Compliance – New Jersey Prevailing Wage Act
	Uncompleted Contracts Affidavit (For Bidder, if applicable) MUST ALSO PROVIDE DPMC FORM 701
	Certificate of Insurance Statement
	Collection of Use Tax on Sales to Local Government Statement
	Time of Completion
	Disclosure of Investment Activities in Iran form
I HAV	E TAKEN THE FOLLOWING ACTIONS:
	Visited the site and attended the Pre-Bid Meeting (Where applicable)
	Reviewed the Contract Documents (including any permits the County or its professionals may have obtained), Work, Site, Locality, and Local Conditions and Laws and Regulations that in any manner may affect Cost, Progress, Performance or Furnishing of Work.
	Reviewed Bond Requirements
	Provided Proof of Compliance with New Jersey Prevailing Wage Act
	Reviewed Form of Owner/Contractor Agreement and General Conditions to the Contract

NOTE: QUESTIONS PERTAINING TO THIS BID ARE TO BE DIRECTED TO DIVISION OF ENGINEERING AT 908-789-3675

BIDDING DOCUMENTS

The Bidding Documents consist of the following items:

- ADDENDA, if issued
- CLARIFICATIONS, if issued
- INSTRUCTION TO BIDDERS
- BID FORM
- SPECIFCATIONS: As outlined in the Table of Contents and included in the Project Manual.
- DRAWINGS:
 As per List of Drawings, indicated on the Project Title Sheet.

Bidder's Name

BID FORM

I/We have carefully examined the plans, specifications, and advertisement for bid for the

REBID: SENSORY TRAIL IMPROVEMENTS WATCHUNG RESERVATION BOROUGH OF MOUNTAINSIDE, COUNTY OF UNION, NEW JERSEY BA#5-2017; UNION COUNTY ENGINEERING PROJECT #2016-006

that is on file in the Union County Division of Engineering. I/We have inspected the site of the work and will contract to do all the work and furnish all materials mentioned in said plans and specifications. Work will be accomplished in the manner prescribed therein.

BASE BID ITEMS:

ITEM NO	DESCRIPTION	UNIT	CONTRACT QUANTITY	UNIT PRICE	AMOUNT
1	Clearing and Preparation of Site, Mobilization and Demobilization	LS	1		
2	Earthwork and Subgrade Preparation, including all Cuts, Fills, Import Fill (if required), Compaction, Grading, Removal of Excess/Unsuitable Soils, and all Incidental Work	LS	1		
3	Excavate Existing Walkway to be Removed, 2" Thick, Topsoil, Lime, Fertilize and Seed	SY	785		
4	Root Prune (if and where directed)	ALLOW	1	\$2,500.00	\$2,500.00
5	Excavate, 4" Thick, Compact Subgrade, and Construct Stone Dust Walkway, 4" Thick, including Filter Fabric	SY	1,350		
6	Talking Informational Sensory Kiosk, including Concrete Foundations	UN	2		
7	Stepping Stones (to match existing)	LS	1		
8	Rest Flag Pole and Conduit (for future lighting)	LS	1		
9	Trash and Recycling Receptacle, including Concrete Foundations	PR	2		
10	Stone Veneer Seat Wall, 21" High, including Concrete Footing	LF	85		
11	Concrete Paver Patio, including sub-base	SY	395		
12	Concrete Paver Walkway, including sub-base	SY	190		
13	Timber Boardwalk, including Vertical Posts and Concrete Foundations	SF	1,145		
14	Galvanized Steel Handrail, including Vertical Posts and Concrete Foundations	LF	260		
15	Galvanized Steel Handrail	LF	360		

16	Concrete Depressed Curb	LF	710	
17	Engineered Wood Fiber Safety	SF	2,510	
	Mulch, 6" Thick			
18	Raised Garden Planter	UN	3	
19	Gazebo, 30' Wide, including	UN	1	
	Concrete Foundations			
20	Chitter-Chatter Noodle, including	PR	1	
	Concrete Foundations			
21	Sensory Play Center, including	UN	1	
	Concrete Foundations			
22	Log Crawl Tunnel, including	UN	1	
	Concrete Foundations			
23	Log Balance Beam, including	UN	2	
	Concrete Foundations			
24	Log Stepper, including Concrete	UN	4	
	Foundations			
25	Mushroom Stepper, including	UN	3	
	Concrete Foundations			
26	Goblet Drum, including Concrete	UN	1	
	Foundation			
27	Kundo Drum, including Concrete	UN	1	
	Foundation			
28	Kettle Drum, including Concrete	UN	1	
	Foundation			
29	Vivo Metallophone, including	UN	1	
	Concrete Foundation			
30	Log Bench, 6' Long, including	UN	10	
	Concrete Foundations			
31	Acorn Seat, including Concrete	UN	8	
	Foundations			
32	Decorative Table, including	UN	2	
	Concrete Foundations			
33	Fire Pit Kit, including sub-base	UN	1	
34	Fire Wood Storage Rack with	UN	1	
	Cover, including 4" Thick Concrete			
	Pad			
35	Sugar Maple, 2" – 2 ½" caliper (if	UN	1	
	and where ordered)			
36	Golden Rain Tree, 7' – 8' height (if	UN	1	
	and where ordered)			
37	Forest Pansy Eastern Redbud, 7' –	UN	1	
	8' height (if and where ordered)			
38	Cherokee Brave Dogwood, 7' – 8'	UN	5	
	height (if and where ordered)			
39	Pink Chimes Japanese Snowbell, 7'	UN	1	
	 – 8' height (if and where ordered) 	1		
40	Goldilocks Hinoki False Cypress, 8'	UN	1	
	- 10' height (if and where ordered)			
41	Blue Colorado Spruce, 8' – 10'	UN	2	
	height (if and where ordered)			
42	Green Giant Arborvitae, 8' – 10'	UN	3	
	height (if and where ordered)	1		
43	Lo & Behold Ice Chip Butterfly	UN	8	
	Bush, 12" – 18" height (if and where			
	ordered)			

		T	T _		1
44	Ruby Spice Summersweet, 24" –	UN	3		
	30" height (if and where ordered)				
45	Sunshine Blue Bluebeard, 18" – 24"	UN	3		
40	height (if and where ordered)	1181	3		
46	Blue Mist Dwarf Fothergilla, 18" –	UN	3		
47	24" height (if and where ordered)	1181	05		
47	Hoogendorn Japanese Holly, 18" –	UN	25		
40	24" height (if and where ordered)	LINI	3		
48	Henry's Garnet Virginia Sweetspire,	UN	3		
	24" – 30" height (if and where ordered)				
49	,	UN	3		
49	Gold Star Juniper, 24" – 30" spread (if and where ordered)	UN	3		
50	Bird's Nest Spruce, 18" – 24" height	UN	6		
50		UN	0		
E4	(if and where ordered)	LINI	4		
51	Summer Wine Ninebark, 24" – 30"	UN	1		
F0	height (if and where ordered)	1181	44		
52	Anthony Waterer Spirea, 18" – 24"	UN	11		
F0	height (if and where ordered)	1181			
53	Bloomerang Purple Lilac, 24" – 30"	UN	1		
F4	height (if and where ordered)				
54	Compact Koreanspice Virburnum,	UN	3		
	24" – 30" height (if and where				
	ordered)		_		
55	Common Milkweed, 2 gallon (if and	UN	5		
	where ordered)				
56	Pink Grapefruit Yarrow, 2 gallon (if	UN	4		
	and where ordered)	1181	40		
57	Overdam Feather Reed Grass, 2	UN	18		
58	gallon (if and where ordered)	UN	12		
58	Zagreb Tickseed, 2 gallon (if and where ordered)	UN	12		
59	Magnus Purple Coneflower, 2	UN	8		
59	gallon (if and where ordered)	UN	0		
60	Hidcote English Lavender, 2 gallon	UN	8		
60	(if and where ordered)	UN	0		
61	Morning Light Maiden Grass, 2	UN	4		
01		UN	4		
62	gallon (if and where ordered) Walker's Low Catmint, 2 gallon (if	UN	19		
02	and where ordered)	UN	19		
63	Hameln Dwarf Fountain Grass, 2	UN	29		
03	gallon (if and where ordered)	ON	29		
64	Karley Rose Oriental Fountain	UN	7		
04	Grass, 2 gallon (if and where	UN	'		
	ordered)				
65	Russian Sage, 2 gallon (if and	UN	12		
0.5	where ordered)	0.14	'-		
66	Northwind Switchgrass, 2 gallon (if	UN	6		
00	and where ordered)	5.1	~		
67	Alexandra Garden Phlox, 2 gallon (if	UN	4		
J.	and where ordered)	0.1	- f		
68	Goldsturm Black-Eyed Susan, 2	UN	8		
30	gallon (if and where ordered)	0.1			
69	May Night Garden Sage, 2 gallon (if	UN	6		
	and where ordered)	0.1			
<u> </u>		l	l	I	1

70	Carousel Little Bluestem, 2 gallon (if and where ordered)	UN	3	
71	Helene Von Stein Lamb's Ear, 2 gallon (if and where ordered)	UN	11	

TOTAL BASE BID ITEMS NO. 1 THRU 71:	
Written	Figures
BID CONTINGENCY: (To be used if and when directed by the Count	ty)
FIFTY THOUSAND DOLLARS AND NO CENTS Written	\$50,000.00 Figures
TOTAL BASE BID ITEMS NO. 1 THROUGH 71 PLUS BID CONTINGEI	NCY AMOUNT:
Written	Figures

ALTERNATES:

Alternates may be added to the Total Base Bid Amount. The bid will be awarded and / or Alternates will be selected as follows:

- 1. Award Base Bid Only
- 2. Award Base Bid + Alternate No. 1, and 2
- 3. Award Base Bid + Alternate No. 1, 2 and 3
- 4. Award Base Bid + Alternate No. 1, 2, 3, and 4

Contractor must propose on the alternate listed below and as further described in Division -2 of these Specifications.

ALTERNATE N	<u>lO. 1</u> : Braille Trail Loop Nylon Rope, incl	uding Vertical Posts and Gravel Foundations
ADD 1,105 LF:	\$ Written	\$ Figures
ALTERNATE N	IO. 2: Braille Trail Loop Nylon Rope	
ADD 185 LF:	\$ Written	\$ Figures
<u>ALTERNATE N</u>	I <u>O. 3</u> : Braille Trail Loop Sign, including C	Concrete Foundation
ADD 10 UN:	\$ Written	\$ Figures
ALTERNATE N	I <u>O</u> . 4: Trailhead Entry Sign, including Co	ncrete Foundations
ADD 1 UN:	\$ Written	\$ Figures

NOTE: Bid Contingency may include one-half of one percent of contract amount set aside for local training if and when directed by the County.

Diadei 3 Name	Bidder's	Name	
---------------	----------	------	--

CONSENT OF SURETY TO ACCOMPANY PROPOSAL (BID)

	$_$ (hereinafter called Surety), organized and existing under the laws of th	e State of				
	_ duly authorized and qualified to transact business in the State of New	Jersey, in				
consideration of the sum of One Dollar (\$1.00), lawful money of the United States of America, to it in har						
paid, receipt whereof is hereby acknowledged, and in consideration, hereby certifies and agrees that						
the contract for which the	e attached proposal is made be awarded to(h	ereinafter				
called Contractor) for the	e performance of certain work and labor or the supplying of certain ma	iterials, or				
both, as more particular	ly set forth in said proposal and described for purposes of this instrur	nent as a				
proposal for	to the COUNTY OF UNION and if Contractor shall enter	er into the				
contract, Surety will beco	ome bound as surety for its faithful performance, labor and material pay	ment and				
will provide the Contractor with a performance, labor and material payment bond in the full amount o						
contract price.						
NOTE:	NAME OF INSURANCE COMPANY					
Expiration date Needed if Annual Surety	ADDRESS:					
	ODICINAL SIGNATURE					
	ORIGINAL SIGNATURE ATTORNEY-IN-FACT FOR INSURANCE CO.					

NOTE: PROOF OF AUTHORITY OF OFFICERS OF SURETY COMPANY TO EXECUTE THIS DOCUMENT MUST BE SUBMITTED.

BIDDER SIGNATURE PAGE

THE BIDDER MUST READ THE FOLLOWING INSTRUCTIONS TO COMPLETE THIS PAGE:

- 1. If doing business under a <u>trade name, partnership or a sole proprietorship</u>, you must submit the bid under exact title of the trade name, partnership, or proprietorship, and the bid must be signed by either the <u>owner</u>, or a <u>partner</u> and <u>witnessed</u> by a <u>notary public</u>.
- 2. If a <u>Corporation</u>, the bid must be signed by the <u>President</u> or <u>Vice President</u> and <u>witnessed</u> by a <u>Corporate Secretary</u> (corporate title must be exact) and <u>affix corporate seal</u>. If a Corporate Secretary does not exist, President or Vice President's signature shall be witnessed by a Notary Public.
- 3. Other persons <u>authorized</u> by <u>corporate resolution</u> to execute agreements in its behalf may also sign the bid documents (pages). <u>Copy of a resolution must accompany the bid</u>.
- 4. The person who signs this bid form must also sign the Non-Collusion Affidavit.

You **cannot** witness your own signature.

5.

	NAME OF BIDDER
	ADDRESS OF BIDDER
ORIGINAL SIGNATURE CORPORATE SECRETARY	ADDICES OF BIDDER
	TEL:
PRINT NAME AND TITLE CORPORATE SECRETARY	FAX: E-Mail:
	BY:
	ORIGINAL SIGNATURE
Corporate Seal	
	PRINT OR TYPE NAME AND TITL

WARNING: IF YOU FAIL TO FULLY, ACCURATELY, AND COMPLETELY SUPPLY THE INFORMATION REQUESTED ON THIS PAGE, YOUR BID MAY BE REJECTED.

Bidder's Name	Bidder's Name
---------------	---------------

STATEMENT OF OWNERSHIP DISCLOSURE

N.J.S.A. 52:25-24.2 (P.L. 1977, c.33, as amended by P.L. 2016, c.43)

This statement shall be completed, certified to, and included with all bid and proposal submissions. Failure to submit the required information is cause for automatic rejection of the bid or proposal.

Name o	of Organization:	
<u>Organi</u>	zation Address:	
<u>Part</u> l C	check the box that represents the type of business organization:	
□Sole F	Proprietorship (skip Parts II and III, execute certification in Part IV)	
□Non-F	Profit Corporation (skip Parts II and III, execute certification in Part IV)	
□For-Profit Corporation (any type) □Limited Liability Company (LLC)		
□Partne	ership □Limited Partnership □Limited Liability Partnership (LLP)	
□Other	(be specific):	
Part II		
	The list below contains the names and addresses of all stockholders in the corporation who own 10 percent or more of its stock, of any class, or of all individual partners in the partnership who own a 10 percent or greater interest therein, or of all members in the limited liability company who own a 10 percent or greater interest therein, as the case may be. (COMPLETE THE LIST BELOW IN THIS SECTION)	
	OR	
	No one stockholder in the corporation owns 10 percent or more of its stock, of any class, or no individual partner in the partnership owns a 10 percent or greater interest therein, or no member in the limited liability company owns a 10 percent or greater interest therein, as the case may be. (SKIP TO PART IV)	

STATEMENT OF OWNERSHIP DISCLOSURE - CONTINUED

(Please attach additional sheets if more space is needed):

Name of Individual or Business Entity	Home Address (for Individuals) or Business Address

<u>Part III</u> DISCLOSURE OF 10% OR GREATER OWNERSHIP IN THE STOCKHOLDERS, PARTNERS OR LLC MEMBERS LISTED IN PART II

If a bidder has a direct or indirect parent entity which is publicly traded, and any person holds a 10 percent or greater beneficial interest in the publicly traded parent entity as of the last annual federal Security and Exchange Commission (SEC) or foreign equivalent filing, ownership disclosure can be met by providing links to the website(s) containing the last annual filing(s) with the federal Securities and Exchange Commission (or foreign equivalent) that contain the name and address of each person holding a 10% or greater beneficial interest in the publicly traded parent entity, along with the relevant page numbers of the filing(s) that contain the information on each such person. Attach additional sheets if more space is needed.

Website (URL) containing the last annual SEC (or foreign equivalent) filing	Page #'s

STATEMENT OF OWNERSHIP DISCLOSURE - CONTINUED

Please list the names and addresses of each stockholder, partner or member owning a 10 percent or greater interest in any corresponding corporation, partnership and/or limited liability company (LLC) listed in Part II **other than for any publicly traded parent entities referenced above**. The disclosure shall be continued until names and addresses of every noncorporate stockholder, and individual partner, and member exceeding the 10 percent ownership criteria established pursuant to N.J.S.A. 52:25-24.2 has been listed. **Attach additional sheets if more space is needed.**

Stockholder/Partner/Member and Corresponding Entity Listed in Part II	Home Address (for Individuals) or Business Address

Part IV Certification

I, being duly sworn upon my oath, hereby represent that the foregoing information and any attachments thereto to the best of my knowledge are true and complete. I acknowledge: that I am authorized to execute this certification on behalf of the bidder/proposer; that the *County of Union* is relying on the information contained herein and that I am under a continuing obligation from the date of this certification through the completion of any contracts with *County of Union* to notify the *County of Union* in writing of any changes to the information contained herein; that I am aware that it is a criminal offense to make a false statement or misrepresentation in this certification, and if I do so, I am subject to criminal prosecution under the law and that it will constitute a material breach of my agreement(s) with the, permitting the *County of Union* to declare any contract(s) resulting from this certification void and unenforceable.

Full Name (Print):	Title:	
Signature:	Date:	

Bidder's Name	Bidder's Name
---------------	---------------

SUBCONTRACTOR IDENTIFICATION STATEMENT LIST OF SUBCONTRACTORS

This form is ONLY required for plumbing and gas fitting, steam and hot water heating and ventilating apparatus, steam power plants, electrical work, structural steel, ornamental iron work, and any other trades required to be identified by the specifications (including, but not limited, to satisfying any DPMC Classification requirements).

CHECK THIS BOX IF NONE OF THE ABOVE LISTED TRADES OR THOSE REQUIRED TO BE IDENTIFIED IN THE SPECIFICATIONS ARE TO BE USED TO PERFORM THE WORK In compliance with N.J.S.A. 40A:11-16 and the bid specifications, the undersigned hereby lists the name or names of the following subcontractors: Company Name: Address: Subcontract Amount: \$ Telephone: Specific Scope of Work Subcontracted: License No. Company Name: Address: ___ Telephone: Subcontract Amount: \$ Specific Scope of Work Subcontracted: License No. Company Name: Telephone: _____ Subcontract Amount: \$_____ Specific Scope of Work Subcontracted: License No. _____ IF MORE THAN THREE SUBCONTRACTORS, PLEASE COPY THIS SHEET AS NECESSARY AND ATTACH TO THE BID PACKAGE. (Continued on following page)

Bidder's Name	!

SUBCONTRACTOR IDENTIFICATION CERTIFICATION

Note the law does not permit the listing of alternate subcontractors. However, multiple subcontractors for the same trade are permitted to be named provided the bidder meets the following requirements:

- Bidder identifies each subcontractor named for that category;
- Bidder states the scope of work, goods and services (the portion of the work) to be performed by each subcontractor; and
- Bidder provides the price quote provided by each subcontractor.

The bidder is advised that any change of subcontractor(s) from ones listed herein is subject to the County's approval. Change of subcontractor(s) will be approved only if made for good cause and not as a result of an arbitrary purpose.

The undersigned Bidder certifies and declares that the subcontractors listed above shall be used as subcontractors to complete certain portions of the work in this project as set forth in N.J.S.A. 40A: 11-16.

Witness		NAME OF BIDDER
Date		
		ADDRESS
	Ву:	
		ORIGINAL SIGNATURE ONLY
		PRINT NAME AND TITLE

Bidder's Name:	

ACKNOWLEDGMENT OF ADDENDUM

COUNTY OF UNION

(Name of Construction /Public	Works Project) (Project	or Bid Number)
following notices, revisions, or ad- indicating date of receipt, bidder ad- notice, revision or addendum. N	denda to the bid advertisement, so cknowledges the submitted bid take ote that the County of Union's re	ereby acknowledges receipt of the pecifications or bid documents. By es into account the provisions of the cord of notice to bidders shall take proposal may be subject for rejection
Local Unit Reference Number or Title of Addendum/Revision	How Received (mail, fax, pick- up, etc.)	Date Received
or Title or Addendamy (oviolen	ap, otoly	
ACKNOWLEDGMENT BY BIDDE	R:	
NAME OF BIDDER:		
ORIGINAL SIGNATURE:		
PRINTED NAME AND TITLE:		

DATE: _____

CONTRACTOR BUSINESS REGISTRATION CERTIFICATE

New Mandatory Requirement - Effective 1/18/2010

The recently enacted **P.L. 2009, c.315**, requires that effective January 18, 2010; a contracting agency must receive proof of the bidder's business registration prior to the award of a contract. However, the proof must show that the bidder was in fact registered with the State of New Jersey Department of the Treasury, Division of Revenue and obtained the business registration prior to the receipt of bids.

If subcontractors are named on the bid, proof of the business registration for each subcontractor must be provided prior to the award of bid. Similarly to the bidder, the proof must show that each subcontractor was registered with the State of New Jersey Department of the Treasury, Division of Revenue and obtained the business registration prior to the receipt of bids.

Proof of business registration shall be
A copy of a Business Registration Certificate issued by the Department of the Treasury
Division of Revenue; or
A copy of the web version provided by the NJ Division of Revenue, or
Register online at www.nj.gov/treasury/revenue/taxreg.htm. Click the "online" link and then select "Register for Tax and Employer Purposes or call the Division at 609-292-1730. Note: A NJ Certificate of Authority is not acceptable.

FAILURE to submit proof of registration of the bidder or any subcontractor named on the bid prior to the award of a contract shall be cause to reject the bids.

FAILURE of the bidder or any subcontractor named on the bid to be <u>registered</u> prior to the receipt of bids is cause for a **MANDATORY REJECTION** of bids. (A NON-WAIVABLE DEFECT). This covers construction work as well as non-construction bids.

IN ADDITION:

The contractor shall provide written notice to all **subcontractors and suppliers** not specifically named on the bid of the responsibility to register and submit proof of business registration to the contractor. The requirement of proof of business registration extends down through all levels (tiers) of the project.

Before final payment on the contract is made by the contracting agency, the contractor shall submit an accurate list and the proof of business registration of each subcontractor or supplier used in the fulfillment of the contract, or shall attest that no subcontractors were used.

For the term of the contract, the contractor and each of its affiliates and a subcontractor and each of its affiliates [N.J.S.A. 52:32-44(g)(3)] shall collect and remit to the Director, New Jersey Division of Taxation, the use tax due pursuant to the Sales and Use Tax Act on all sales of tangible personal property delivered into this State, regardless of whether the tangible personal property is intended for a contract with a contracting agency.

A business organization that fails to provide a copy of a business registration as required pursuant to section 1 of P.L.2001,c.134 (C.52:32-44 et al.) or subsection e. or f. of section 92 of P.L.1977,c.110 (C.5:12-92), or that provides false business registration information under the requirements of either of those sections, shall be liable for a penalty of \$25 for each day of violation, not to exceed \$50,000 for each business registration copy not properly provided under a contract with a contracting agency.

BUSINESS REGISTRATION


Mandatory Requirement

P.L. 2009, c.315, requires that effective January 18, 2010; a contracting agency must receive proof of the bidder's business registration prior to the award of a contract. However, the proof must show that the bidder was in fact registered with the State of New Jersey Department of the Treasury, Division of Revenue and obtained the business registration prior to the receipt of bids.

If subcontractors are named on the bid, proof of the business registration for each must be provided prior to the award of a contract. Similarly to the bidder, the proof must show that each subcontractor was registered with the State of New Jersey Department of the Treasury, Division of Revenue and obtained the business registration prior to the receipt of bids.

Proof of business registration shall be:

- A copy of a Business Registration Certificate issued by the Department of Treasury, Division of Revenue; or
- A copy of the web printed version provided by the NJ Division of Revenue



	ATTACH BRC HERE
	
I	

Bidder's	Name	

AFFIRMATIVE ACTION REQUIREMENT

REQUIRED AFFIRMATIVE ACTION EVIDENCE

General Requirements of P.L. 1975, c. 127: You are hereby put on notice that:

CONSTRUCTION CONTRACTS: The successful contractor must submit within three (3) days of the notice of intent to award or the signing of the contract the initial project manning report (A.A.201). This report should be submitted at the time the signed contract is returned to the County of Union. Attention: *Affirmative Action Officer*.

If the successful contract <u>does not submit the initial project manning report</u> (A.A.201) within the three (3) days from the time the signed contract is returned to the County of Union, the County of Union <u>WILL</u> declare the contractor <u>non-responsive and award the</u> contract to the next lowest responsible bidder.

NAME OF BIDDER
ORIGINAL SIGNATURE
PRINT OR TYPE NAME AND TITLE
DATE THIS FORM IS COMPLETED

EXPERIENCE STATEMENT

I hereby certify that my company has performed the following private or public work, which is relevant to this bid. I further certify that my company has never defaulted under any contract. Should you not sign this form due to prior defaults, please provide details on an attached sheet.

Witness	NAME OF BIDDER
Date	
	ADDRESS
	By: ORIGINAL SIGNATURE ONLY
	PRINT NAME AND TITLE

YOU MAY ATTACH ADDITIONAL SHEETS, BUT YOU MUST SIGN AND WITNESS THIS SHEET.

Bidder's Name

CERTIFICATE OF BIDDER SHOWING ABILITY TO PERFORM CONTRACT

STATE OF NEW JERSEY /)
STATE OF NEW JERSEY / COUNTY OF	Specify, if Other	
COUNTY OF)	
I,		, of the (City, Town, Borough, etc.) of
State of		, of the (City, Town, Borough, etc.) of, of full age, being duly sworn according
to law on my oath depose and say	that:	
l am	of the firm of	
the Bidder making the proposal for	r the above named Project	("Contractor"), and that I executed said
proposal with full authority to do so	o; and that said Contractor,	pursuant to N.J.S.A. 40A:11-20, certifies
that it owns, leases or controls all	the necessary equipment r	equired by the Plans, Specifications and
Advertisements under this Bids are	e asked for.	
If the Bidder is not the actual owner	er or lessee of any such eq	uipment, then the Bidder shall attach to this
Certificate information identifying t	the source from which the e	equipment will be obtained, and such
information shall be accompanied	by a certificate from the ov	vner or person in control of the equipment
definitively granting to the Bidder t	the control of the equipmen	at required during such time as may be
necessary for the completion of the	at portion of the contract.	
,	•	
(Also type or print name of affiant	under signature)	<u></u>
(7130 type of print hame of amant	ander signature,	
Bv:		

Bidder's	Name	
----------	------	--

NON-COLLUSION AFFIDAVIT

(N.J.S.A. 52:34-15)

STATE OF	
COUNTY OF) SS :
I, of the City of	, in the County of, of full age, being duly sworn according to law, on my oath
depose and say that: I am	of the firm of , the
bidder making the proposal for the above above named project, and that I executed has not, directly or indirectly, entered into taken any action in restraint of free, comp that all statements contained in said prop knowledge that the COUNTY OF UNION	e named project, and that I executed the said proposal for the did the said proposal with full authority to do so; that said bidder of any agreement, participation in any collusion, or otherwise detitive bidding in connection with the above named project; and dosal and in this Affidavit are true and correct, and made with full , NEW JERSEY relies upon the truth of the statements contained ontained in the affidavit in awarding the contract for the said
contract upon an agreement or understar	agency has been employed or retained to solicit or secure such nding for a commission, percentage, brokerage or contingent fee, established commercial or selling agencies maintained by 5).
	NAME OF BIDDER
	ORIGINAL SIGNATURE ONLY
	NOTE: The person who signed the bidder signature page for the bidder should sign this form also.
Subscribed and sworn before me thisday of, 200	
Notary Public of the State of My commission expires:	

WARNING: IF YOU FAIL TO FULLY, ACCURATELY, AND COMPLETELY FILL OUT THIS AFFIDAVIT OF NON-COLLUSION, YOUR BID MAY BE REJECTED.

Contractor Registration Advisement

For Public Works Projects

A new law, known as "The Public Works Contractor Registration Act" (P.L. 1999, c.238), became effective April 11, 2000. Under the Act, no contractor/subcontractor will be permitted to bid on or engage in any contract for public work, as defined in Section 2 of P.L. 1963, c.150 (C:34:11-56.26), unless that contractor/subcontractor is registered with the New Jersey Department of Labor. The Act provides that upon registration with the Department, a public works contractor/subcontractor will be issued a certificate by the Department indicating compliance with the Act's requirements. The registration fee has been set at \$300.00 per year. Upon the effective date of the Act, public bodies will be expected to request production of such a certificate from those bidding on or engaging in public works projects.

It is important to note that the term "contractor," is defined in the, Act as, "a person, partnership, association, joint stock company, trust, corporation or other legal business entity or successor thereof who enters into a contract which is subject to the provision of the "New Jersey Prevailing Wage Act," P.L. 1963, c.150 (C.34:11-56.25, et seq.) for the construction, reconstruction, demolition, alteration, repair or maintenance of a public building regularly open to and used by the general public or a public institution, and includes any subcontractor or lower tier subcontractor as defined herein: except that, for the purposes of the act, no pumping station, treatment plant or other facility associated with utility and environmental construction, reconstruction, demolition, alteration, repair or maintenance shall be regarded as a public building regularly open to and used by the general public or a public institution."

Registration forms, copies of the Act, and other relevant information can be obtained by contacting:

Contractor Registration Unit New Jersey Department of Labor Division of Wage & Hour Compliance PO Box 389 Trenton, New Jersey 08625-0389 Telephone: 609-292-9464 Fax: 609-633-8591

E-mail: contreg@dol.state.nj.us

Bidder's	Name	

AMERICANS WITH DISABILITIES ACT EQUAL OPPORTUNITY FOR INDIVIDUALS WITH DISABILITIES

The contractor and the County of Union (hereafter "Owner") do hereby agree that the provisions of Title II of the Americans With Disabilities Act of 1990 (the "Act") (42 U.S.C.S12.101 et seq.), which prohibits discrimination on the basis of disability by public entities in all services, programs and activities provided or made available by public entities, and the rules and regulations promulgated pursuant thereunto, are made a part of this contract. In providing any aid, benefit, or service on behalf of the Owner pursuant to this contract, the contractor agrees that the performance shall be in strict compliance with the Act. In the event the contractor, its agents, servants, employees, or subcontractors violate or are alleged to have violated the Act during the performance of this contract, the contractor shall defend the Owner in any action or administrative proceeding commenced pursuant to this Act. The contractor shall indemnify, protect, and save harmless the Owner, its agents, servants, and employees from and against any and all suits, claims, losses, demands, or damages of whatever kind or nature arising out of or claimed to arise out of the alleged violation. The contractor shall, at its own expense, appear, defend, and pay any and all charges for legal services and any and all costs and other expenses arising from such action or administrative proceeding or incurred in connection therewith. In any and all complaints brought pursuant to the Owner's grievance procedure, the contractor agrees to abide by any decision of the Owner which is rendered pursuant to said grievance procedure. If any action or administrative proceeding results in an award of damages against the Owner, or if the Owner incurs any expense to cure a violation of the ADA which has been brought pursuant to its grievance procedure, the contractor shall satisfy and discharge the same at its own expense.

The Owner shall, as soon as practicable after a claim has been made against it, give written notice thereof to the contractor along with full and complete particulars of the claim. If any action or administrative proceeding is brought against the Owner or any of its agents, servants, and employees, the Owner shall expeditiously forward or have forwarded to the contractor every demand, complaint, notice, summons, pleading, or process received by the Owner or its representatives.

It is expressly agreed and understood that any approval by the Owner of the services provided by the contractor pursuant to this contract will not relieve the contractor of the obligation to comply with the Act and to defend, indemnify, protect, and save harmless the Owner pursuant to this paragraph.

It is further agreed and understood that the Owner assumes no obligation to indemnify or save harmless the contractor, its agents, servants, employees and subcontractors for any claim which may arise out of their performance of this Agreement. Furthermore, the contractor expressly understands and agrees that the provisions of this indemnification clause shall in no way limit the contractor's obligations assumed in this Agreement, nor shall they be construed to relieve the contractor from any liability, nor preclude the Owner from taking any other actions available to it under any other provisions of this Agreement or otherwise at law.

Name	(Please print or type)	
Signature	Date	

STATEMENT OF BIDDER'S QUALIFICATIONS

All questions must be answered and the data given must be clear and comprehensive. <u>This statement must be notarized</u>. Questions may be answered on separate attached sheets. The Bidder may submit any additional information it desires.

manent Main Office Address)
en Organized)
Corporation, where incorporated)
ber of years your organization has been engaged in construction or contracting business ent firm or trade name?
many years of experience in construction work has your organization had (a) as a gener ractor? And/or (b) As a subcontractor?
tracts on hand: (Attach a list or table showing gross amounts of each Contract and the opriate dates of completion)
eral character of work performed by you
e you ever failed to complete any work awarded to you?
e you ever defaulted on a Contract? If so, complete details, including wher why?
, i

STATEMENT OF BIDDER'S QUALIFICATIONS - (continued)

11.	Has any officer or partner of your organization ever failed to complete a construction contract handled in its own name? If so, state name of individual, name of owner, location and type of project, and reason for the failure to complete.
12.	List your major equipment available for this Contract.
13.	Experience in the construction work similar in importance to this Project.
14.	Have you had any material adverse changes from the trades as listed in NJ Notice of Classification within last five (5) years? If so, list prior classification.
15.	Background and experience of the principal members of your organization, including the officers

Individual's Name	Present Position or Office	Yrs. of Construction Experience	Magnitude & Type of Work	In What

16.	Bank Reference. (Name, Address, Phone, Representative)			
17.	Will you, upon request, fill out a detailed financial statement and furnish any other information that may be required by the proper agency?			
18.	The undersigned, hereby authorizes and requests any person, firm or corporation to furnish any information requested by the proper agency in verification of the responses comprising this Statement of Bidder's Qualifications.			
17.	Bidder's telephone number, fax	x number and e	e-mail address (if applicable).	
	Phone			
	Fax			
	E-mail			
	Mobile	<u></u>		
Dated	at	this	day of _, 20	
BIDDE	ER (Signature)	_		
BIDDE	R (Print Name)			
Subsc this	ribed and sworn to before me day of	, 20		
Specif	Notary Public of New Jersey/ y Other State mmission Expires	, 20		

Bidder's N	ame

CONTRACTOR PERFORMANCE RECORD

List all contracts completed by you below or provide separate form.

Name of Owner	Name & Location of Project: Type Of Work	Prime or Sub- Cont.	Engineer or Architect in Charge for Owner	Contract Price (Omit Cost)	Date Completed	Was Time* Extension Necessary	Were Any Penalties Imposed	Were Liens* Claims or Stop Notice Filed

^{*} If answer is YES, provide explanation of details in connection with non-completion of contracts, time extensions, penalties imposed, labor troubles, liens, claims and notices filed against contracts listed in preceding item "Performance Record" on an attached sheet.

Bidder's	Name			
----------	------	--	--	--

CONTRACTOR PERFORMANCE RECORD CERTIFICATION

The information above is true and complete to the best of my knowledge and belief.

	(Name of Organization)
	(Signature)
	(Title)
Subscribed and sworn to before me	
this, 20	
(Seal) Notary Public of New Jersey/ Specify Other State	<u> </u>
My Commission Expires, 20	

Bidder's I	Name
------------	------

AFFIDAVIT REGARDING LIST OF DEBARRED, SUSPENDED OR DISQUALIFIED BIDDERS

STATE OF NEW JERSEY /)
COUNTY OF	Specify, if Other) SS:)
I, State of to law on my oath depose and	fsay that:	, of the (City, Town, Borough, etc.) of , of full age, being duly sworn according
authority to do so. Said Bidde	r is not at the time of the making vernment's List of Debarred, Sus	I have executed the said Proposal with full this bid included on the New Jersey State spended or Disqualified Bidders as a result
	-	Name of Contractor
	By: (Signature	e of Authorized Representative)
Subscribed and sworn to before this day of		
(Seal) Notary Public of New Je Specify Other State	ersey/	
My Commission Expires	, 20 .	

Bidder's Name	
---------------	--

PRIOR NEGATIVE EXPERIENCE QUESTIONNAIRE (N.J.S.A. 40A:11-4)

	1.	mediation, or other confailed to provide or per	ntractually stipulated form goods or service	een found, through either court adjudication, arbitration alternate dispute resolution mechanism, to have: ces; or failed to complete a contract in a timely mannual aprior contract with a public entity?
to utilize the services of another contractor to provide the goods or perform the services or to correct or complete the contract?		yes	no	If yes, please provide full, detailed explanation.
to utilize the services of another contractor to provide the goods or perform the services or to correct or complete the contract?				
Within the past ten (10) years, have you defaulted on a contract, thereby requiring a public ent to look to your surety for completion of the contract or tender of the costs of completion?	2.	to utilize the services of	of another contractor	
to look to your surety for completion of the contract or tender of the costs of completion?		yes	no	If yes, please provide full, detailed explanation.
to look to your surety for completion of the contract or tender of the costs of completion?				
the agencies or department of the executive branch of the State of New Jersey at the time of the contract award, where the action was based on failure to perform a contact for goods or service with a public entity?	3.	to look to your surety f	or completion of the	e contract or tender of the costs of completion?
the agencies or department of the executive branch of the State of New Jersey at the time of the contract award, where the action was based on failure to perform a contact for goods or service with a public entity?				
yes no If yes, please provide full, detailed explanation.	1.	the agencies or depart contract award, where	ment of the executiv	ve branch of the State of New Jersey at the time of th
		yes	no	If yes, please provide full, detailed explanation.

Bidder's	Name			
----------	------	--	--	--

PRIOR NEGATIVE EXPERIENCE CERTIFICATION

I hereby certify that the above statements are day of, 20	true and accurate as of this	
Name of Contractor		
By(Signature of Authorized Representative)		
Subscribed and sworn to before me		
this, day of, 20		
(Seal) Notary Public of New Jersey/ Specify Other State		
My Commission Expires	20	

Bidder's	Name		

TO BE COMPLETED ONLY WHEN FINAL PAYMENT IS REQUESTED

CONTRACTOR'S CERTIFICATION OF COMPLIANCE - NEW JERSEY PREVAILING WAGE ACT

TO:	County of Union	CONTRACT:
	Division of Engineering	
	2325 South Avenue Scotch Plains, New Jersey 07076	
	Scotch Flains, New Jersey 0/0/6	
PROJ	JECT:	
	cordance with the requirements of the ndersigned contractor on the public wo	e New Jersey Prevailing Wage Act, N.J.S.A. 34:11-56 et al *, ork being performed for:
	C	COUNTY OF UNION
		with the contract requirements regarding the payment of the ler "The New Jersey Prevailing Wage Act" N.J.S.A. 34:11-56
	CONTRACTOR: ADDRESS:	
	DV.	
	BY:	ORIGINAL SIGNATURE ONLY
	E OF NEW JERSEY	
	by me duly sworn according to law, or	
of	ays thatisis the above name	ed contractor, and that
	cts set forth in the above statement are	
	cribed and sworn before me day of, 200	
	y Public:	
IVIV C	ommission Expires:	

* N.J.S.A. 34:11-56.33 requires the contractor and subcontractor to file written statements with the public body in form satisfactory to the Commissioner certifying to the amounts then due and owing from such contractor and subcontractor filing such statement to any and all workmen for wages due on account of the public work, setting forth therein the names of the persons whose wages are unpaid and the amount due to each respectively. Union County will withhold the amount so deducted for the benefit of the workmen whose wages are unpaid as shown by the verified statement filed, and will pay directly to any workman the amount shown by such statement to be due to him for such wages. Such payment shall thereby discharge the obligation of the contractor to the person receiving such payment to the extent of the amount thereof.

Bidder's Name

UNCOMPLETED CONTRACTS AFFIDAVIT

(To be Submitted with DPMC Form 701)

PURSUANT TO N.J.A.C. 17:19-2.13, BIDDER DECLARES THE FOLLOWING WITH RESPECT TO ITS UNCOMPLETED CONTRACTS, ON ALL WORK, FROM WHATEVER SOUCE (PUBLIC AND PRIVATE), BOTH IN NEW JERSEY AND FROM OTHER GOVERNMENTAL JURISDICTIONS

	DD 0 1507	00101111		NAME AND TELEBRIONE MUMBER OF
ENTITY	PROJECT TITLE	ORIGINAL CONTRACT AMOUNT	UNCOMPLETED AMOUNT AS OF BID OPENING DATE	NAME AND TELEPHONE NUMBER OF PARTY TO BE CONTACTED FRM ENTITY FOR VERIFICATION

TOTAL AMOUNT OF UNCOMPLETED CONTRA	ACTS \$	
Sworn and Subscribed to Before me	BIDDER:	
Thisday of, 20	(Signature)	
Notary Public	(Print Name)	

Bidder's Name

CERTIFICATE OF INSURANCE STATEMENT

The Bidder fully understands the County of Union insurance requirements as stated in the Instructions to Bidders as well as the Owner/Contractor Agreement and agrees to provide all insurance required by these documents <u>prior</u> to the issuance of the Notice to Proceed.

BIDDER (Signature)	
BIDDER (Print Name)	

Bidder's Name	_
---------------	---

COLLECTION OF USE TAX ON SALES TO LOCAL GOVERNMENTS STATEMENT

The Bidder fully understands the requirements of the use tax on sales to local governments as stated in the General Conditions to the Contract for Construction and the Instructions to Bidders, and agrees at all times to comply with the "Contractor Use Tax Collection Legislation", as defined therein, and the terms relating thereto contained in the Contract Documents.

BIDDER (Signature)	_
BIDDER (Print Name)	_

Bidder's N	Name
------------	------

TIME OF COMPLETION

calendar days and will be substantia	illy completed within One-Hunc	of work will be started within ten (10) dred and Fifty (150) calendar days
from the date of the notice to procee	d.	
,	of	
NAME (Print or type)	COMPANY	
Agree to complete work in the time f	rame specified	
		SIGNATURE
SITE VISIT – GENERAL CONTRAC	CTOR	
,	of	
NAME (Print or type)	COMPANY	_
Visited the site of the work on		
		SIGNATURE

COUNTY OF UNION NEW JERSEY Division of Purchasing

DISCLOSURE OF INVESTMENT ACTIVITIES IN IRAN

Solicitation Number:	Bidder/Offeror:
proposes to enter into or renew a c perjury, that the person or entity, o identified on a list created and m engaging in investment activities in principles which are the subject of law, rule or contract, including bu	5, any person or entity that submits a bid or proposal or otherwise ontract must complete the certification below to attest, under penalty of rone of the person or entity's parents, subsidiaries, or affiliates, is not aintained by the Department of the Treasury as a person or entity I Iran. If the Director finds a person or entity to be in violation of the the law, s/he shall take action as may be appropriate and provided by the not limited to, imposing sanctions, seeking compliance, recovering ault and seeking debarment or suspension of the person or entity.
I certify, pursuant to Public Law authorized to bid/renew:	2012, c. 25, that the person or entity listed above for which I am
person or entity that provides oil	es of \$20,000,000 or more in the energy sector of Iran, including a or liquefied natural gas tankers, or products used to construct or toil or liquefied natural gas, for the energy sector of Iran,
	ttends \$20,000,000 or more in credit to another person or entity, for 45 ty will use the credit to provide goods or services in the energy sector
parents, subsidiaries, or affiliates and precise description of the act under penalty of perjury. Failure	ty is unable to make the above certification because it or one of its has engaged in the above-referenced activities, a detailed, accurate vities must be provided in part 2 below to the Division of Purchase to provide such will result in the proposal being rendered as non-es, fines and/or sanctions will be assessed as provided by law.
IRAN. You must provide, accurate	THER INFORMATION RELATED TO INVESTMENT ACTIVITIES IN and precise description of the activities of the bidding person/entity, or ffiliates, engaging in the investment activities in Iran outlined above by
Name	Relationship to Bidder/Offeror
Description of Activities	
Duration of Engagement	Anticipated Cessation Date

<u>DISCLOSURE OF INVESTMENT ACTIVITIES IN IRAN – (Continued)</u>

Bidder/Offeror	
Contact Name	Contact Phone Number
and any attachments thereto to the beauthorized to execute this certification of that Union County is relying on the informat continuing obligation from the date of County to notify the County in writing of acknowledge that I am aware that it is a in this certification, and if I do so, I recontinuity will also constitute a material breat	by oath, hereby represent and state that the foregoing information est of my knowledge are true and complete. I attest that I am n behalf of the above referenced person or entity. I acknowledge mation contained herein and hereby acknowledge that I am under this certification through the completion of any contracts with the f any changes to the answers of information contained herein. In criminal offense to make a false statement or misrepresentation gnize that I am subject to criminal prosecution under the law and each of my agreement(s) with Union County, New Jersey and that the ready contract(s) resulting from this certification void and
Full Name (Print)	Signature
Title	Date

STANDARD SPECIFICATIONS

The Standard Specifications for Road and Bridge Construction of New Jersey Department of Transportation, 2007 Edition; is added to and/or amended elsewhere herein by the Notice to Contractors (Advertisement), Proposal, Information for Bidders, General Conditions, Special Provisions, Project Plans, and Supplementary Specifications; shall, insofar as technical requirements are involved, govern in the execution of this project.

Such Standard Specifications are made a part of these Specifications by this reference and will not be repeated herein. It is the responsibility of prospective bidders to familiarize themselves with these Standard Specifications, copies of which may be examined at the office of the Engineer and may be obtained, upon payment of the cost thereof, from:

Department of Transportation State of New Jersey 1035 Parkway Avenue Trenton, New Jersey 08625

The Notice to Bidders (Advertisement), Proposal, General Conditions, Instructions to Bidders, Special Provisions, Project Plans and/or Technical Specifications shall govern and prevail in the case of conflict between them and the Standard Specifications.

In these Standard Specifications the words "COMMISSIONER" or "DEPARTMENT" shall refer to and mean the person, persons, body, board or agent legally empowered to enter into contracts and otherwise legally act for the Owner. The words "RESIDENT ENGINEER (RE)", "ENGINEER" or "STATE" shall refer to and mean the professional engineering representative of the Owner as hereinbefore defined and the word "INSPECTOR" shall mean the authorized project representative of the Engineer with the authority as hereinbefore defined. The word "LABORATORY" shall mean and refer to the Engineer who may, at his discretion, and with the consent of the Owner, employ qualified technical personnel or testing laboratories to assist him in fulfilling the duties normally assigned to the "LABORATORY" in these Standard Specifications.

When reference is made herein to the bulletins, standards, specifications, publications or requirements of the Manual on Uniform Traffic Control Devices (MUTCD), Institute of Traffic Engineers (ITE), Federal Highway Administration (FHWA), American Association of State Highway Officials (AASHO), the American Concrete Institute (ACI), the American Society of Civil Engineers (ASCE) or similar national or regional societies, associations, institutes or organizations; the requirements of the bulletins, specifications, publications or requirements referred to shall be considered a part of these Specifications by such reference and shall not be repeated herein but shall have the same import and be as binding as if herein set forth in full.



STATE OF NEW JERSEY

Department of Labor and Workforce Development
Division of Wage and Hour Compliance - Public Contracts Section
PO Box 389
Trenton, NJ 08625-0389

PREVAILING WAGE RATE DETERMINATION

The New Jersey Prevailing Wage Act (N.J.S.A. 34:11-56.25 et seq.) requires that the Department of Labor and Workforce Development establish and enforce a prevailing wage level for workers engaged in public works in order to safeguard their efficiency and general well being and to protect them as well as their employers from the effects of serious and unfair competition.

Prevailing wage rates are wage and fringe benefit rates based on the collective bargaining agreements established for a particular craft or trade in the locality in which the public work is performed. In New Jersey, these rates vary by county and by the type of work performed.

Applicable prevailing wage rates are those wages and fringe benefits in effect on the date the contract is awarded. All pre-determined rate increases listed at the time the contract is awarded must also be paid, beginning on the dates specified. Rates that have expired will remain in effect until new rates are posted.

Prevailing Wage Rate

The prevailing wage rate for each craft will list the effective date of the rate and the following information:

W =Wage Rate per Hour

B = Fringe Benefit Rate per Hour*

T = Total Rate per Hour

* Fringe benefits are an integral part of the prevailing wage rate. Employers not providing such benefits must pay the fringe benefit amount directly to the employee each payday. Employers providing benefits worth less than the fringe benefit amount must pay the balance directly to the employee each payday.

Unless otherwise stated in the Prevailing Wage Rate Determination, the fringe benefit rate for overtime hours remains at the straight time rate.

When the Overtime Notes in the Prevailing Wage Rate Determination state that the overtime rates are "inclusive of benefits," the benefit rate is increased by the same factor as the wage rate (i.e. multiplied by 1.5 for time and one-half, multiplied by 2 for double time, etc.).

Apprentice Rate Schedule

An "apprentice" is an individual who is registered with the United States Department of Labor - Office of Apprenticeship and enrolled in a certified apprenticeship program during the period in which they are working on the public works project.

The apprentice <u>wage</u> rate is a percentage of the journeyman wage rate, unless otherwise indicated. The apprentice <u>benefit</u> rate is the full journeyman benefit rate, unless otherwise indicated.

If there is no apprentice rate schedule listed, the individual must be paid at least the journeyman rate even if that individual is in a certified apprentice program for that trade.

If there is no ratio of apprentices to journeymen listed for a particular craft, then the ratio shall be one (1) apprentice to every four (4) journeymen.

1/5/2017 Page 1 of 68

Comments/Notes

For each craft listed there will be comments/notes that cover the definition of the regular workday, shift differentials, overtime, recognized holidays, and any other relevant information.

Public Works Contractor Registration

The Public Works Contractor Registration Act (N.J.S.A. 34:11-56.48, et seq.) requires that **all** contractors, subcontractors, or lower tier subcontractors who are working on or who bid on public works projects register with the Department of Labor and Workforce Development. Applications are available at www.nj.gov/labor (click on Wage & Hour and then go to Registration & Permits).

Pursuant to N.J.S.A. 34:11-56.51:

No contractor shall bid on any contract for public work as defined in section 2 of P.L.1963, c. 150 (C.34:11-56.26) unless the contractor is registered pursuant to this act. No contractor shall list a subcontractor in a bid proposal for the contract unless the subcontractor is registered pursuant to P.L.1999, c.238 (C.34:11-56.48 et seq.) at the time the bid is made. No contractor or subcontractor, including a subcontractor not listed in the bid proposal, shall engage in the performance of any public work subject to the contract, unless the contractor or subcontractor is registered pursuant to that act.

Snow Plowing

Snow plowing contracts are <u>not</u> subject to the New Jersey Prevailing Wage Act or the Public Works Contractor Registration Act.

1/5/2017 Page 2 of 68

County - UNION

Craft: Air Conditioning & Refrigeration - Service and Repair

PREVAILING WAGE RATE

	03/14/16
Journeyman (Mechanic)	W37.18
	B21.68
	T58.86

Craft: Air Conditioning & Refrigeration - Service and Repair

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
As Shown	Mo. 1-3	Mo. 4-12	2nd Year	3rd Year	4th Year	5th Year		Wage = %	of Jnymn	Wage
Wage and Bene	50%	55%	60%	65%	75%	85%		Bene = %	of Jnymn	Bene

Ratio of Apprentices to Journeymen - 1:4

APPRENTICE RATE SCHEDULE FOR THOSE APPRENTICES ENTERING PROGRAM AFTER 3-1-13:

INTERVAL PERIOD AND RATES

As Shown 1st Year 2nd Year 3rd Year 4th Year 5th Year Wage =% of Jnymn Wage Wage and Benefit 40% 50% 60% 70% 80% Bene. =% of Jnymn Wage

Craft: Air Conditioning & Refrigeration - Service and Repair COMMENTS/NOTES

THESE RATES MAY BE USED FOR THE FOLLOWING:

- Service/Repair/Maintenance Work to EXISTING facilities.
- Replacement or Installation of air conditioning and refrigeration equipment when the combined tonnage does not exceed 15 tons for refrigeration, or 25 tons for air conditioning.
- Replacement or Installation of "packaged" or "unitary" rooftop-type units when the combined tonnage of the units does not exceed 75 tons.

NOTE: These rates may NOT be used for any work in new construction (including work on new additions).

The regular workday shall consist of 8 hours, starting between 6:00 AM and 10:00 AM, Monday through Friday.

SHIFT DIFFERENTIALS:

- The second and third shifts shall be paid an additional 15% of the hourly rate.
- All shifts must run for a minimum of 5 consecutive days.

OVERTIME:

Hours worked in excess of 8 per day or before or after the regular workday, that are not shift work, and all hours on Saturday shall be paid at time and one-half the hourly rate, inclusive of benefits. All hours on Sunday and holidays shall be paid at double the hourly rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 3 of 68

County - UNION

Craft: Boilermaker PREVAILING WAGE RATE

	01/01/17
Foreman	W48.70
	B41.32
	T90.02
General Foreman	W50.70
	B42.30
	T93.00
Journeyman	W43.70
	B39.72
	T83.42

Craft: Boilermaker APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
1000 Hours	65%	70%	75%	80%	85%	90%	95%			
Benefit =	33.58	34.50	35.38	36.24	37.12	37.49	38.85			

Ratio of Apprentices to Journeymen - *

* 1 apprentice will be allowed for the first 5 journeymen, 1 apprentice for the next 10 journeymen and 1 apprentice for each succeeding 20 journeymen up to a maximum of 5 apprentices per contractor on any one job.

Craft: Boilermaker COMMENTS/NOTES

HIGH WORK: All apprentices working on the erection, repair, or dismantling of smoke stacks, standpipes, or water towers shall be paid the Journeyman rate.

The regular workday shall consist of 8 hours, between 8:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall work 7½ hours and receive 8 hours pay, at a rate equal to the regular hourly rate plus 10%.
- The third shift shall work 7 hours and receive 8 hours pay, at a rate equal to the regular hourly rate plus 20%.
- For "Municipal Water Works" projects only, the following shall apply: Two, four day, 10 hour shifts may be worked at straight time Monday through Thursday. The day shift shall work four days, at 10 hours, for 10 hours pay. The second shift shall work four days, at nine and a half hours, for 10 hours pay, plus 10% the hourly rate for new work and .25 cents on repair work. Friday may be used as a make-up day at straight time, due to weather conditions, hoilday or any other circumstances beyond the employer's control.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays (except Labor Day) shall be paid at double the hourly rate. All hours on Labor Day shall be paid at four times the hourly rate.
- If any other craft employed by the same contractor, or a subcontractor thereof, receives double time in lieu of time and one-half, then the Boilermaker shall receive double time in lieu of time and one-half.
- For "Municipal Water Works" projects only, the following shall apply: Four 10 hour days may be worked Monday through Thursday at straight time. Friday may be used as a make-up day for a day lost to inclement weather, holiday or other conditions beyond the control of the employer. Overtime shall be paid for any hours that exceed 10 hours per day or 40 hours per week.

1/5/2017 Page 4 of 68

County - UNION

RECOGNIZED HOLIDAYS: New Year's Day, Washington's Birthday, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 5 of 68

County - UNION

Craft: Boilermaker - Minor Repairs PREVAILING WAGE RATE

	01/01/17
Foreman	W32.54
	B16.17
	T48.71
General Foreman	W33.04
	B16.17
	T49.21
Mechanic	W31.04
	B16.17
	T47.21

Craft: Boilermaker - Minor Repairs COMMENTS/NOTES

NOTE: These rates apply to MINOR REPAIR WORK ONLY (repair work in the field for which the contract amount does not exceed \$125,000.00).

OVERTIME:

Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays (except Labor Day) shall be paid at double the hourly rate. All hours on Labor Day shall be paid at four times the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Washington's Birthday, Good Friday, Memorial Day, July 4th, Labor Day, Presidential Election Day, Thanksgiving Day, day after Thanksgiving, Christmas Day. Saturday holidays observed the following Monday.

1/5/2017 Page 6 of 68

County - UNION

Craft: Bricklayer, Stone Mason PREVAILING WAGE RATE

	11/01/16	05/01/17	05/01/18
Deputy Foreman	W43.00	W0.00	W0.00
	B30.91	B0.00	B0.00
	T73.91	T76.04	T78.23
Foreman	W46.00	W0.00	W0.00
	B30.91	B0.00	B0.00
	T76.91	T79.04	T81.23
Journeyman	W40.00	W0.00	W0.00
	B30.91	B0.00	B0.00
	T70.91	T73.04	T75.23
		1	l

Craft: Bricklayer, Stone Mason APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
6 Months	40%	50%	55%	60%	65%	70%	75%	80%		
Benefits	3.72	4.65	5.12	5.58	20.48	21.83	23.18	24.52		

Ratio of Apprentices to Journeymen - 1:5

Craft: Bricklayer, Stone Mason COMMENTS/NOTES

The regular workday shall consist of 8 hours, between 6:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- When a 2 shift schedule (including a day shift) is established, the first, or day shift, shall be established on an 8 hour basis. The second shift shall be established on an 8 hour basis, and receive the regular rate plus 10%, inclusive of benefits
- When a three shift schedule is established, the first shift shall be established on an 8 hour basis, the second shift on a 7.5 hour basis, and the third shift on a 7 hour basis. The first shift shall receive the regular hourly rate, the second shift shall receive the regular rate plus 10%, inclusive of benefits, and the third shift shall receive the regular rate plus 15%, inclusive of benefits.
- When there is no day shift, and a second or third shift is established, it shall be established on an 8 hour basis. The second shift shall receive the regular rate plus 10%, inclusive of benefits, and the third shift shall receive the regular rate plus 15%, inclusive of benefits.
- When an irregular shift must be established, this shift shall receive the regular rate plus 10%, inclusive of benefits.

OVERTIME:

- The first 2 hours in excess of 8 per day, or before or after the regular workday that are not shift work, Monday through Friday, shall be paid at time and one-half the regular rate, inclusive of benefits. Any additional overtime shall be paid at double the regular rate, inclusive of benefits. The first 10 hours on Saturday shall be paid at time and one-half the regular rate, inclusive of benefits. Any additional overtime shall be paid at double the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.
- Saturday may be used as a make-up day for hours lost to inclement weather.
- When Bricklayers/Stone Masons work on Saturday with Laborers, and no other crafts are working on the project for the day, benefits may be paid at straight time. If other crafts are present, the applicable overtime rate for benefits shall be paid.

1/5/2017 Page 7 of 68

County - UNION

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays will be observed the following Monday.

1/5/2017 Page 8 of 68

County - UNION

Craft: Carpenter PREVAILING WAGE RATE

	11/01/16	05/01/17	11/01/17	05/01/18	11/01/18
Foreman	W53.42	W0.00	W0.00	W0.00	W0.00
	B30.44	B0.00	B0.00	B0.00	B0.00
	T83.86	T85.04	T86.04	T87.29	T88.54
Journeyman	W46.45	W0.00	W0.00	W0.00	W0.00
	B26.48	B0.00	B0.00	B0.00	B0.00
	T72.93	T74.23	T75.23	T76.48	T77.73

Craft: Carpenter APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
Yearly	40%	55%	65%	80%	90%					
Benefit	57% of	Appren	1	Wage Rate	for all	intervals				

Ratio of Apprentices to Journeymen - 1:3

Craft: Carpenter COMMENTS/NOTES

FOREMAN REQUIREMENTS:

- When there are 2 or more Carpenters on a job, 1 shall be designated as a Foreman.
- When there are 21 or more Carpenters on a job, 2 shall be designated as Foremen.

The regular workday shall consist of 8 hours, starting between 7:00 AM and 9:00 AM.

SHIFT DIFFERENTIALS:

- When a 2 shift schedule (including a day shift) is established, the day shift shall be established on an 8 hour basis. The second shift shall be established on an 8 hour basis, and receive the regular rate plus 15%, inclusive of benefits.
- When a three shift schedule is established, the first shift shall be established on an 8 hour basis, the second shift on a 7.5 hour basis, and the third shift on a 7 hour basis. The first shift shall receive the regular hourly rate, the second shift shall receive the regular rate plus 15% and the third shift shall receive the regular rate plus 20%, inclusive of benefits.
- When there is no day shift, and a second or third shift is established, it shall be established on an 8 hour basis. The second shift shall receive the regular rate plus 15% and the third shift shall receive the regular rate plus 20%, inclusive of benefits.

OVERTIME:

- All hours in excess of 8 per day, or before or after an established shift that are not shift work, and all hours on Saturdays shall be paid at time and one-half the hourly rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the hourly rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday to Thursday, at straight time. Friday may be used as a make-up day for a day lost due to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 9 of 68

County - UNION

Craft: Carpenter - Resilient Flooring PREVAILING WAGE RATE

	11/01/16	05/01/17	11/01/17	05/01/18	11/01/18
Foreman	W53.42	W0.00	W0.00	W0.00	W0.00
	B30.44	B0.00	B0.00	B0.00	B0.00
	T83.86	T85.04	T86.04	T87.29	T88.54
Journeyman	W46.45	W0.00	W0.00	W0.00	W0.00
	B26.48	B0.00	B0.00	B0.00	B0.00
	T72.93	T74.23	T75.23	T76.48	T77.73

Craft: Carpenter - Resilient Flooring APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
Yearly	40%	55%	65%	80%	90%					
Benefit	57%	of	Appren	tice	Wage Rate	for all	intervals			

Ratio of Apprentices to Journeymen - *

Craft: Carpenter - Resilient Flooring

COMMENTS/NOTES

FOREMAN REQUIREMENTS:

- On any job where there are 4 or more Carpenters of Resilient Flooring, 1 must be designated a Foreman.

FOR SYNTHETIC TURF INSTALLATION ONLY:

- The rate shall be 90% of the wage and benefit rate.

The regular workday consists of 8 hours, starting between 6:00 AM and 9:00 AM.

SHIFT DIFFERENTIALS:

- When a 2 shift schedule (including a day shift) is established, the day shift, shall be established on an 8 hour basis. The second shift shall be established on an 8 hour basis, and receive the regular wage rate plus 15%.
- When a three shift schedule is established, the first shift shall be established on an 8 hour basis, the second shift on a 7.5 hour basis, and the third shift on a 7 hour basis. The first shift shall receive the regular wage rate, the second shift shall receive the regular wage rate plus 15% and the third shift shall receive the regular wage rate plus 20%.
- When there is no day shift, and a second or third shift is established, it shall be established on an 8 hour basis. The second shift shall receive the regular wage rate plus 15% and the third shift shall receive the regular wage rate plus 20%.

OVERTIME:

- Hours in excess of 8 per day or 40 per week, or before or after the regular workday, Monday through Friday, shall be paid at time and one-half the wage rate. Saturday may be used as a make-up day, at straight time, up to 8 hours, for hours lost to reasons beyond the control of the employer, up to a total of 40 hours per week; hours in excess of 8 on Saturday shall then be paid at time and one-half the wage rate. If Saturday is not a make-up day, all hours on Saturday shall be paid at time and one-half the wage rate. All hours on Sundays and holidays shall be paid at double the wage rate.
- Four 10-hour days may be worked, Monday to Thursday, at straight time. Friday may be used as a make-up day for hours lost to reasons beyond the control of the employer. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the wage rate.

1/5/2017 Page 10 of 68

^{* 1} apprentice shall be allowed to every 2 journeymen or major fraction therof. No more than 3 apprentices on any one job or project.

County - UNION

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays will be observed the following Monday.

1/5/2017 Page 11 of 68

County - UNION

Craft: Cement Ma	ason	PREVAILING	WAGE RATI	E					
See "B	ricklayer, Stone Ma	ason" Rates							
Craft: Cement Ma	ason	APPRENTICE	RATE SCHI	EDULE					
INTERVAL		PERIOD AND RAT	ES						
Ratio of Apprentice	es to Journeymen -	1:4		•					
Craft: Cement Mason COMMENTS/NOTES									
See "Bricklayer, Stone Mason" Rates									

1/5/2017 Page 12 of 68

County - UNION

Craft: Diver PREVAILING WAGE RATE

	11/29/16	05/01/17	11/01/17	05/01/18	11/01/18
Diver	W56.34	W0.00	W0.00	W0.00	W0.00
	B44.37	B0.00	B0.00	B0.00	B0.00
	T100.71	T101.91	T103.11	T104.36	T105.61
Tender	W44.60	W0.00	W0.00	W0.00	W0.00
	B44.37	B0.00	B0.00	B0.00	B0.00
	T88.97	T90.17	T91.37	T92.62	T93.87

Craft: Diver COMMENTS/NOTES

NOTE: All dive crews must consist of a Tender, a Diver, and a standby Diver (standby Diver is the same rate as a Diver).

DEPTH & PENETRATION RATES: Divers shall be paid the following depth and penetration rates, in addition to the regular hourly rate, when applicable:

AIR DIVES: MIXED GAS DIVES:

0-59 feet: No additional wage 60-74 feet: + \$0.25 per foot 75-125 feet: + \$0.78 per foot 126-200 feet: + \$2.00 per foot

PENETRATION DIVES:

126-200 feet: + \$1.50 per foot 201-275 feet: + \$1.75 per foot 276-350 feet: + \$2.00 per foot 351-425 feet: + \$2.50 per foot

OVERTIME:

Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Presidential Election Day, Thanksgiving Day, Christmas Day. Veterans' Day may be switched with the day after Thanksgiving.

1/5/2017 Page 13 of 68

County - UNION

Craft: Dockbuilder PREVAILING WAGE RATE

	11/29/16	05/01/17	11/01/17	05/01/18	11/01/18
Foreman	W51.29 B44.37 T95.66	W0.00 B0.00 T96.79	W0.00 B0.00 T97.99	W0.00 B0.00 T99.24	W0.00 B0.00 T100.49
Foreman (Concrete Form Work)	W50.14 B31.56 T81.70	W0.00 B0.00 T82.90	W0.00 B0.00 T84.10	W0.00 B0.00 T85.35	W0.00 B0.00 T86.60
Journeyman	W44.60 B44.37 T88.97	W0.00 B0.00 T90.17	W0.00 B0.00 T91.37	W0.00 B0.00 T92.62	W0.00 B0.00 T93.87
Journeyman (Concrete Form Work)	W43.60 B31.56 T75.16	W0.00 B0.00 T76.36	W0.00 B0.00 T77.56	W0.00 B0.00 T78.81	W0.00 B0.00 T80.06

Craft: Dockbuilder APPRENTICE RATE SCHEDULE

INTERVAL	PERIOD AND RATES									
Yearly	17.84	22.30	28.99	35.68						
Benefit	29.95	for all	intervals		Concrete	Form	Only	= 21.81	for all	intervals

Ratio of Apprentices to Journeymen - *

* When there are 4 or fewer Dockbuilders on a job, no more than 1 may be an apprentice. When there are 5 or more Dockbuilders, there may be 1 apprentice for every 5 Dockbuilders.

Craft: Dockbuilder COMMENTS/NOTES

CREOSOTE HANDLING:

When handling creosote products on land piledriving, floating marine construction, and construction of wharves, the worker shall receive an additional \$0.25 per hour.

HAZARDOUS WASTE WORK:

- Hazardous waste removal work on a state or federally designated hazardous waste site where Level A, B, or C personal protection is required: an additional 20% of the hourly rate, per hour.
- Hazardous waste removal work in Level D, or where personal protection is not required: an additional \$1.00 per hour.

CERTIFIED WELDER: When required on the job by the project owner, a Certified Welder shall receive an additional \$1.00 per hour.

FOREMAN REQUIREMENTS:

The first Dockbuilder on the job shall be designated a Foreman.

OVERTIME:

Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.

1/5/2017 Page 14 of 68

County - UNION

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Presidential Election Day, Thanksgiving Day, Christmas Day. Veterans' Day may be switched with the day after Thanksgiving.

1/5/2017 Page 15 of 68

County - UNION

Craft: Drywall Finisher PREVAILING WAGE RATE

		ı
	05/01/16	05/01/17
Foreman	W42.55	W44.30
	B23.10	B22.60
	T65.65	T66.90
General Foreman	W44.45	W46.20
	B23.10	B22.60
	T67.55	T68.80
Journeyman	W38.75	W40.50
	B23.10	B22.60
	T61.85	T63.10

Craft: Drywall Finisher APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
4 Months	30%	40%	50%	60%	70%	75%	80%	85%	90%	
Benefits	Intervals	1 to 3 =	9.85	Intervals	4 to 6 =	12.28	Intervals	7 to 9 =	14.95	

Ratio of Apprentices to Journeymen - 1:4

Craft: Drywall Finisher COMMENTS/NOTES

The regular workday shall consist of 8 hours between 7:00 AM and 5:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.
- When 3 shifts are worked, the second shift shall receive 8 hours pay for 7.5 hours of work, and the third shift shall receive 8 hours pay for 7 hours of work.
- Shift work must run for a minimum of 5 consecutive workdays.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays shall be paid at time and one -half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.
- Saturday or Sunday may be used to make up a day lost to inclement weather, at straight time.

RECOGNIZED HOLIDAYS: New Year's Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Saturday holiday observed the preceding Friday. Sunday holiday observed the following Monday.

1/5/2017 Page 16 of 68

County - UNION

Craft: Electrician PREVAILING WAGE RATE

	05/30/16	05/29/17	05/28/18
Cable Splicer	W58.71	W60.08	W61.52
	B33.74	B34.53	B35.35
	T92.45	T94.61	T96.87
Foreman	W59.77	W61.17	W62.64
	B34.34	B35.15	B35.98
	T94.11	T96.32	T98.62
Journeyman	W53.37	W54.62	W55.93
	B30.67	B31.39	B32.13
	T84.04	T86.01	T88.06

Craft: Electrician APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
Yearly	40%	49%	58%	68%	80%		of Jour	neyman	Wage	Rate
Benefit	40%	49%	58%	68%	80%		of Jour	neyman	Benefit	Rate

Ratio of Apprentices to Journeymen - 2:3

Craft: Electrician COMMENTS/NOTES

THESE RATES ALSO APPLY TO THE FOLLOWING:

- -All burglar and fire alarm work.
- -All fiber optic work.
- -Teledata work in new construction.
- -Teledata work involving 16 Voice/Data Lines or more.

The regular workday shall be 8 hours, between 8:00 AM and 4:30 PM.

FOREMAN REQUIREMENTS:

- On any job where there are 1 to 10 Journeymen electricians, 1 shall be designated a Foreman.

SHIFT DIFFERENTIALS:

- Shift work must run for a minimum of 5 consecutive workdays.
- 2nd Shift (4:30 PM to 12:30 AM) shall receive 8 hours pay for 7.5 hours work + an additional 10% of the regular rate, per hour, inclusive of benefits.
- 3rd Shift (12:30 AM to 8:00 AM) shall receive 8 hours pay for 7 hours work + an additional 15% of the regular rate, per hour, inclusive of benefits.

OVERTIME:

Hours in excess of 8 per day, or outside of the regular workday, Monday through Friday, and all hours on Saturdays, shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.

1/5/2017 Page 17 of 68

County - UNION

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 18 of 68

County - UNION

Craft: Electrician - Teledata (15 Voice/Data Lines & Less)

PREVAILING WAGE RATE

	11/01/16
Master	W52.18
Technician/General	B28.69
Foreman	T80.87
Senior Technician/Lead	W47.77
Foreman	B26.26
(21-30 Workers on Job)	T74.03
Technician A/Foreman (11-20 Workers on Job)	W45.76 B25.16 T70.92
Technician B/Working	W43.75
Foreman	B24.06
(4-10 Workers on Job)	T67.81
Technician C/Journeyman (1-3 Workers on Job)	W40.14 B22.07 T62.21

Craft: Electrician - Teledata (15 Voice/Data Lines & Less)

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
6 Months	20.14	21.48	23.72	26.41	29.54	32.23	35.36	38.49		
Benefits	7.85	8.38	9.25	10.29	11.52	12.56	13.79	15.01		

Ratio of Apprentices to Journeymen - 2:3

Craft: Electrician - Teledata (15 Voice/Data Lines & Less)

COMMENTS/NOTES

APPRENTICE RATE SCHEDULE FOR THOSE APPRENTICES ENTERING PROGRAM AFTER 10-31-14:

INTERVAL PERIOD AND RATES

6 Months 17.90 19.25 21.48 24.17 27.30 29.99 33.12 36.26 Benefits 6.98 7.51 8.38 9.42 10.65 11.69 12.92 14.13

NOTES:

- These rates are for service, maintenance, moves, and/or changes affecting
- 15 Voice/Data (teledata) lines or less. These rates may NOT be used for any teledata work in new construction (including additions) or any fiber optic work.
- The number of Teledata workers on the jobsite is the determining factor for which Foreman category applies .

The regular workday shall be 8 hours, between 8:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- Shift work must run for a minimum of 5 consecutive workdays.

1/5/2017 Page 19 of 68

County - UNION

- 2nd Shift (4:30 PM to 12:30 AM) shall receive 8 hours pay for 7.5 hours work + an additional 10% of the regular rate, per hour, inclusive of benefits.
- 3rd Shift (12:30 AM to 8:00 AM) shall receive 8 hours pay for 7 hours work + an additional 15% of the regular rate, per hour, inclusive of benefits.

OVERTIME:

Hours in excess of 8 per day, or outside of the regular workday, Monday through Friday, and all hours on Saturdays, shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 20 of 68

County - UNION

Craft:	Electrician - Teledata (16 Instruments & More)	PREVAILING WAGE RATE
	See "Electrician" Rates	
Craft:	Electrician - Teledata (16 Instruments & More)	COMMENTS/NOTES
See	ELECTRICIAN Rates	

1/5/2017 Page 21 of 68

County - UNION

Craft: Electrician- Outside Commercial

PREVAILING WAGE RATE

		1	1
	05/30/16	05/29/17	05/28/18
Cable Splicer	W58.99	W60.37	W61.82
	B33.46	B34.24	B35.06
	T92.45	T94.61	T96.88
Certified Welder	W56.31	W57.62	W59.01
	B31.94	B32.68	B33.47
	T88.25	T90.30	T92.48
Equipment Operator	W53.63	W54.88	W56.20
	B30.42	B31.13	B31.88
	T84.05	T86.01	T88.08
Foreman (1-10	W60.07	W61.47	W62.94
Journeyman workers on	B34.07	B34.86	B35.70
job)	T94.14	T96.33	T98.64
Foreman (11-20	W61.67	W63.11	W64.63
Journeyman workers on	B34.98	B35.79	B36.66
job)	T96.65	T98.90	T101.29
General Foreman (21-30	W63.28	W64.76	W66.32
Journeyman workers on	B35.89	B36.73	B37.61
job)	T99.17	T101.49	T103.93
General Foreman (31-60	W68.65	W70.25	W71.94
Journeyman workers on	B38.94	B39.84	B40.80
job)	T107.59	T110.09	T112.74
General Foreman (61+	W69.72	W71.34	W73.06
Journeyman workers on	B39.54	B40.46	B41.44
job)	T109.26	T111.80	T114.50
Groundman	W32.18	W32.93	W33.72
	B18.26	B18.68	B19.13
	T50.44	T51.61	T52.85
Journeyman	W53.63	W54.88	W56.20
Lineman/Technician	B30.42	B31.13	B31.88
	T84.05	T86.01	T88.08
Sub-Foreman	W60.07	W61.47	W62.94
	B34.07	B34.86	B35.70
	T94.14	T96.33	T98.64

1/5/2017 Page 22 of 68

County - UNION

Craft: Electrician- Outside Commercial APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
1000 Hours	60%	65%	70%	75%	80%	85%	90%				
Benefits	56.4% of	Journey	man	wage	+ \$.01						

Craft: Electrician- Outside Commercial

COMMENTS/NOTES

EFFECTIVE 5-30-16- The apprentice benefit rate shall be 56.7% + \$.01.

EFFECTIVE 5-29-17- The apprentice benefit rate shall be 56.7% + \$.01.

EFFECTIVE 5-28-18- The apprentice benefit rate shall be 56.7% + \$.01.

The regular worday shall be 8 hours, between 8:00 AM and 4:30 PM.

FOREMAN REQUIREMENTS:

On jobs where there are 2 Journeymen, one shall be a Foreman. The following number of Foreman, General Foreman, Assistant General Foreman and Sub-Foreman shall be required with respect to number of Journeymen on site:

2-10 Journeymen (1 Foreman)

11-20 Journeymen (1 Foreman and 1 Sub-Foreman)

21-30 Journeymen (1 Foreman and 2 Sub-Foremen)

SHIFT DIFFERENTIALS:

Shift work must run for a minimum of 5 consecutive workdays.

2nd Shift (4:30 PM to 12:30 AM): 8 hrs. pay for 7.5 hrs. work + an additional 10% of the regular rate, inclusive of benefits.

3rd Shift (12:30 AM to 8:00 AM): 8 hrs. pay for 7 hrs. work + an additional 15% of the regular rate per hour, inclusive benefits.

OVERTIME:

Hours in excess of 8 per day, or outside of the regular workday, Monday through Friday, and all hours on Saturdays, shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS:

New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day and Christmas Day.

1/5/2017 Page 23 of 68

^{*} FOR UTILITY WORK PLEASE SEE STATEWIDE RATES

County - UNION

Craft: Electrician-Utility Work (North) PR	REVAILING WAGE RATE
--	---------------------

Rates are located in the "Statewide" rate package

Craft: Electrician-Utility Work (North)

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
6 Months	60%	65%	70%	75%	80%	85%	90%				
Benefits	62.5% of	Appren	tice	Wage	Rate	for all	intervals				

Craft: Electrician-Utility Work (North) COMMENTS/NOTES

Electrician-Utility Work (North) rates are located in the "Statewide" rate package.

1/5/2017 Page 24 of 68

County - UNION

Craft: Electrician-Utility Work (South) PREVAILING W	AGE	RATE
--	-----	------

Rates are located in the "Statewide" rate package

Craft: Electrician-Utility Work (South)

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
6 Months	27.37	29.65	31.93	34.21	36.49	38.77	41.05				
Benefits	24.01	25.34	26.73	28.09	29.43	30.80	32.18				

Craft: Electrician-Utility Work (South) COMMENTS/NOTES

Electrician-Utility Work (South) rates are located in the "Statewide" rate package.

1/5/2017 Page 25 of 68

County - UNION

Craft: Elevator Constructor PREVAILING WAGE RATE

	03/17/16	03/17/17	03/17/18
Journeyman	W60.96	W62.64	W64.48
	B39.77	B41.56	B43.36
	T100.73	T104.20	T107.84

Craft: Elevator Constructor APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
Yearly	27.22	33.53	39.62	45.72							
Benefits	31.75	32.88	34.41	35.93							

Ratio of Apprentices to Journeymen - 1:1

Craft: Elevator Constructor COMMENTS/NOTES

The regular workday shall consist of either 7 or 8 hours to be established at the beginning of the project, between 7:00 AM and 4:30 PM.

OVERTIME:

For all hours worked before or after the regular workday, Monday through Friday, and all hours on Saturday and Sunday, shall be paid at double the hourly rate. Holiday pay is one days wages (8 hours) plus double the hourly rate for all hours worked.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Good Friday, Memorial Day, July 4th, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day and the day after, Christmas Day. Saturday holidays shall be observed on the previous Friday and Sunday holidays shall be observed on the following Monday.

1/5/2017 Page 26 of 68

County - UNION

Craft: Elevator Modernization & Service PREVAILING WAGE RATE

	03/17/16	03/17/17	03/17/18
Journeyman	W47.91	W49.14	W50.49
	B38.17	B39.91	B41.66
	T86.08	T89.05	T92.15

Craft: Elevator Modernization & Service

INTERVAL		PERIOD AND RATES									
Yearly	27.22	26.35	31.14	35.93							
Benefits	31.68	31.99	33.37	34.74							

APPRENTICE RATE SCHEDULE

Ratio of Apprentices to Journeymen - 1:1

Craft: Elevator Modernization & Service COMMENTS/NOTES

MODERNIZATION (addition, replacement, refurbishing, relocation, or changes in design or appearance, of elevator equipment in existing buildings):

- The regular workday consists of 8 hours, between 7:00 AM and 4:30 PM.
- Overtime:

Hours in excess of 8 per day, or before or after the regular workday, Monday through Friday, and all hours on Saturday and Sunday shall be paid at time and one-half the hourly rate. Holiday pay is one days wages (8 hours) plus time and one-half the hourly rate for all hours worked.

SERVICE (repair or replacement of parts for the purpose of maintaining elevator equipment in good operating condition):

- The regular workday consists of 8 hours, between 6:00 AM and 6:00 PM.
- Overtime:

Hours in excess of 8 per day, or before or after the regular workday, Monday through Friday, and all hours on Saturday shall be paid at time and one-half the hourly rate. All hours on Sunday and holidays shall be paid at double the hourly rate.

RECOGNIZED HOLIDAYS (Modernization and Service): New Year's Day, Presidents' Day, Good Friday, Memorial Day, July 4th, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day and the day after, Christmas Day. Saturday holidays shall be observed on the previous Friday and Sunday holidays shall be observed on the following Monday.

1/5/2017 Page 27 of 68

County - UNION

Craft: Glazier PREVAILING WAGE RATE

	06/20/16
Foreman	W47.39
	B23.26
	T70.65
General Foreman	W49.39
	B23.50
	T72.89
Journeyman	W43.39
	B22.78
	T66.17
I .	1

Craft: Glazier APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
4 Months	30%	40%	50%	60%	70%	75%	80%	85%	90%		
Benefits	Intervals	1 to 3 =	6.51	Intervals	4 to 6 =	9.33	Intervals	7 to 9 =	11.67		

Ratio of Apprentices to Journeymen - 1:4

Craft: Glazier COMMENTS/NOTES

APPRENTICE RATE SCHEDULE FOR THOSE APPRENTICES ENTERING PROGRAM AS OF 5-1-14:

INTERVAL PERIOD AND RATES

6 Months 50% 55% 60% 65% 70% 75% 80% 90% Benefits 8.10 8.10 10.34 10.34 11.51 11.51 14.62 14.62

Hazard/Height Pay: +\$1.00 per hour

FOREMAN REQUIREMENTS:

- When there are 4 or more Glaziers on a job, 1 must be designated a Foreman.
- When there are 15 or more Glaziers on a job, 1 must be designated a General Foreman.

The regular workday shall consist of 8 hours, between 7:00 AM and 5:30 PM, Monday to Friday.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.
- When 3 shifts are worked, the second shift shall receive 8 hours pay for 7.5 hours of work, and the third shift shall receive 8 hours pay for 7 hours of work.

OVERTIME:

Hours in excess of 8 per day, or before or after the regular workday Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the regular rate. All hours on Sundays and holidays shall be paid at double the regular rate.

1/5/2017 Page 28 of 68

County - UNION

RECOGNIZED HOLIDAYS: New Year's Day, Memorial Day, July 4th, Labor Day, General Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Saturday holiday observed the preceding Friday. Sunday holiday observed the following Monday.

1/5/2017 Page 29 of 68

County - UNION

Craft: Heat & Frost Insulator PREVAILING WAGE RATE

	10/17/16
Foreman	W52.52
	B30.17
	T82.69
General Foreman	W55.07
	B31.28
	T86.35
Journeyman	W51.24
	B29.61
	T80.85

Craft: Heat & Frost Insulator APPRENTICE RATE SCHEDULE

INTERVAL	PERIOD AND RATES									
Yearly	23.77	28.19	34.05	39.96						
Benefits	17.83	21.08	23.21	25.16						

Ratio of Apprentices to Journeymen - 1:3

Craft: Heat & Frost Insulator COMMENTS/NOTES

NOTE: These rates apply to the installing of insulation on hot and cold mechanical systems.

The regular workday shall be 8 hours between 8:00 AM and 4:30 PM.

SHIFT DIFFERENTIAL:

- Shift work must run for a minimum of 5 consecutive workdays.
- Second Shift shall work 7.5 hours and receive 8 hours pay, at the regular rate, plus 25% per hour.
- Third Shift shall work 7 hours and receive 8 hours pay, at the regular rate, plus 30% per hour.

OVERTIME:

The first 2 hours in excess of 8 per day, hours outside of the regular workday Monday through Friday that are not shift work, and the first 10 hours on Saturday, shall be paid at time and one-half the regular rate, inclusive of benefits. All hours in excess of 10 per day, and all hours on Sunday and holidays (except Labor Day) shall be paid at double the regular rate, inclusive of benefits. All hours on Labor Day shall be paid at triple the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Presidential Election Day, Thanksgiving Day and Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 30 of 68

County - UNION

Craft: Heat & Frost Insulator - Asbestos Worker

PREVAILING WAGE RATE

	10/17/16
Asbestos Helper	W33.52
Abatement	B22.69
	T56.21
Firestop/Hazmat	W26.93
	B9.25
	T36.18
Foreman	W52.52
	B30.17
	T82.69

Craft: Heat & Frost Insulator - Asbestos Worker

APPRENTICE RATE SCHEDULE

INTERVAL	PERIOD AND RATES									
	SEE	НЕАТ &	FROST	INSULAT						
				Oit						

Ratio of Apprentices to Journeymen - 1:3

Craft: Heat & Frost Insulator - Asbestos Worker

COMMENTS/NOTES

NOTE: These rates apply only to the removal of insulation materials/asbestos from mechanical systems, including containment erection and demolition, and placing material in appropriate containers.

The regular workday shall be 8 hours between 8:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- Shift work must run for a minimum of 5 consecutive workdays.
- The second shift shall work 7.5 hours and receive 8 hours pay at the regular rate, plus 25% per hour.
- The third shift shall work 7 hours and receive 8 hours pay at the regular rate, plus 30% per hour.

OVERTIME: The first 2 hours in excess of 8 per day, hours outside of the regular workday Monday through Friday that are not shift work, and the first 10 hours on Saturday, shall be paid at time and one-half the regular rate, inclusive of benefits. All hours in excess of 10 per day, and all hours on Sunday and holidays (except Labor Day) shall be paid at double the regular rate, inclusive of benefits. All hours on Labor Day shall be paid at triple the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Presidential Election Day, Thanksgiving Day and Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 31 of 68

County - UNION

Craft: Ironworker PREVAILING WAGE RATE

	08/02/16	07/01/17
Rod /Fence Foreman	W42.24	W0.00
	B44.27	B0.00
	T86.51	T88.51
Rod/Fence Journeyman	W39.24	W0.00
	B44.27	B0.00
	T83.51	T85.51
Structural Foreman	W44.54	W0.00
	B44.27	B0.00
	T88.81	T90.56
Structural Journeyman	W41.54	W0.00
	B44.27	B0.00
	T85.81	T87.56

Craft: Ironworker APPRENTICE RATE SCHEDULE

INTERVAL	PERIOD AND RATES									
6 Months	50%	60%		Yearly	70%	80%	90%			

Ratio of Apprentices to Journeymen - 1:4

Craft: Ironworker COMMENTS/NOTES

HAZARDOUS WASTE WORK: On hazardous waste removal work on a state or federally designated hazardous waste site where the Ironworker is required to wear Level A,B, or C personal protection: +\$3.00 per hour

The regular workday consists of 8 hours between 6:00 AM and 4:30 PM.

FOREMAN REQUIREMENTS:

When there are 2 or more Ironworkers on a job, 1 shall be designated a Foreman.

SHIFT DIFFERENTIALS:

- When a 2 shift schedule is established, the first, or day shift, shall be established on an 8 hour basis. The second shift shall be established on an 8 hour basis, and receive the regular rate plus 15%.
- When a three shift schedule is established, the first shift shall be established on an 8 hour basis, the second shift on a 7.5 hour basis, and the third shift on a 7 hour basis. The first shift shall receive the regular hourly rate, the second shift shall receive the regular rate plus 15%, and the third shift shall receive the regular rate plus 20%.
- When there is no day shift, and a second or third shift is established, it shall be established on an 8 hour basis.
- When an irregular shift is established for the Ironworker (Structural) classification, the rate shall be paid at time and one-half the regular rate, inclusive of benefits. When an irregular shift is established for the Rod/Fence classification, the shift shall be established on an 8 hour basis and receive the regular rate, plus 20%.

OVERTIME:

1/5/2017 Page 32 of 68

County - UNION

- All hours in excess of 8 per day, or before or after an established shift that are not shift work, and all hours on Saturday, shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sunday and holidays shall be paid at double the hourly rate, inclusive of benefits. Saturday may be used as a make-up day for a day lost to inclement weather. If Saturday is not a make-up day, all hours on Saturday shall be paid at time and one-half the hourly rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday to Thursday, at straight time. Friday may be used as a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 33 of 68

County - UNION

Craft: Laborer - Asbestos & Hazardous Waste Removal

PREVAILING WAGE RATE

	04/07/16
Journeyman (Handler)	W29.87
	B22.92
	T52.79

Craft: Laborer - Asbestos & Hazardous Waste Removal

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES										
Yearly	17.92	20.91	23.90	26.88								
Benefits	21.27	for	all	intervals								

Ratio of Apprentices to Journeymen - *

Craft: Laborer - Asbestos & Hazardous Waste Removal

COMMENTS/NOTES

NOTE: These rates apply to work in connection with Asbestos, Radiation, Hazardous Waste, Lead, Chemical, Biological, Mold Remediation and Abatement.

The regular workday shall be 8 hours between 6:00 AM and 6:00 PM.

OVERTIME:

- Hours in excess of 8 per day, Monday through Saturday, and all hours on Sunday and holidays shall be paid at time and one-half the regular rate.
- When the owner (Public Body) mandates that work is to be performed on Sunday, those hours may be worked at straight time, up to 8 hours per day, up to 40 hours per week.
- Benefits on ALL overtime hours shall be paid at straight time.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Good Friday, Easter, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 34 of 68

^{*} Ratio of apprentices to journeymen shall not be more than one apprentice for the first journeyman and no more than (1) apprentice for each additional three (3) journeymen.

County - UNION

Craft: Laborer - Building PREVAILING WAGE RATE

	11/01/16	05/01/17	11/01/17	05/01/18
Class A Journeyman	W31.55	W0.00	W0.00	W0.00
	B27.22	B0.00	B0.00	B0.00
	T58.77	T59.67	T60.72	T62.57
Class B Journeyman	W31.05	W0.00	W0.00	W0.00
	B27.22	B0.00	B0.00	B0.00
	T58.27	T59.17	T60.22	T62.07
Class C Journeyman	W26.43	W0.00	W0.00	W0.00
	B27.22	B0.00	B0.00	B0.00
	T53.65	T54.55	T55.60	T57.45
Foreman	W35.46	W0.00	W0.00	W0.00
	B27.22	B0.00	B0.00	B0.00
	T62.68	T63.58	T64.63	T66.48
General Foreman	W39.38	W0.00	W0.00	W0.00
	B27.22	B0.00	B0.00	B0.00
	T66.60	T67.50	T68.55	T70.40

Craft: Laborer - Building APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
6 Months	60%	50% 70% 80% 90%									
Benefit	23.97	23.97	23.97	23.97							

Ratio of Apprentices to Journeymen - *

Craft: Laborer - Building

COMMENTS/NOTES

CLASS A: Specialist laborer including mason tender or concrete pour crew; scaffold builder (scaffolds up to 14 feet in height); operator of forklifts, Bobcats (or equivalent machinery), jack hammers, tampers, motorized tampers and compactors, vibrators, street cleaning machines, hydro demolition equipment, riding motor buggies, conveyors, burners; and nozzlemen on gunite work.

CLASS B: Basic laborer - includes all laborer work not listed in Class A or Class C.

CLASS C: Janitorial-type light clean-up work associated with the TURNOVER of a project, or part of a project, to the owner. All other clean-up work is Class B.

The regular workday shall be 8 hours between 6:00 AM and 6:00 PM.

SHIFT DIFFERENTIALS:

- Shift work must run for a minimum of 5 consecutive workdays.
- When a 2-shift schedule is worked, including a day shift, both shifts shall be establised on the basis of 8 hours pay for 8 hours worked. The second shift shall receive the regular rate plus an additional 10%.
- When a 3-shift schedule is worked, the day shift shall be established on the basis of 8 hours pay for 8 hours worked, the second shift shall be established on the basis of 8 hours pay for 7.5 hours worked, and the third shift shall be established

Page 35 of 68

^{*} Ratio of apprentices to journeymen shall not be more than one apprentice for the first journeyman and no more than (1) apprentice for each additional three (3) journeymen.

County - UNION

on the basis of 8 hours pay for 7 hours worked. The day shift shall receive the regular rate, the second shift shall receive the regular rate plus an additional 10%, and the third shift shall receive the regular rate plus an additional 15%.

- When a second or third shift is worked with no day shift, the second or third shift shall be established on the basis of 8 hours pay for 8 hours worked. The second shift shall receive the regular rate plus an additional 10%, and the third shift shall receive the regular rate plus an additional 15%.

OVERTIME:

- Hours in excess of 8 per day, or outside the regular workday that are not shift work, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the regular rate. Saturday may be used as a make-up day (paid at straight time) for a day lost to inclement weather, or for a holiday that is observed during the work week, Monday through Friday. All hours on Sundays and holidays shall be paid at double the regular rate.
- Four 10-hour days may be worked Monday to Thursday, at straight time, with Friday used a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the regular rate.
- Benefits on ALL overtime hours shall be paid at time and one-half.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 36 of 68

County - UNION

Craft: Laborer - Heavy & General	PREVAILING WAGE RATE
----------------------------------	----------------------

Rates are located in the "Statewide" rate package

Craft: Laborer - Heavy & General

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES										
1000 Hours	60% 70% 80% 90%											
Benefit	18.78	for	all	intervals								

Ratio of Apprentices to Journeymen - *

Craft: Laborer - Heavy & General

COMMENTS/NOTES

Heavy & General Laborer rates are located in the "Statewide" rate package.

With respect to the APPRENTICE RATE SCHEDULE, the following shall apply:

On 3-1-17- benefits shall be \$19.53.

1/5/2017 Page 37 of 68

^{*} No more than 1 apprentice for the first journeyman and no more than 1 apprentice for each additional 3 journeymen.

County - UNION

Craft: Laborer-Residential and Modular Construction

PREVAILING WAGE RATE

	01/05/17	04/01/17
* Skilled Tradesman (only	W25.25	W25.55
applies to Modular	B5.45	B5.45
Construction)	T30.70	T31.00
Foreman (person directing	W25.25	W25.55
crew, regardless of his	B5.45	B5.45
skill classification)	T30.70	T31.00
Laborer	W21.25	W21.55
	B5.45	B5.45
	T26.70	T27.00
Laborer (for single family	W16.55	W17.05
and stand-alone duplex	B2.95	B2.95
owned by single owner)	T19.50	T20.00

Craft: Laborer-Residential and Modular Construction

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
As shown	800 hours	0 hours 600 hours 600 hours									
wage & benefits	70%	80%	90%								

Ratio of Apprentices to Journeymen-

One (1) apprentice shall be allowed for the first journeyman on site and no more than one (1) additional apprentice for each additional three (3) journeymen on site.

Craft: Laborer-Residential and Modular Construction

COMMENTS/NOTES

* SKILLED TRADESMAN-

any worker doing work not typically done by a Building Laborer. Some examples are installing interior doors, sheet rock, hooking up appliances, installing light fixtures, installing railing systems, etc. Please note where local building codes require that certain work be performed under the supervision of a licensed tradesman (i.e. Plumber, Electrician, etc.) Laborers shall work under such supervision.

RESIDENTIAL CONSTRUCTION- All residential construuction (not commercial), single-family, stand-alone duplex houses, townhouses and multi-family buildings of not more than four (4) floors, including basement levels. Please note the construction must be residential in nature for ALL FLOORS at an elevation of no more than FOUR (4) FLOORS, INCLUDING BASEMENT. In addition, barracks and dormitories are not considered residential projects.

MODULAR RESIDENTIAL CONSTRUCTION- all aspects of modular residential construction (not commercial) at the site of installation of structures of no more than four (4) stories, including all excavation and site preparation, footings and foundation systems whether poured on-site or prefabricated, all underground waterproofing, underground utilities, concrete slabs, sidewalks, driveways, paving, hardscape and landscaping. Please note the construction must be residential in nature for ALL STORIES at an elevation of no more than FOUR (4) STORIES. All work performed by the Set Crew (the crew of workers who set the modular boxes on the foundation), including the rigging, setting, attaching and assembly of all modules and structural members, preparation of the foundation to accept modules, such as sill plates, connection of all in-module and under-module connections including, but not limited to, plumbing, electrical, HVAC, fire suppression, CATS,

1/5/2017 Page 38 of 68

County - UNION

telephone, television/internet, and fiber optic, the building or installation of any porches or decks regardless of material or method of construction, the on-site installation of, or completion of any roof system, doors, windows and fenestrations, including flashing, gutter and soffit systems, waterproofing, insulation and interior and exterior trim work, and painting. Please note that modular construction does not include on-site stick built construction, tip up construction or panel built construction.

The regular workday shall be 8 hours between 6:00 AM and 6:00 PM.

OVERTIME

Hours worked in excess of 8 per day/40 per week, Monday through Saturday, and all hours worked on Sunday and holidays shall be paid at time and one-half the hourly rate.

RECOGNIZED HOILDAYS:

New Year's Day, Martin Luther King Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day and Christmas Day.

1/5/2017 Page 39 of 68

County - UNION

Craft: Millwright PREVAILING WAGE RATE

	11/01/16
Foreman	W53.53 B31.65 T85.18
Journeyman	W46.55 B27.60 T74.15

Craft: Millwright APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES										
6 Months	40%	0% 45% 50% 55% 60% 65% 70% 75% 85% 95%								95%		
Benefits	58% of	Appren	tice	Wage	Rate	for all	intervals	+ \$.60				

Ratio of Apprentices to Journeymen - 1:3

Craft: Millwright COMMENTS/NOTES

FOREMAN REQUIREMENTS:

- When there are 2 or more Millwrights on a job, 1 shall be designated as a Foreman.
- When there are 21 or more Millwrights on a job, 2 shall be designated as Foremen.

The regular workday shall consist of 8 hours, starting between 7:00 AM and 9:00 AM.

SHIFT DIFFERENTIALS:

- When a 2 shift schedule (including a day shift) is established, the day shift shall be established on an 8 hour basis. The second shift shall be established on an 8 hour basis, and receive the regular rate plus 15%, inclusive of benefits.
- When a three shift schedule is established, the first shift shall be established on an 8 hour basis, the second shift on a 7.5 hour basis, and the third shift on a 7 hour basis. The first shift shall receive the regular hourly rate, the second shift shall receive the regular rate plus 15% and the third shift shall receive the regular rate plus 20%, inclusive of benefits.
- When there is no day shift, and a second or third shift is established, it shall be established on an 8 hour basis. The second shift shall receive the regular rate plus 15% and the third shift shall receive the regular rate plus 20%, inclusive of benefits.

OVERTIME:

- All hours in excess of 8 per day, or before or after an established shift that are not shift work, and all hours on Saturdays shall be paid at time and one-half the hourly rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the hourly rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday to Thursday, at straight time. Friday may be used as a make-up day for a day lost due to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays will be observed the following Monday.

1/5/2017 Page 40 of 68

County - UNION

Craft: Operating Engineer I	PREVAILING WAGE RATE
-----------------------------	----------------------

Rates are located in the "Statewide" rate package

Craft: Operating Engineer APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES										
Yearly	60%	9% 70% 80% 90%										

Ratio of Apprentices to Journeymen - *

Craft: Operating Engineer COMMENTS/NOTES

Operating Engineer rates are located in the "Statewide" rate package.

1/5/2017 Page 41 of 68

^{* 1} apprentice for each piece of heavy equipment. At least 10 pieces of heavy equipment or a minimum of 5 Operating Engineers must be on site.

County - UNION

Craft:	Operating Engineer - Field Engineer	PREVAILING WAGE RATE
--------	-------------------------------------	----------------------

Rates are located in the "Statewide" rate package

Craft: Operating Engineer - Field Engineer

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
Yearly	70%	75%	of Rod/	Chainman	Wage					
Yearly			80%	90%	Transit/	Instrument	man	Wage		

Ratio of Apprentices to Journeymen - *

Craft: Operating Engineer - Field Engineer

COMMENTS/NOTES

Operating Engineer - Field Engineer rates are located in the "Statewide" rate package.

1/5/2017 Page 42 of 68

^{*} No more than 1 Field Engineer Apprentice per Survey Crew.

County - UNION

Craft: Painter - Bridges PREVAILING WAGE RATE

	05/01/16	05/01/17
Foreman	W57.38	W61.13
	B26.92	B25.67
	T84.30	T86.80
General Foreman	W59.38	W63.13
	B26.92	B25.67
	T86.30	T88.80
Journeyman	W52.38	W56.13
	B26.92	B25.67
	T79.30	T81.80

Craft: Painter - Bridges APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
6 Months	40%	50%			60%	70%		80%	90%		
Benefits	Intervals	1 to 2 =	8.88	Intervals	3 to 4 =	10.81	Intervals	5 to 6 =	13.48		

Ratio of Apprentices to Journeymen - 1:4

Craft: Painter - Bridges COMMENTS/NOTES

These rates apply to: All bridges that span waterways, roadways, railways and canyons. All tunnels, overpasses, viaducts and all appurtenances.

FOREMEN REQUIREMENTS:

- When there are 4 or more Painters on a job, 1 shall be designated a Foreman.
- When there are 15 or more Painters on a job, 1 shall be designated a General Foreman.

The regular workday shall consist of 8 hours between 7:00 AM and 5:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays and Sundays shall be paid at time and one-half the regular rate. All hours on holidays shall be paid at double the regular rate.
- Saturday or Sunday may be used to make up a day lost to inclement weather, at straight time.
- Four 10-hour days may be worked, at straight time, Monday through Friday.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Saturday holiday observed the preceding Friday. Sunday holiday observed the following Monday.

1/5/2017 Page 43 of 68

County - UNION

Craft: Painter - Line Striping PREVAILING WAGE RATE

	12/29/16
Apprentice (1st year)	W24.45
	B10.75
	T35.20
Apprentice (2nd year)	W28.45
	B16.80
	T45.25
Foreman (Charge Person)	W36.60
	B17.08
	T53.68
Journeyman 1 (at least 1	W32.33
year of working exp. as a	B17.08
journeyman)	T49.41
Journeyman 2 (at least 2	W36.10
years of working exp. as a	B17.08
journeyman)	T53.18

Craft: Painter - Line Striping COMMENTS/NOTES

OVERTIME:

Hours in excess of 8 per day, Monday through Saturday, and all hours on Sundays and holidays shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans Day, Thanksgiving Day and Christmas Day. Veterans Day may be substituted for the day after Thanksgiving.

1/5/2017 Page 44 of 68

County - UNION

Craft: Painter - New Construction PREVAILING WAGE RATE

	05/01/16	05/01/17
Foreman	W42.26	W44.39
	B22.94	B22.35
	T65.20	T66.74
General Foreman	W46.10	W48.43
	B23.40	B22.81
	T69.50	T71.24
Journeyman	W38.42	W40.36
	B22.49	B21.90
	T60.91	T62.26

Craft: Painter - New Construction APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
4 Months	30%	40%	50%	60%	70%	75%	80%	85%	90%	
Benefits	Intervals	1 to 3 =	8.00	Intervals	4 to 6 =	10.00	Intervals	7 to 9 =	11.00	

Ratio of Apprentices to Journeymen - 1:4

Craft: Painter - New Construction COMMENTS/NOTES

APPRENTICE RATE SCHEDULE FOR THOSE APPRENTICES ENTERING PROGRAM ON 5-1-14:

INTERVAL PERIOD AND RATES

6 Months 40% 45% 55% 65% 70% 75% 80% 90% Benefits 8.00 8.00 10.00 10.00 11.00 11.00 14.00 14.00

Spraying, sandblasting, lead abatement, work on tanks or stacks, work performed above 3 stories or 30 feet in height, or using swing scaffolds requires an additional 10% of the wage rate.

FOREMEN REQUIREMENTS:

- When there are 4 or more Painters on a job, 1 shall be designated a Foreman.
- When there are 15 or more Painters on a job, 1 shall be designated a General Foreman.

The regular workday shall consist of 8 hours between 7:00 AM and 5:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.

OVERTIME:

- Hours in excess of 8 per day, or before or after the regular workday, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the regular rate. All hours on Sundays and holidays shall be paid at double the regular rate.

1/5/2017 Page 45 of 68

County - UNION

- Saturday or Sunday may be used to make up a day lost to inclement weather, at straight time.
- Four 10-hour days may be worked, at straight time, Monday through Friday.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day, July 4th, Labor Day, General Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 46 of 68

County - UNION

Craft: Painter - Repainting PREVAILING WAGE RATE

	05/01/16	05/01/17
Foreman	W31.59	W34.17
	B18.45	B18.45
	T50.04	T52.62
General Foreman	W34.45	W37.39
	B18.87	B18.45
	T53.32	T55.84
Journeyman	W28.74	W31.16
	B18.87	B18.45
	T47.61	T49.61

Craft: Painter - Repainting APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES										
	SEE	PAINTER	NEW	CONSTR	TION							

Ratio of Apprentices to Journeymen - 1:4

Craft: Painter - Repainting COMMENTS/NOTES

NOTE: These rates may only be used on jobs where no major alterations occur, and where not more than 3 other trades are present on the job, but may NOT, under any circumstances, be used for work on bridges, stacks, elevated tank, or generating stations.

Spraying, sandblasting, lead abatement, work on tanks or stacks, work performed above 3 stories or 30 feet in height, or using swing scaffolds requires an additional 10% of the wage rate.

FOREMEN REQUIREMENTS:

- When there are 4 or more Painters on a job, 1 shall be designated a Foreman.
- When there are 15 or more Painters on a job, 1 shall be designated a General Foreman.

OVERTIME:

- Hours in excess of 8 per day and 40 per week shall be paid at time and one-half the regular rate. All hours on Sundays and holidays shall be paid at double the regular rate.
- Four 10-hour days may be worked, at straight time, Monday through Sunday.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day, July 4th, Labor Day, General Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 47 of 68

County - UNION

Craft: Painter- Containment PREVAILING WAGE RATE

	05/01/16	05/01/17		
Journeyman	W33.43	W37.68		
	B23.92	B22.92		
	T57.35	T60.60		

Craft: Painter- Containment COMMENTS/NOTES

NOTE: These rates shall require no painting, but used in a supporting capacity only, such as wrapping, boxing, fencing, etc. on tanks.

The regular workday shall consist of 8 hours between 7:00 AM and 5:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays and Sundays shall be paid at time and one-half the regular rate. All hours on holidays shall be paid at double the regular rate.
- Four 10-hour days may be worked, at straight time, Monday through Friday.

RECOGNIZED HOLIDAYS: New Year's Day President's Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Saturday holiday observed the preceding Friday. Sunday holiday observed the following Monday.

1/5/2017 Page 48 of 68

County - UNION

Craft: Painter-Elevated Water Tanks

PREVAILING WAGE RATE

	05/01/16	05/01/17
Foreman	W47.17	W50.92
	B24.17	B22.92
	T71.34	T73.84
General Foreman	W49.17	W52.92
	B24.17	B22.92
	T73.34	T75.84
Journeyman	W42.17	W45.92
	B24.17	B22.92
	T66.34	T68.84
I .	I	I

Craft: Painter-Elevated Water Tanks

APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
	SEE	PAINTER	BRIDGES								

Craft: Painter-Elevated Water Tanks

COMMENTS/NOTES

These rates apply to: All new and repaint elevated water tanks (interior and exterior).

FOREMEN REQUIREMENTS:

- When there are 4 or more Painters on a job, 1 shall be designated a Foreman.
- When there are 15 or more Painters on a job, 1 shall be designated a General Foreman.

The regular workday shall consist of 8 hours between 7:00 AM and 5:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays and Sundays shall be paid at time and one-half the regular rate. All hours on holidays shall be paid at double the regular rate.
- Saturday or Sunday may be used to make up a day lost to inclement weather, at straight time.
- Four 10-hour days may be worked, at straight time, Monday through Friday.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Saturday holiday observed the preceding Friday. Sunday holiday observed the following Monday.

1/5/2017 Page 49 of 68

County - UNION

Craft: Painter-Structural Steel PREVAILING WAGE RATE

	05/01/16	05/01/17
Foreman	W46.12	W49.87
	B24.51	B23.26
	T70.63	T73.13
General Foreman	W48.12	W51.87
	B24.51	B23.26
	T72.63	T75.13
Journeyman	W41.12	W44.87
	B24.51	B23.26
	T65.63	T68.13

Craft: Painter-Structural Steel APPRENTICE RATE SCHEDULE

INTERVAL		PERIC	DD AND RAT	ES			
	SEE	PAINTER	BRIDGES				

Craft: Painter-Structural Steel COMMENTS/NOTES

These rates apply to: All work in power plants (any aspect). On steeples, on dams, on hangers, transformers, substations, etc. and on open steel, whether new or repaint. All new work (excluding traditional commercial painting work) in refineries, tank farms, water/sewerage treatment facilities and on pipelines.

FOREMEN REQUIREMENTS:

- When there are 4 or more Painters on a job, 1 shall be designated a Foreman.
- When there are 15 or more Painters on a job, 1 shall be designated a General Foreman.

The regular workday shall consist of 8 hours between 7:00 AM and 5:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays and Sundays shall be paid at time and one-half the regular rate. All hours on holidays shall be paid at double the regular rate.
- Saturday or Sunday may be used to make up a day lost to inclement weather, at straight time.
- Four 10-hour days may be worked, at straight time, Monday through Friday.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Saturday holiday observed the preceding Friday. Sunday holiday observed the following Monday.

1/5/2017 Page 50 of 68

County - UNION

Craft: Paperhanger - New Construction

PREVAILING WAGE RATE

	05/01/16	05/01/17
Foreman	W43.25	W45.32
	B22.59	B21.44
	T65.84	T66.76
Journeyman	W39.32	W41.20
	B22.59	B22.01
	T61.91	T63.21

Craft: Paperhanger - New Construction

APPRENTICE RATE SCHEDULE

INTERVAL		PERIC	DD AND RAT	ES						
4 Months	30%	40%	50%	60%	70%	75%	80%	85%	90%	
Benefits	Intervals	1 to 3 =	8.00	Intervals	4 to 6 =	10.00	Intervals	7 to 9 =	11.00	

Ratio of Apprentices to Journeymen - 1:4

Craft: Paperhanger - New Construction

COMMENTS/NOTES

APPRENTICE RATE SCHEDULE FOR THOSE APPRENTICES ENTERING PROGRAM ON 5-1-14:

INTERVAL PERIOD AND RATES

6 Months 40% 45% 55% 65% 70% 75% 80% 90% Benefits 8.00 8.00 10.00 10.00 11.00 11.00 14.00 14.00

FOREMEN REQUIREMENTS:

- When there are 4 or more Paperhangers on a job, 1 shall be designated a Foreman.

The regular workday shall consist of 8 hours between 7:00 AM and 5:30 PM.

SHIFT DIFFERENTIALS:

- The second shift shall receive an additional 10% of the hourly rate, per hour, and the third shift shall receive an additional 15% of the hourly rate, per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the regular rate. All hours on Sundays and holidays shall be paid at double the regular rate.
- Saturday or Sunday may be used to make up a day lost to inclement weather, at straight time.
- Four 10-hour days may be worked, at straight time, Monday through Friday.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day, July 4th, Labor Day, General Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 51 of 68

County - UNION

Craft: Paperhanger - Renovation PREVAILING WAGE RATE

	05/01/16	05/01/17
Foreman	W32.39	W35.06
	B18.96	B18.53
	T51.35	T53.59
Journeyman	W29.45	W31.88
	B18.96	B18.53
	T48.41	T50.41

Craft: Paperhanger - Renovation APPRENTICE RATE SCHEDULE

INTERVAL		PERIC	DD AND RAT	ES				
	SEE	PAPER-	HANGER	NEW	LIC	TION		

Ratio of Apprentices to Journeymen - 1:4

Craft: Paperhanger - Renovation COMMENTS/NOTES

NOTE: These rates may only be used on jobs where no major alterations occur, and where not more than 3 other trades are present on the job, but may NOT, under any circumstances, be used for work on bridges, stacks, elevated tanks, or generating stations.

FOREMEN REQUIREMENTS:

- When there are 4 or more Paperhangers on a job, 1 shall be designated a Foreman.

OVERTIME:

- Hours in excess of 8 per day and 40 per week shall be paid at time and one-half the regular rate.
- Four 10-hour days may be worked, at straight time, Monday through Sunday.

1/5/2017 Page 52 of 68

County - UNION

Craft: Pipefitter PREVAILING WAGE RATE

	05/04/16	05/01/17	05/01/18	05/01/19
Foreman	W51.07	W0.00	W0.00	W0.00
	B40.18	B0.00	B0.00	B0.00
	T91.25	T93.35	T95.57	T97.79
Journeyman	W47.32	W0.00	W0.00	W0.00
	B37.25	B0.00	B0.00	B0.00
	T84.57	T86.67	T88.89	T91.11

Craft: Pipefitter APPRENTICE RATE SCHEDULE

INTERVAL		PERIC	DD AND RAT	ES				
Yearly	35%	45%	55%	65%	75%			
Benefit	14.46	18.16	21.89	25.48	27.82			

Ratio of Apprentices to Journeymen - 1:5

Craft: Pipefitter COMMENTS/NOTES

FOREMAN REQUIREMENTS:

- When there are 2 or more Journeyman Pipefitters on a job, 1 shall be designated a Foreman.
- There shall be a Foreman for every 8 Journeyman Pipefitters on a job.

The regular workday shall be 8 hours between 7:00 AM and 3:30 PM.

SHIFT DIFFERENTIAL:

- 2nd Shift (3:30 PM-11:30 PM) shall work 7.5 hours and receive 8 hours pay at the regular rate, plus 25% per hour.
- 3rd Shift (11:30 PM-7:00 AM) shall work 7 hours and receive 8 hours pay at the regular rate, plus 30% per hour.

OVERTIME:

- All hours worked in excess of 8 per day, Monday through Friday, and all hours worked on Saturday, shall be paid at time and one-half, inclusive of benefits. All hours on Sunday and holidays shall be paid at double time, inclusive of benefits.
- By mutual agreement, employees may work four 10-hour days, Monday to Thursday, at straight time rate. Friday may be used as a make-up day for a day lost to inclement weather, and may be paid at straight time. If Friday is not a make-up day, the first 8 hours shall be paid at time and one-half, inclusive of benefits; hours in excess of 8 shall be paid at double time, inclusive of benefits.

SHIFT DIFFERENTIAL (Maintenance Work Only):

- 2nd Shift (3:30 PM-11:30 PM) shall work 7.5 hours and receive 8 hours pay at the regular rate, plus 10% per hour.
- 3rd Shift (11:30 PM-7:00 AM) shall work 7 hours and receive 8 hours pay at the regular rate, plus 15% per hour.

OVERTIME (Maintenance Work Only):

- All hours in excess of 8 per day, Monday through Saturday, shall be paid at time and one-half, inclusive of benefits. All hours on Sundays and holidays shall be paid at double time, inclusive of benefits.

NOTE: Maintenance work is work to repair, restore, or improve the efficiency of existing facilities. This does NOT apply to

Page 53 of 68

County - UNION

ANY new construction.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays are observed the following Monday.

1/5/2017 Page 54 of 68

County - UNION

Craft:	Plasterer	PREVAILING WAGE RATE

See Bricklayer, Stone Mason Rates

Craft: Plasterer COMMENTS/NOTES

See BRICKLAYER, STONE MASON Rates

1/5/2017 Page 55 of 68

County - UNION

Craft: Plumber PREVAILING WAGE RATE

	05/04/16
Foreman	W55.52
	B32.99
	T88.51
General Foreman	W59.12
	B32.99
	T92.11
Journeyman	W51.41
	B32.99
	T84.40
I .	1

Craft: Plumber APPRENTICE RATE SCHEDULE

INTERVAL		PERIC	DD AND RAT	ES				
Yearly	30%	45%	55%	65%	75%			
Benefits	12.77	18.77	20.44	22.13	23.80			

Ratio of Apprentices to Journeymen - *

Craft: Plumber COMMENTS/NOTES

FOREMAN REQUIREMENTS:

- On any job having 2 or more Plumbers, 1 must be designated a Foreman.
- On any job having 9 or more Plumbers, 2 shall be designated as Foremen.

The regular workday shall consist of 8 hours between 7:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- Shift work must continue for a minimum of 5 consecutive workdays.
- When two shifts are worked, the second shift shall work 7.5 hours and receive 8 hours pay, at a rate equal to the hourly rate plus 10%, inclusive of benefits.
- When a third shift is worked, the third shift shall work 7 hours and receive 8 hours pay, at a rate equal to the hourly rate plus 15%, inclusive of benefits.

OVERTIME:

- All hours in excess of 8 per day, or before of after the regular workday that are not shift work, Monday through Friday, and all hours on Saturday, shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sunday and holidays, shall be paid at double the hourly rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday to Thursday, at straight time. Friday may be used as a make-up day for a day lost due to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays will be observed the following Monday.

1/5/2017 Page 56 of 68

^{*} Employers may employ 1 apprentice on any job where 1 or 2 journeymen are employed. Thereafter, 1 apprentice may be employed for every 4 journeymen.

County - UNION

Craft: Roofer PREVAILING WAGE RATE

	06/06/16
Foreman	W36.52 B25.03 T61.55
Journeyman	W35.52 B25.03 T60.55

Craft: Roofer APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
6 Months	14.21	17.76	21.31	24.86	28.42	31.97					
Benefits	2.10	2.10	22.28	22.28	22.28	22.28					

Ratio of Apprentices to Journeymen - *

- * A) For roofing jobs that are of the 1 or single ply nature: 1:2 or fraction thereof
- B) For roofing jobs on new built up roofs: 1:3 or fraction thereof
- C) For roofing jobs that are of a tear-off nature: 1:2 or fraction thereof
- D) For roofing jobs {not requiring complete removal of existing systems, installation done over existing roof}: 1:3 or

fraction thereof

Craft: Roofer COMMENTS/NOTES

Pitch: +.50 per hour

Mop Man: +.30 per hour

The regular workday consists of 8 hours between 8:00 AM and 4:30 PM.

OVERTIME:

Hours in excess of 8 per day, or before or after the regular workday, Monday through Friday, and all hours on Saturdays, Sundays, and holidays shall be paid at time and one-half the regular rate.

RECOGNIZED HOLIDAYS: New Year's Day, Good Friday, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 57 of 68

County - UNION

Craft: Sheet Metal Sign Installation PREVAILING WAGE RATE

	10/31/16
Foreman	W33.79 B31.82 T65.61
Journeyman	W32.54 B31.82 T64.36

Craft: Sheet Metal Sign Installation APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES									
1000 hours	35%	40%	45%	50%	55%	60%	65%	70%	75%	80%	
Benefits	10.28	11.73	13.18	14.65	16.47	17.96	19.44	20.93	22.40	23.89	

Ratio of Apprentices to Journeymen - 1:3

Craft: Sheet Metal Sign Installation COMMENTS/NOTES

FOREMAN REQUIREMENT:

When there are 6 or more Sheet Metal Sign Installers on a job, 1 shall be designated a Foreman.

The regular workday consists of 8 hours, between 7:00 AM and 3:30 PM.

OVERTIME:

Hours before or after the regular workday, Monday though Friday, and all hours worked on Saturday shall be paid at time and one-half the hourly rate. All hours on Sunday and holidays shall be paid at double the hourly rate.

Four(4) 10 hour days may be worked, Monday through Friday, at straight time, for projects lasting at least one week in duration. The fifth day may be used as a make-up day at straight time for a day lost due to inclement weather. However, if the fifth day is not a make-up day, all hours worked will be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Good Friday, Memorial Day, July 4th, Labor Day, Veterans' Day, Thanksgiving Day and the day after, Christmas Day. Saturday holidays observed the preceding Friday, Sunday holidays observed the following Monday.

1/5/2017 Page 58 of 68

County - UNION

Craft: Sheet Metal Worker PREVAILING WAGE RATE

	08/02/16	06/01/17
Foreman	W49.99	W0.00
	B38.73	B0.00
	T88.72	T91.22
General Foreman	W50.99	W0.00
	B38.73	B0.00
	T89.72	T92.22
Journeyman	W46.49	W0.00
	B38.73	B0.00
	T85.22	T87.72

Craft: Sheet Metal Worker APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
Yearly	35%	45%	55%	65%	of	Journey	man	Wage	Rate	
Benefit	35%	45%	55%	65%	of	Journey	man	Benefit	Rate	

Ratio of Apprentices to Journeymen - 1:4

Craft: Sheet Metal Worker COMMENTS/NOTES

FOREMAN REQUIREMENTS:

- When there are 2 or more Sheet Metal Workers on a project, 1 must be designated a Foreman.
- When there are 17 or more Sheet Metal Workers on a project, 1 must be designated a General Foreman.
- When there is only 1 Sheet Metal Worker (1 Journeyman) on a project, he/she shall receive \$1.00 more than the regular Journeyman's rate.

The regular workday is 8 hours between 7:00 AM and 4:30 PM.

SHIFT DIFFERENTIAL:

- 2nd Shift (3:30 PM 12:00 AM): +17% of regular hourly rate
- Shift work must run for a minimum of 5 consecutive workdays.

OVERTIME:

- Hours in excess of 8 per day, or before or after the regular workday, that are not shift work, and the first 10 hours on Saturdays shall be paid at time and one-half of the regular rate, inclusive of benefits. Hours in excess of 10 per day on Saturday, and all hours on Sundays and holidays shall be at double the regular rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday through Friday, at straight time, with hours in excess of 10 per day, and hours in excess of 40 per week paid at the overtime rates listed above.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Good Friday, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays will be observed the following Monday.

1/5/2017 Page 59 of 68

County - UNION

Craft: Sprinkler Fitter PREVAILING WAGE RATE

	01/01/17	07/01/17	01/01/18	07/01/18	01/01/19
Foreman	W62.93	W64.93	W64.38	W66.63	W66.08
	B26.12	B26.12	B26.67	B26.67	B27.22
	T89.05	T91.05	T91.05	T93.30	T93.30
General Foreman	W65.93	W67.93	W67.38	W69.63	W69.08
	B26.12	B26.12	B26.67	B26.67	B27.22
	T92.05	T94.05	T94.05	T96.30	T96.30
Journeyman	W58.83	W60.83	W60.28	W62.53	W61.98
	B26.12	B26.12	B26.67	B26.67	B27.22
	T84.95	T86.95	T86.95	T89.20	T89.20

Craft: Sprinkler Fitter APPRENTICE RATE SCHEDULE

INTERVAL	PERIOD AND RATES									
1000 Hours	9.50	11.25	50%	55%	60%	65%	70%	75%	80%	85%
Benefits	10.67	10.67	21.22	21.22	21.22	21.22	Intervals	7 to 10	Jourymn	Ben.

APPRENTICE RATE SCHEDULE FOR THOSE APPRENTICES REGISTERED AS OF 7-1-13:

INTERVAL PERIOD AND RATES

1000 hours 25% 30% 40% 45% 55% 60% 70% 75% 85% 90%

Benefits 10.67 10.67 21.22 21.22 21.22 Intervals 7 to 10 receive Journeyman Ben.

Craft: Sprinkler Fitter COMMENTS/NOTES

The regular workday consists of 8 consecutive hours between 6:00 AM and 4:30 PM.

FOREMAN REQUIREMENTS:

- The first Sprinkler Fitter on the job must be designated a Foreman.
- On any job having 12 or more Sprinkler Fitters, one must be designated a General Foreman.

SHIFT DIFFERENTIALS:

- Shift work must run for a minimum of 2 consecutive workdays.
- 2nd and 3rd shift shall receive an additional 15% of the regular rate, per hour.
- Any "off hours" shift starting at 8:00 PM or later shall receive an additional 25% of the regular rate, per hour.

OVERTIME:

The first 2 hours in excess of 8 per day, after the regular workday that are not shift work, Monday through Friday, shall be paid at time and one-half the regular rate. Hours worked in excess of 10 per day, Monday through Friday, and all hours on Saturday, Sunday and holidays, shall be paid double the regular rate.

Four 10 hour days may be worked, Monday through Thursday, at striaght-time.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Good Friday, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 60 of 68

County - UNION

Craft: Tile Finisher-Marble PREVAILING WAGE RATE

	01/01/17	07/01/17	01/01/18
Finisher	W46.01	W46.32	W46.66
	B32.68	B33.44	B34.18
	T78.69	T79.76	T80.84

Craft: Tile Finisher-Marble APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
750 Hours	50%	55%	65%	70%	75%	85%	90%	95%		

Ratio of Apprentices to Journeymen - 1:4

Craft: Tile Finisher-Marble COMMENTS/NOTES

OVERTIME:

Hours in excess of 7 per day, Monday through Friday, and the first 7 hours on Saturdays shall be paid at time and one half the regular rate, inclusive of benefits. Hours in excess of 7 on Saturdays and all hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Good Friday, Memorial Day, July 4th, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day and the day after, Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 61 of 68

County - UNION

Craft: Tile Setter - Ceramic PREVAILING WAGE RATE

	12/08/16
Finisher	W43.36 B29.09 T72.45
Setter	W56.13 B32.39 T88.52

Craft: Tile Setter - Ceramic APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES								
750 Hours	50%	55%	60%	65%	70%	75%	85%	95%	100%	

Ratio of Apprentices to Journeymen - 1:4

Craft: Tile Setter - Ceramic COMMENTS/NOTES

OVERTIME:

Hours in excess of 7 per day, and the first 10 hours on Saturdays shall be paid at time and one-half the hourly rate. All hours on Saturdays after 10 hours shall be paid double the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day, Christmas Day.

1/5/2017 Page 62 of 68

County - UNION

Craft: Tile Setter - Marble PREVAILING WAGE RATE

	01/01/17	07/01/17	01/01/18
Tile Setter	W57.74	W58.18	W58.53
	B34.26	B35.27	B36.37
	T92.00	T93.45	T94.90

Craft: Tile Setter - Marble APPRENTICE RATE SCHEDULE

INTERVAL	PERIOD AND RATES								
750 Hours	50%	55%	65%	70%	75%	85%	90%	95%	

Ratio of Apprentices to Journeymen - 1:4

Craft: Tile Setter - Marble COMMENTS/NOTES

OVERTIME:

Hours in excess of 7 per day, Monday through Friday, and the first 7 hours on Saturdays shall be paid at time and one-half the regular rate, inclusive of benefits. Hours in excess of 7 on Saturdays, and all hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Good Friday, Memorial Day, July 4th, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day and the day after, Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 63 of 68

County - UNION

Craft: Tile Setter - Mosaic & Terrazzo PREVAILING WAGE RATE

	01/01/17
Grinder or Assistant	W50.86 B34.14 T85.00
Mechanic	W52.46 B34.16 T86.62

Craft: Tile Setter - Mosaic & Terrazzo APPRENTICE RATE SCHEDULE

INTERVAL		PERIOD AND RATES							
750 Hours	50%	55%	65%	70%	75%	85%	90%	95%	

Ratio of Apprentices to Journeymen - 1:5

Craft: Tile Setter - Mosaic & Terrazzo COMMENTS/NOTES

The regular workday consists of 7 hours, between 8:00 AM and 3:30 PM.

OVERTIME:

- Hours in excess of 7 per day, or before or after the regular workday, Monday through Friday, and all hours on Saturdays shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Good Friday, Monday after Easter, Memorial Day, July 4th, Labor Day, Columbus Day, Veterans' Day, Thanksgiving Day and the day after, Christmas Day. Sunday holidays observed the following Monday.

1/5/2017 Page 64 of 68

County - UNION

Craft: Truck Driver PREVAILING WAGE RATE

	11/01/16	05/01/17	11/01/17	05/01/18	11/01/18
Descript Halle	14/00 40	14/00 00	W/00 00	W07.00	14/07 00
Bucket, Utility,	W36.40	W36.83	W36.83	W37.26 B35.40	W37.66
Pick-up, Fuel Delivery trucks	B33.01 T69.41	B33.78	B34.58 T71.41	T72.66	B35.80 T73.46
Delivery trucks	169.41	T70.61	171.41	172.00	173.46
Dump truck, Asphalt	W36.40	W36.83	W36.83	W37.26	W37.66
Distributor, Tack	B33.01	B33.78	B34.58	B35.40	B35.80
Spreader	T69.41	T70.61	T71.41	T72.66	T73.46
Euclid-type vehicles	W36.55	W36.98	W36.98	W37.41	W37.81
(large, off-road	B33.01	B33.78	B34.58	B35.40	B35.80
equipment)	T69.56	T70.76	T71.56	T72.81	T73.61
Helper on Asphalt	W36.40	W36.83	W36.83	W37.26	W37.66
Distributor truck	B33.01	B33.78	B34.58	B35.40	B35.80
	T69.41	T70.61	T71.41	T72.66	T73.46
Slurry Seal,	W36.40	W36.83	W36.83	W37.26	W37.66
Seeding/Fertilizing/	B33.01	B33.78	B34.58	B35.40	B35.80
Mulching truck	T69.41	T70.61	T71.41	T72.66	T73.46
Straight 3-axle truck	W36.45	W36.88	W36.88	W37.31	W37.71
	B33.01	B33.78	B34.58	B35.40	B35.80
	T69.46	T70.66	T71.46	T72.71	T73.51
Tractor Trailer	W36.55	W36.98	W36.98	W37.41	W37.81
(all types)	B33.01	B33.78	B34.58	B35.40	B35.80
	T69.56	T70.76	T71.56	T72.81	T73.61
Vacuum or Vac-All	W36.40	W36.83	W36.83	W37.26	W37.66
truck (entire unit)	B33.01	B33.78	B34.58	B35.40	B35.80
, ,	T69.41	T70.61	T71.41	T72.66	T73.46
Winch Trailer	W36.65	W37.08	W37.08	W37.51	W37.91
	B33.01	B33.78	B34.58	B35.40	B35.80
	T69.66	T70.86	T71.66	T72.91	T73.71

Craft: Truck Driver COMMENTS/NOTES

BLENDED RATE:

When a truck driver is performing work on the site and also serving as a material delivery driver, the driver shall be paid a "blended rate" which shall be 80% of the above-listed wage rates, plus the full benefit rate. This rate shall be used when the driver "round robins" for a minimum of 6 hours during the work day.

HAZARDOUS WASTE REMOVAL:

- On hazardous waste removal work on a State designated hazardous waste site where the driver is in direct contact with hazardous materials and when personal protective equipment is required for respiratory, skin, and eye protection, the driver shall receive an additional \$3.00 per hour (with or without protective gear).
- A hazardous waste related certified worker at a designated hazardous waste site who is not working in a zone requiring level A, B or C personal protection shall receive an additional \$1.00 per hour.

TRUCK FOREMAN: \$.75 cents per hour above regular rate. Overtime shall be increased accordingly.

1/5/2017 Page 65 of 68

County - UNION

The regular workday shall be 8 hours, starting between 6:00 AM and 8:00 AM.

SHIFT DIFFERENTIAL:

- Shifts starting at 4:00 PM (2nd Shift): + \$2.50 per hour.
- Shifts starting at 12:00 AM (midnight/3rd Shift): time and one-half the hourly rate.
- Shifts starting at a time other than from 6:00 AM to 8:00 AM, when such hours are mandated by the project owner: + \$2.50 per hour.

OVERTIME:

- Hours in excess of 8 per day, or before or after the regular workday, Monday through Friday, that are not shift work, and all hours on Saturdays shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.
- Employees may work four 10-hour days at straight time, Monday through Thursday, with Friday used as a make-up day for a lost day. If Friday is not a make-up day, then all hours on Friday shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day (Decoration Day), July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays will be observed the following Monday. The day after Thanksgiving may be substituted for Veterans' Day.

1/5/2017 Page 66 of 68

County - UNION

Craft: Truck Driver-Material Delivery Driver

PREVAILING WAGE RATE

	05/01/12
Driver	W22.90
	B10.17
	T33.07

Craft: Truck Driver-Material Delivery Driver

COMMENTS/NOTES

BLENDED RATE:

When a truck driver is performing work on the site and also serving as a material delivery driver, the driver shall be paid a "blended rate". See the "Truck Driver" craft for the blended rates.

Truck Foreman/Shop Steward: +\$0.25 per hour

SHIFT DIFFERENTIALS:

- 2nd Shift shall receive an additional \$0.50 per hour
- 3rd Shift shall receive time and one-half the hourly rate.

OVERTIME:

- Hours in excess of 8 per day, or before or after the regular workday that are not shift work, Monday through Friday, and all hours on Saturday shall be paid at time and one-half the hourly rate. All hours on Sunday and holidays shall be paid at double the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, President's Day, Memorial Day (Decoration Day), July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays will be observed the following Monday. The day after Thanksgiving may be substituted for Veterans' Day.

1/5/2017 Page 67 of 68

County - UNION

Craft:	Welder	PREVAILING WAGE RATE
	Welder	
Craft:	Welder	COMMENTS/NOTES

Welders rate is the same as the craft to which the welding is incidental $\!.$

1/5/2017 Page 68 of 68

STATEWIDE RATES

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

{For apprentice rates refer to "Operating Engineers" apprentice rates in any county rate package}

On all machines, including pile drivers with booms of 100 feet and over (including jib) the Operating Engineer shall receive the regular hourly rate plus: \$1.00 per hour on rigs with 100 foot Boom (including jib) up to 139 feet, and \$2.00 per hour on rigs with 140 foot Boom (including jib) and over. On all hoists where "Cat Head" or "Sheave Point" is 100 feet or more above ground level, the same differential pay shall apply as applicable to booms 100 feet and over.

The regular workday consists of 8 hours, Monday to Friday, between 6:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- Shift work must run for 5 consecutive workdays.
- When 2 shifts are worked, the second shift shall receive an additional 10% of the regular rate inclusive of benefits, per hour.
- When 3 shifts are worked, the second shift shall receive 8 hours pay for 7.5 hours of work, plus an additional 10% of the regular rate inclusive of benefits, per hour. The third shift shall receive 8 hours pay for 7 hours of work, plus an additional 15% of the regular rate inclusive of benefits, per hour.
- When such hours are mandated by the project owner, a shift that starts between 8:00 PM and midnight and ends by 6:00 AM Saturday, or that starts after 8:00 PM on Sunday, provided there are consecutive hours of work within the shift, shall receive an additional 15% of the regular rate, inclusive of benefits.
- On Highway, Road, Street, and Sewer projects irregular shifts starting between 5:00 PM and 12:00 AM may be worked Monday through Friday, and shall receive an additional 15% of the regular rate, inclusive of benefits. When working with other trades that receive a higher irregular shift rate, the Operating Engineer shall also receive the higher irregular shift rate.

OVERTIME:

- Hours in excess of 8 per day, or outside of the regular workday, Monday through Friday, that are not shift work, and all hours on Saturdays shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with all hours on Friday paid at time and one-half the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday.

On hazardous waste removal work or asbestos removal work, on a state or federally designated hazardous waste site, where the operating engineer is in direct contact with hazardous material and when personal protective equipment is required for respiratory, skin, and eye protection, the operating engineer shall receive an additional 20% of the hourly wage, per hour.

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Log Skidder

Effective Dat	tes:	THE STATE OF THE S	on Date : 00/30/201
	07/01/2010	5	01/01/2017
Rate	Fringe	Total	Total
46.48	30.63	77.11	78.26
CLASSIFIC	ATIONS:		
A-Frame			
Backhoe (co	ombination)		
Boom Attac	hment on loade	rs (Except pipehoo	ok)
Boring & Di	rilling Machine		
Brush Chop	per, Brush Shre	dder, Tree Shredde	er
Bulldozer, fi	inish grade		
Cableway			
Carryall			
Concrete Pu	mp		
Concrete Pu	mping System	(Pumpcrete & simi	ilar types)
Conveyor, 1	25 feet or longe	er	
Drill Doctor	(Duties include	e dust collector and	d maintenance)
Front End L	oader (2 cu. yd:	s. but less than 5 cu	u. yds.)
Grader, finis	sh		
Groove Cutt	ting Machine (r	ide-on type)	
Heater Plane	er		
hydraulic,	single and doub		lectric, air brick shaft caisson, Chicago-boom type)
Hydraulic C	rane (10 tons &	under)	
Hydro-Axe			
Hydro-Blast	er		
		power-operated uni jack or pile load to	

12/05/2016

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
46.48	30.63	77.11	78.26

CLASSIFICATIONS:

Pan

Paver, concrete

Plate & Frame Filter Press

Pumpcrete (unit type)

Pumpcrete, Squeezecrete, or Concrete Pumping machine (regardless of size)

Scraper

Side Boom

Straddle Carrier (Ross and similar types)

Vacuum Truck

Whiphammer

Winch Truck (hoisting)

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dat	tes:				
	07/01/2016	6	01/01/2017		
Rate	Fringe	Total	Total		
44.57	30.63	75.20	76.35		
CLASSIFIC					
Aspnait Cur	bing Machine				
Asphalt Plan	nt Engineer				
Asphalt Spr	eader				
Autograde (Curb Trimmer &	Sidewalk Shoul	der Slipform (CMI & similar types)		
Autograde (Curecrete Machi	ne (CMI & simil	ar types)		
Autograde T	Tube Finisher &	Texturing Machi	ne (CMI & similar types)		
Bar Bending	g Machines (Pov	wer)			
Batcher, Bat	tching Plant, &	Crusher [On Site	I		
Belt Convey	or System				
Boom-Type	Skimmer Mach	ine			
Bridge Deck	c Finisher				
Bulldozer (a	ıll sizes)				
Captain (Po	wer Boats)				
Car Dumper	(railroad)				
Compressor & Blower unit for loading/unloading of concrete, cement, fly ash, or similar type materials (used independently or truck-mounted)					
Compressor (2 or 3 battery)					
Concrete Breaking Machine					
Concrete Cleaning/Decontamination Machine					
Concrete Fin	nishing Machine	e			
Concrete Saw or Cutter (ride-on type)					

Concrete Spreader (Hetzel, Rexomatic & similar types)

Concrete Vibrator

12/05/2016

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Ladder (motorized)

Laddervator

Effective Dat	es:		
	07/01/2010	6	01/01/2017
Rate 44.57	Fringe 30.63	Total 75.20	Total 76.35
CLASSIFIC		75.20	, 0.50
Conveyors -	under 125 feet		
Crane Signa	lman		
Crushing Ma	achine		
Directional l	Boring Machine	e	
Ditching Ma	chine - Small (Ditchwitch, Verme	eer or similar types)
Dope Pot - N	Mechanical (wit	h or without pump)
Dumpster			
Elevator			
Fireman			
Fork Lift (E	conomobile, Lu	ıll & similar types)	
Front End L	oader (1 cu. yd.	and over but less	than 2 cu. yds.)
Generator (2	or 3 battery)		
Giraffe Grin	der		
Grader & M	otor Patrols		
Grout Pump			
Gunnite Ma	chine (Excludin	ng nozzle)	
Hammer - V	ibratory (in con	junction with gene	erator)
Heavy Equip	oment Robotics	- Operator/Techni	cian
Hoist (roof,	tugger, aerial pl	latform hoist, hous	e car)
Hopper			
Hopper Doo	rs (power opera	ated)	

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dates:

Tug Captains

Tug Master (Power Boats)

Effective Dat	es:		
	07/01/2010	5	01/01/2017
Rate 44.57	Fringe 30.63	Total 75.20	Total 76.35
CLASSIFIC		73.20	70.55
	(Dinky-type)		
Maintenance	e Utility Man		
Master Envi	ronmental Mair	ntenance Technician	1
Mechanic			
Mixer (Exce	pt paving mixe	rs)	
Pavement Breaker (truck-mounted or small self-propelled ride-on type)			
Pavement Breaker - maintenance of compressor or hydraulic unit			
Pipe Bendin	g Machine (pov	ver)	
Pitch Pump			
Plaster Pump (regardless of size)			
Post Hole D	igger (post pour	nder, auger)	
Roller (black	c top)		
Scale (power	r)		
Seamen Pulv	verizing Mixer		
Shoulder Wi	dener		
Silo			
Skimmmer N	Machine (boom	type)	
Steel Cutting	g Machine (serv	vice & maintenance)
Tamrock Dr	ill		
Tractor			
Transfer Ma	chines		

12/05/2016

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
44.57	30.63	75.20	76.35

CLASSIFICATIONS:

Ultra High Pressure Waterjet Cutting Tool System - Operator/Maintenance Technician

Vacuum Blasting Machine - Operator/Maintenance Technician

Vibrating Plant (used with unloading)

Welder & Repair Mechanic

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
41.23	30.63	71.86	73.01

CLASSIFICATIONS:

Assistant Engineer/Oiler

Driller's Helper

Field Engineer - Transit man or Instrument man

Maintenance Apprentice (Deckhand)

Maintenance Apprentice (Oiler)

Mechanic's Helper

Off Road Back Dump

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
38.65	30.63	69.28	70.43

CLASSIFICATIONS:

Field Engineer - Rodman or Chainman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
48.81	30.63	79.44	80.59

CLASSIFICATIONS:

Lead Engineer, Foreman Engineer, Safety Engineer (minimum)

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Da	tes:			
07/01/2016			01/01/2017	
Rate 48.07	Fringe 30.63	Total 78.70	Total 79.85	
CLASSIFIC		76.70	17.63	
		er (CMI & similar	types)	
		er - Recycle Type (
Autograde I similar typ		Spreader Combina	tion (CMI &	
Autograde S	Slipform Paver (CMI & similar typ	oes)	
Backhoe (E	xcavator)			
Central Pow	ver Plant			
Concrete Pa	wing Machine			
Draglines				
Drill, Bauer	, AMI and simil	ar types		
Drillmaster,	Quarrymaster			
		down-the-hole dril rill, self-powered d		
Elevator Gr	ader			
Field Engin	eer-Chief of Par	ty		
Front End L	oader (5 cu. yar	ds or larger)		
Gradall				
Grader, Rag	go			
Helicoptor Co-Pilot				
Helicoptor Communications Engineer				
Juntann Pile Driver				
Locomotive	(large)			
Mucking Machine				

Pavement & Concrete Breaker (Superhammer & Hoe Ram)

12/05/2016

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT

PREVAILING WAGE RATE DETERMINATION

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
48.07	30.63	78.70	79.85

CLASSIFICATIONS:

Pile Driver

Prentice Truck

Roadway Surface Grinder

Scooper (loader & shovel)

Shovel (Excavator)

Trackhoe (Excavator)

Tree Chopper with boom

Trenching Machine (cable plow)

Tunnel Boring Machine

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Da	ites:				
07/01/2016			01/01/2017		
Rate 42.94	Fringe 30.63	Total 73.57	Total 74.72		
CLASSIFIC		13.31	74.72		
Chipper					
Compresso	r (single)				
	preader (small t	wne)			
-		elevator graders)			
Engines, La	arge Diesel (162	0 HP) & Staging P	'ump		
Farm Tract	or				
Fertilizing	Equipment (ope	ration & maintenar	nce)		
Fine Grade	Machine (small	type)			
Form Line	Grader (small ty	vpe)			
Front End I	Loader (under 1	cubic yard)			
Generator (single)				
Grease, Ga	s, Fuel, & Oil S	upply Trucks			
Heaters (No	elson or other ty	pe)			
Lights - por	rtable generating	g light plant			
Mixer, Con	crete (small)				
Mulching Equipment (operation & maintenance)					
Power Broom or Sweeper					
Pump (diesel engine & hydraulic - regardless of power)					
Pump (larger than 2 inch suction, including submersible pumps)					
Road Finisl	Road Finishing Machine (small type)				
Roller - gra	de, fill, or stone	base			
Seeding Equipment (operation & maintenance)					

Sprinkler & Water Pump Trucks

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
42.94	30.63	73.57	74.72

CLASSIFICATIONS:

Steam Generator or Boiler

Stone Spreader

Tamping Machine (vibrating ride-on type)

Temporary Heating Plant (Nelson or other type, including proprane, natural gas, and flow-type units)

Water or Sprinkler Truck

Welding Machine (gas, diesel, or electric convertor, of any type)

Welding System - Multiple (rectifier transformer type)

Wellpoint Systems (including installation by bull gang and maintenance)

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
49.89	30.63	80.52	81.67

CLASSIFICATIONS:

Helicoptor Pilot/Engineer

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
53.82	30.63	84.45	86.35

CLASSIFICATIONS:

Cranes, Derricks, Pile Driver (all types), over 100 tons and TOWER CRANE with boom (including jib and/or leads) 140 ft. and over

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
52.82	30.63	83.45	85.35

CLASSIFICATIONS:

Cranes, Derricks, Pile Driver (all types), over 100 tons and TOWER CRANE with boom (including jib and/or leads) from 100 ft. to 139 ft

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
50.07	30.63	80.70	81.85

CLASSIFICATIONS:

Cranes, Derricks, Pile Driver (all types), under 100 tons with a boom (including jib and/or leads) 140 ft. and over

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
51.82	30.63	82.45	84.35

CLASSIFICATIONS:

Cranes, Derricks, Pile Driver (all types), over 100 tons and TOWER CRANE with a boom (including jib and/or leads) under 100 ft.

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
49.07	30.63	79.70	80.85

CLASSIFICATIONS:

Cranes, Derricks, Pile Driver (all types), under 100 tons with a boom (including jib and/or leads) from 100 ft. to 139 ft.

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

STRUCTURAL STEEL ERECTION Rates Expiration Date: 06/30/2017

{For apprentice rates refer to "Operating Engineers" apprentice rates in any county rate package}

The regular workday consists of 8 hours, Monday to Friday, between 6:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- Shift work must run for 5 consecutive workdays.
- When 2 shifts are worked, the second shift shall receive an additional 10% of the regular rate inclusive of benefits, per hour.
- When 3 shifts are worked, the second shift shall receive 8 hours pay for 7.5 hours of work, plus an additional 10% of the regular rate inclusive of benefits, per hour. The third shift shall receive 8 hours pay for 7 hours of work, plus an additional 15% of the regular rate inclusive of benefits, per hour.
- When such hours are mandated by the project owner, a shift that starts between 8:00 PM and midnight and ends by 6:00 AM Saturday, or that starts after 8:00 PM on Sunday, provided there are consecutive hours of work within the shift, shall receive an additional 15% of the regular rate, inclusive of benefits.
- On Highway, Road, Street, and Sewer projects irregular shifts starting between 5:00 PM and 12:00 AM may be worked Monday through Friday, and shall receive an additional 15% of the regular rate, inclusive of benefits. When working with other trades that receive a higher irregular shift rate, the Operating Engineer shall also receive the higher irregular shift rate.

OVERTIME:

- Hours in excess of 8 per day, or outside of the regular workday, Monday through Friday, that are not shift work, and all hours on Saturdays shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with all hours on Friday paid at time and one-half the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday.

On hazardous waste removal work or asbestos removal work, on a state or federally designated hazardous waste site, where the operating engineer is in direct contact with hazardous material and when personal protective equipment is required for respiratory, skin, and eye protection, the operating engineer shall receive an additional 20% of the hourly wage, per hour.

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
51.70	30.63	82.33	83.48

CLASSIFICATIONS:

Helicopter Pilot or Engineer

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT

PREVAILING WAGE RATE DETERMINATION

Rates Expiration Date: 06/30/2017

Effective Dates:

STRUCTURAL STEEL ERECTION

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
47.64	30.63	78.27	79.42

CLASSIFICATIONS:

A-Frame

Cherry Picker -10 tons or less (Over 10 tons use crane rate)

Hoist (all types Except Chicago-boom)

Jack (screw, air hydraulic, power-operated unit or console type, Except hand jack or pile load test type)

Side Boom

Straddle Carrier

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
44.98	30.63	75.61	76.76

CLASSIFICATIONS:

Aerial Platform Used On Hoists

Apprentice Engineer/Oiler with Compressor or Welding Machine

Captain (Power Boats)

Compressor (2 or 3 in battery)

Conveyor or Tugger Hoist

Elevator or House Car

Fireman

Forklift

Generator (2 or 3)

Maintenance Utility Man

Tug Master (Power Boats)

Welding Machines, Gas or Electric Converters on any type-2 or 3 in battery including diesels

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

STRUCTURAL STEEL ERECTION Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
43.45	30.63	74.08	75.23

CLASSIFICATIONS:

Compressor (Single)

Generators

Welding Machines, Gas, Diesel, Or Electric Converters of any type-single

Welding System, Multiple (Rectifier Transformer Type)

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
41.69	30.63	72.32	73.47

CLASSIFICATIONS:

Assistant Engineer/Oiler

Drillers Helper

Field Engineer - Transit/Instrument Man

Maintenance Apprentice (Deckhand)

Maintenance Apprentice (Oiler)

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
49.26	30.63	79.89	81.04

CLASSIFICATIONS:

Lead Engineer, Foreman Engineer, Safety Engineer (Minimum)

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
38.65	30.63	69.28	70.43

CLASSIFICATIONS:

Field Engineer - Rodman or Chainman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

STRUCTURAL STEEL ERECTION Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
48.40	30.63	79.03	80.18

CLASSIFICATIONS:

Field Engineer-Chief of Party

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
55.84	30.63	86.47	88.37

CLASSIFICATIONS:

Cranes (all cranes, land or floating with booms, including jib, 140 ft. and over, above ground). Derricks (all derricks, land, floating or Chicago Boom type with booms including jib, 140 ft. and over, above ground), and Pile Drivers (all types) over 100 tons and Tower Cranes.

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
54.18	30.63	84.81	86.71

CLASSIFICATIONS:

Cranes (all cranes, land or floating with booms including jib, less than 140 ft. abovr ground), Derricks (all derricks. land, floating or Chicago Boom type with booms including jib, less than 140 ft. above ground), Pile Drivers (all types), over 100 tons and Tower Crane. **Effective Dates:**

07/01/2016			01/01/2017
Rate Fringe Total			Total
52.09	30.63	82.72	83.87

CLASSIFICATIONS:

Cranes (all cranes, land or floating with booms including jib, 140 ft. and over, above ground), Derricks (all derricks, land, floating or Chicago Boom type with booms including jib, 140 ft. and over, above ground), Pile Drivers (all types), under 100 tons.

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
50.43	30.63	81.06	82.21

CLASSIFICATIONS:

Cranes (all cranes, land or floating with booms including jib, less than 140 ft. above ground), Derricks (all derricks, land, floating or Chicago Boom type with booms including jib, less than 140 ft. above ground), Pile Drivers (all types), under 100 tons.

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

STRUCTURAL STEEL ERECTION Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
52.09	30.63	82.72	83.87

CLASSIFICATIONS:

Helicopter Co-Pilot

Helicopter Communications Engineer

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

TEST BORING PRELIMINARY TO CONSTRUCTION-SOUTH/WEST Rates Expiration Date: 06/30/2017

THESE RATES APPLY IN THE FOLLOWING COUNTIES ONLY:

Atlantic, Burlington, Camden, Cape May, Cumberland, Gloucester, Hunterdon, Mercer, Monmouth, Ocean, Salem, Sussex, Warren

On all machines, including pile drivers with booms of 100 feet and over (including jib) the Operating Engineer shall receive the regular hourly rate plus: \$1.00 per hour on rigs with 100 foot Boom (including jib) up to 139 feet, and \$2.00 per hour on rigs with 140 foot Boom (including jib) and over. On all hoists where "Cat Head" or "Sheave Point" is 100 feet or more above ground level, the same differential pay shall apply as applicable to booms 100 feet and over.

The regular workday consists of 8 hours, Monday to Friday, between 6:00 AM and 4:30 PM.

SHIFT DIFFERENTIALS:

- Shift work must run for 5 consecutive workdays.
- When 2 shifts are worked, the second shift shall receive an additional 10% of the regular rate inclusive of benefits, per hour.
- When 3 shifts are worked, the second shift shall receive 8 hours pay for 7.5 hours of work, plus an additional 10% of the regular rate inclusive of benefits, per hour. The third shift shall receive 8 hours pay for 7 hours of work, plus an additional 15% of the regular rate inclusive of benefits, per hour.
- When such hours are mandated by the project owner, a shift that starts between 8:00 PM and midnight and ends by 6:00 AM Saturday, or that starts after 8:00 PM on Sunday, provided there are consecutive hours of work within the shift, shall receive an additional 15% of the regular rate, inclusive of benefits.
- On Highway, Road, Street, and Sewer projects irregular shifts starting between 5:00 PM and 12:00 AM may be worked Monday through Friday, and shall receive an additional 15% of the regular rate, inclusive of benefits. When working with other trades that receive a higher irregular shift rate, the Operating Engineer shall also receive the higher irregular shift rate.

OVERTIME:

- Hours in excess of 8 per day, or outside of the regular workday, Monday through Friday, that are not shift work, and all hours on Saturdays shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with all hours on Friday paid at time and one-half the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday.

On hazardous waste removal work or asbestos removal work, on a state or federally designated hazardous waste site, where the operating engineer is in direct contact with hazardous material and when personal protective equipment is required for respiratory, skin, and eye protection, the operating engineer shall receive an additional 20% of the hourly wage, per hour.

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
48.07	30.63	78.70	79.85

CLASSIFICATIONS:

Driller

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

TEST BORING PRELIMINARY TO CONSTRUCTION-SOUTH/WEST Rates Expiration Date: 06/30/2017

Effective Dates:

07/01/2016			01/01/2017
Rate Fringe Total			Total
41.23	30.63	71.86	73.01

CLASSIFICATIONS:

Driller's Helper

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

FREE AIR TUNNEL JOBS Rates Expiration Date: 08/31/2017

{For apprentice rates refer to "Heavy & General" apprentice rates in any county rate package}

The regular workday consists of 8 hours, starting at 7:00 AM or 8:00 AM.

SHIFT DIFFERENTIALS:

- Shifts must start at 3:00 PM, 4:00 PM, 12:00 AM, or 1:00 AM, to be considered shift work, except when the project owner mandates special hours of work in the job specifications, in which case those hours may be considered shift work.
- When such hours are mandated by the project owner, a shift that begins before midnight on Friday and ends on Saturday morning, or that begins at or after 8:00 PM on Sunday and ends on Monday morning may be paid at the shift differential rate.
- Shifts shall receive an additional \$2.50 per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, or outside of the regular workday that are not shift work, and all hours on Saturdays, shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with Friday used as a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday. Veterans Day may be substituted for the day after Thanksgiving. However, in the trading of Veterans Day for the day after Thanksgiving, if overtime is worked on Veterans Day, it shall be paid at double the hourly rate.

Hazardous Waste Work:

- -where Level A, B, or C protection is required: + \$3.00/hr
- -other Hazardous Waste site: + \$1.00/hr

Effective Dates:

09/01/2016			03/01/2017
Rate Fringe Total			Total
40.35	27.78	68.13	70.53

CLASSIFICATIONS:

Walking Boss & Superintendent

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
40.05	27.78	67.83	70.23

CLASSIFICATIONS:

Heading Foreman, Shaft Foreman, Rod Foreman, Electrician Foreman, Rigging Foreman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

FREE AIR TUNNEL JOBS Rates Expiration Date: 08/31/2017

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
39.55	27.78	67.33	69.73

CLASSIFICATIONS:

Iron Foreman, Caulking Foreman, Form Foreman, Cement Finishing Foreman, Concrete Foreman, Track Foreman, Cleanup Foreman, Grout Foreman

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
42.05	27.78	69.83	72.23

CLASSIFICATIONS:

Blaster

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
39.00	27.78	66.78	69.18

CLASSIFICATIONS:

Top Labor Foreman

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.65	27.78	66.43	68.83

CLASSIFICATIONS:

Skilled Men (including Caulker, Powder Carrier, all other skilled men)

Skilled Men (including Miner, Drill Runner, Iron Man, Conveyor Man, Manitenance Man, Safety Miner, Rigger, Block Layer, Cement Finisher, Tod Man)

Effective Dates:

09/01/2016			03/01/2017
Rate Fringe Total			Total
38.50	27.78	66.28	68.68

CLASSIFICATIONS:

Semi-Skilled Men (including Bell or Signal Man Top or Bottom, Form Worker & Mover, Concrete Worker, Shaft Man, Tunnel Laborer, Caulker's Helper, all other semi-skilled)

Semi-Skilled Men (including Miner's Helper, Chuck Tender, Track Man, Nipper, Brake Man, Derail Man, Cable Man, Hose Man, Gravel Man, Form Man)

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

FREE AIR TUNNEL JOBS Rates Expiration Date: 08/31/2017

Effective Dates:

09/01/2016			03/01/2017
Rate Fringe Total			Total
38.00	27.78	65.78	68.18

CLASSIFICATIONS:

All Others (including Powder Watchman, Change House Attendant, Top Laborer)

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

DRILL FOR GROUND WATER SUPPLY Rates Expiration Date: 06/30/2017

The well driller and/or helper may perform all work relative to the construction, finishing, and servicing of wells, pumps and borings for ground water supply. The present methods of well drilling entailing as they do, many diverse job operations calling for drilling, pump discharge, piping, and the operation of various types of related power equipment, shall all be within the job duties and functions of the well driller and/or helper. In the event that an extension of work should occur beyond water well drilling functions, into the field of general construction work, such extension of work would come under the appropriate rates listed elsewhere in this wage determination.

- For Work Hours, Shift Differentials, Overtime Rates, and Recognized Holidays see the "Operating Engineers" section of this wage determination.

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
46.82	30.63	77.45	78.60

CLASSIFICATIONS:

Driller

Effective Dates:

07/01/2016			01/01/2017
Rate	Fringe	Total	Total
39.98	30.63	70.61	71.76

CLASSIFICATIONS:

Driller's Helper

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS MARINE-DREDGING Rates Expiration Date: 09/30/2018

NOTE: Boat crews carrying explosive material (dynamite, pourfex, and other similar materials) shall be paid at 120% of the hourly wage rate for hours engaged in handling of said materials. Employees required to possess a Hazardous Material Certification as a condition of employment shall be compensated at 120% of the hourly wage rate.

OVERTIME:

Hours in excess of 40 per week, and all hours on Saturdays and Sundays, shall be paid at time and one-half the hourly rate. All hours on holidays shall be paid at double the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Martin Luther King Day, Good Friday, Memorial Day, July 4th, Labor Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday.

Effective Dates:

10/01/2016			10/01/2017
Rate Fringe Total			Total
37.25	13.78	51.03	52.51

CLASSIFICATIONS:

Lead Dredgerman, Operator, Leverman

Licensed Tug Operator (over 1000 HP)

Effective Dates:

10/01/2016			10/01/2017
Rate Fringe Total			Total
32.22	13.38	45.60	46.95

CLASSIFICATIONS:

Derrick Operator, Spider/Spill Barge Operator

Engineer, Electrician, Chief Welder, Chief Mate

Fill Placer, Operator II

Licensed Boat Operator

Maintenance Engineer

Effective Dates:

10/01/2016			10/01/2017
Rate	Fringe	Total	Total
30.33	13.23	43.56	44.86

CLASSIFICATIONS:

Certified Welder

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

OPERATING ENGINEERS MARINE-DREDGING Rates Expiration Date: 09/30/2018

Effective Dates:

10/01/2016			10/01/2017
Rate	Fringe	Total	Total
29.50	12.86	42.36	43.64

CLASSIFICATIONS:

Mate, Drag Barge Operator, Steward, Assistant Fill Placer

Welder

Effective Dates:

10/01/2016			10/01/2017
Rate	Fringe	Total	Total
28.54	12.78	41.32	42.58

CLASSIFICATIONS:

Boat Operator

Effective Dates:

10/01/2016			10/01/2017
Rate	Fringe	Total	Total
23.71	12.10	35.81	36.92

CLASSIFICATIONS:

Shoreman, Deckhand, Rodman, Scowman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

MICROSURFACING/SLURRY SEAL Rates Expiration Date: 02/28/2018

THESE RATES APPLY IN THE FOLLOWING COUNTIES ONLY:

Atlantic, Burlington, Camden, Cape May, Cumberland, Gloucester, Mercer, Ocean, Salem

***IN ALL OTHER COUNTIES use the Heavy and General Laborers - North "Slurry Seal Laborer" rates. ***

SHIFT DIFFERENTIALS:

Any shift starting at 3:30 PM or later shall receive an additional \$0.35/hr

OVERTIME:

Hours in excess of 8 per day or 40 per week shall be paid at time and one-half the hourly rate. All hours on holidays shall be paid at double the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Washington's Birthday, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day.

Effective Dates:

03/01/2016			03/01/2017
Rate	Fringe	Total	Total
35.75	20.35	56.10	57.77

CLASSIFICATIONS:

Foreman

Effective Dates:

03/01/2016			03/01/2017
Rate	Fringe	Total	Total
33.10	20.35	53.45	55.07

CLASSIFICATIONS:

Box man

Effective Dates:

03/01/2016			03/01/2017
Rate Fringe Total			Total
31.10	20.35	51.45	53.02

CLASSIFICATIONS:

Microsurface/Slurry Preparation

Effective Dates:

03/01/2016			03/01/2017
Rate	Fringe	Total	Total
31.10	20.35	51.45	53.02

CLASSIFICATIONS:

Squeegee man

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

MICROSURFACING/SLURRY SEAL Rates Expiration Date: 02/28/2018

Effective Dates:

03/01/2016			03/01/2017
Rate	Fringe	Total	Total
29.60	20.35	49.95	51.57

CLASSIFICATIONS:

Cleaner, Taper

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ASPHALT LABORERS - SOUTH Rates Expiration Date: 08/31/2017

"THESE RATES APPLY IN THE FOLLOWING COUNTIES ONLY: Atlantic, Burlington, Camden, Cape May, Cumberland,

Gloucester, Mercer, Ocean, Salem

{For apprentice rates refer to "Laborer - Heavy & General" apprentice rates in any county rate package}

The regular workday consists of 8 hours, starting at 7:00 AM or 8:00 AM.

SHIFT DIFFERENTIALS:

- Shifts must start at 3:00 PM, 4:00 PM, 12:00 AM, or 1:00 AM, to be considered shift work, except when the project owner mandates special hours of work in the job specifications, in which case those hours may be considered shift work.
- When such hours are mandated by the project owner, a shift that begins before midnight on Friday and ends on Saturday morning, or that begins at or after 8:00 PM on Sunday and ends on Monday morning may be paid at the shift differential rate
- Shifts shall receive an additional \$2.50 per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, or outside of the regular workday that are not shift work, and all hours on Saturdays, shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with Friday used as a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday. Veterans Day may be substituted for the day after Thanksgiving. However, in the trading of Veterans Day for the day after Thanksgiving, if overtime is worked on Veterans Day, it shall be paid at double the hourly rate.

Hazardous Waste Work:

- -where Level A, B, or C protection is required: + \$3.00/hr
- -other Hazardous Waste site: + \$1.00/hr

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
39.85	27.78	67.63	70.03

CLASSIFICATIONS:

Paving Foreman

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.40	27.78	66.18	68.58

CLASSIFICATIONS:

Head Raker

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.25	27.78	66.03	68.43

CLASSIFICATIONS:

Raker, Screedman, Luteman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ASPHALT LABORERS - SOUTH Rates Expiration Date: 08/31/2017

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.00	27.78	65.78	68.18

CLASSIFICATIONS:

Tampers, Smoothers, Kettlemen, Painters, Shovelers, Roller Boys

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.10	27.78	65.88	68.28

CLASSIFICATIONS:

Milling Controller

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.30	27.78	66.08	68.48

CLASSIFICATIONS:

Traffic Control Coordinator

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

TEST BORING PRELIMINARY TO CONSTRUCTION-NORTH Rates Expiration Date: 10/16/2018

THESE RATES APPLY IN THE FOLLOWING COUNTIES ONLY:

Bergen, Essex, Hudson, Middlesex, Morris, Passaic, Somerset, Union

SHIFT DIFFERENTIAL:

Employees on a shift other than between the hours of 8:00 AM and 5:00 PM shall receive an additional \$1.00 per hour.

OVERTIME:

Hours in excess of 8 per day, Monday through Friday, and all hours on Saturday shall be paid at time and one-half the regular rate. All hours on Sundays and holidays shall be paid at double the regular rate.

RECOGNIZED HOLIDAYS: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day, and Christmas Day. Sunday holidays observed the following Monday.

Hazardous Waste Pay (for Levels A, B, and C): an additional 10% of the hourly rate, per hour.

A newly hired Helper with no experience in the industry shall be paid as follows:

1st year on the job - 70% of Helper wage rate

2nd year on the job - 80% of Helper wage rate

3rd year on the job - 90% of Helper wage rate

All helpers receive full fringe benefit rate.

Effective Dates:

11/01/2016			10/17/2017
Rate	Fringe	Total	Total
30.96	24.76	55.72	57.17

CLASSIFICATIONS:

Helper (4th year helper)

Effective Dates:

11/01/2016			10/17/2017
Rate	Fringe	Total	Total
38.82	24.76	63.58	65.24

CLASSIFICATIONS:

Driller

Effective Dates:

11/01/2016			10/17/2017
Rate	Fringe	Total	
44.64	24.76	69.40	71.28

CLASSIFICATIONS:

Foreman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

HEAVY & GENERAL LABORERS - NORTH Rates Expiration Date: 08/31/2017

THESE RATES APPLY IN THE FOLLOWING COUNTIES ONLY:

Bergen, Essex, Hudson, Hunterdon, Middlesex, Monmouth, Morris, Passaic, Somerset, Sussex, Union, Warren

{For apprentice rates refer to "Laborer - Heavy & General" apprentice rates in any county rate package}

The regular workday consists of 8 hours, starting at 7:00 AM or 8:00 AM.

SHIFT DIFFERENTIALS:

- Shifts must start at 3:00 PM, 4:00 PM, 12:00 AM, or 1:00 AM, to be considered shift work, except when the project owner mandates special hours of work in the job specifications, in which case those hours may be considered shift work.
- When such hours are mandated by the project owner, a shift that begins before midnight on Friday and ends on Saturday morning, or that begins at or after 8:00 PM on Sunday and ends on Monday morning may be paid at the shift differential rate.
- Shifts shall receive an additional \$2.50 per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, or outside of the regular workday that are not shift work, and all hours on Saturdays, shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with Friday used as a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday. Veterans Day may be substituted for the day after Thanksgiving. However, in the trading of Veterans Day for the day after Thanksgiving, if overtime is worked on Veterans Day, it shall be paid at double the hourly rate.

Hazardous Waste Work:

- -where Level A, B, or C protection is required: + \$3.00/hr
- -other Hazardous Waste site: + \$1.00/hr

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
37.60	27.78	65.38	67.78

CLASSIFICATIONS:

"D" Rate:

basic, landscape, asphalt, slurry seal, or railroad track laborer; utility meter installer; traffic director/flagman; salamander tender; pitman; dumpman; rakers or tampers on cold patch work; wrappers or coaters of pipe; waterproofer; timberman; wagon drill or drill master helper; powder carrier; magazine tender; signal man; power buggy operator; tree cutter; operator of basic power tools

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.30	27.78	66.08	68.48

CLASSIFICATIONS:

"C" Rate

pipe layer; laser man; conduit or duct line layer; operator of jack hammer, chipping hammer, pavement breaker, concrete cutter, asphalt cutter, sheet hammer, or walk-behind saw cutter; sandblaster; acetylene cutting or burning; wagon drill, directional drill, or hydraulic drill operator; drill master; core driller; traffic control coordinator; asphalt raker or lute man

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

HEAVY & GENERAL LABORERS - NORTH Rates Expiration Date: 08/31/2017

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.55	27.78	66.33	68.73

CLASSIFICATIONS:

"B" Rate:

concrete finisher; setter of brick or stone pavers; stone cutter; form setter; manhole, catch basin, or inlet builder; asphalt screedman; rammer; hardscaping; gunite nozzle man

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
42.10	27.78	69.88	72.28

CLASSIFICATIONS:

"A" Rate:

blaster

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
39.85	27.78	67.63	70.03

CLASSIFICATIONS:

"FOREMAN" Rate:

labor foreman, asphalt foreman, drill foreman, pipe foreman, grade foreman, finisher foreman, concrete foreman

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
40.85	27.78	68.63	71.03

CLASSIFICATIONS:

"GENERAL FOREMAN" Rate

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

HEAVY & GENERAL LABORERS - SOUTH Rates Expiration Date: 08/31/2017

THESE RATES APPLY IN THE FOLLOWING COUNTIES ONLY:

Atlantic, Burlington, Camden, Cape May, Cumberland, Gloucester, Mercer, Ocean, Salem

{For apprentice rates refer to "Laborer - Heavy & General" apprentice rates in any county rate package}

The regular workday consists of 8 hours, starting at 7:00 AM or 8:00 AM.

SHIFT DIFFERENTIALS:

- Shifts must start at 3:00 PM, 4:00 PM, 12:00 AM, or 1:00 AM, to be considered shift work, except when the project owner mandates special hours of work in the job specifications, in which case those hours may be considered shift work.
- When such hours are mandated by the project owner, a shift that begins before midnight on Friday and ends on Saturday morning, or that begins at or after 8:00 PM on Sunday and ends on Monday morning may be paid at the shift differential rate.
- Shifts shall receive an additional \$2.50 per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, or outside of the regular workday that are not shift work, and all hours on Saturdays, shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with Friday used as a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday. Veterans Day may be substituted for the day after Thanksgiving. However, in the trading of Veterans Day for the day after Thanksgiving, if overtime is worked on Veterans Day, it shall be paid at double the hourly rate.

Hazardous Waste Work:

- -where Level A, B, or C protection is required: + \$3.00/hr
- -other Hazardous Waste site: + \$1.00/hr

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
37.60	27.78	65.38	67.78

CLASSIFICATIONS:

basic, landscape, or railroad track laborer; utility meter installer; traffic director/flagman; salamander tender; pitman; dumpman; rakers or tampers on cold patch work; wrappers or coaters of pipe; waterproofers

tree cutter, timberman

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.30	27.78	66.08	68.48

CLASSIFICATIONS:

wagon drill or drill master helper; powder carrier; magazine tender; signal man

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

HEAVY & GENERAL LABORERS - SOUTH Rates Expiration Date: 08/31/2017

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.30	27.78	66.08	68.48

CLASSIFICATIONS:

pipe layer; laser man; conduit or duct line layer; operator of jack hammer, chipping hammer, pavement breaker, concrete cutter, asphalt cutter, sheet hammer, or walk-behind saw cutter; sandblaster; acetylene cutting or burning

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.30	27.78	66.08	68.48

CLASSIFICATIONS:

wagon or directional drill operator; drill master

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
42.10	27.78	69.88	72.28

CLASSIFICATIONS:

blaster

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
39.85	27.78	67.63	70.03

CLASSIFICATIONS:

labor foreman, drill foreman, pipe foreman, grade foreman, finisher foreman, concrete foreman

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
40.85	27.78	68.63	71.03

CLASSIFICATIONS:

general foreman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE PREVAILING WAGE RATE DETERMINATION

Effective Dates:

09/01/2016			03/01/2017
Rate	Fringe	Total	Total
38.55	27.78	66.33	68.73

HEAVY & GENERAL LABORERS - SOUTH

CLASSIFICATIONS:

concrete finisher; setter of brick or stone pavers; stone cutter; form setter; manhole, catch basin, or inlet builder; rammer; gunite nozzle

Rates Expiration Date: 08/31/2017

TERRITORY ENTIRE STATE

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

PIPELINE - MAINLINE TRANSMISSION Rates Expiration Date: 06/04/2017

These rates apply to the following: welding on Transportation Mainline pipe lines (cross-country pipe lines, or any segments thereof, transporting coal, gas, oil, water or other transportable materials, vapors or liquids, including portions of such pipe lines within private property boundaries up to the final metering station or connection - the point where a valve, consumer connection, or town border station divides mainline transmission lines or higher pressure lateral and branch lines from lower pressure distribution systems).

PER DIEM PAYMENT:

In addition to the total wage rate paid for each craft, the following per diem (per day) amounts must also be paid - Pipeline Journeyman: \$42.50; Pipeline Journeyman Welder: \$102.50; and Pipeline Helper: \$42.50. Note: in order to receive the per diem payment an employee must work a minimum of 8 hours in a 24 hour period.

NOTES:

- Journeymen employed as "stringer bead" welders and journeymen who are regularly employed as "hot-pass" welders shall receive \$1.00 per hour more than other journeymen.
- Welders running "stringer bead" or "hot-pass" on "cutouts" or "tie-ins" on a production basis shall be paid \$1.00 per hour above the journeymen rate.
- Whenever a welder helper is employed using a power buffer or power grinder immediately behind the stringer bead and/or hot-pass welders, and the pipe gang is set on a production basis, the helper shall be paid \$2.00 per hour above the helper rate.
- If back welding is performed inside a pipe under either or both of the following conditions, the welder engaged in the welding will receive \$3.00 per hour above the regular rate for the job only for the days on which such back welding is performed:
 - The employer elects, as a regular procedure, to back weld each line-up. This condition is not intended to apply to occasional back welding performed by the pipe gang to repair a bead, to rectify a "high-lo" condition or wall thickness, etc.
 - A welder is required to back weld a completed weld behind the firing line.
- If the welder helper is required to go inside the pipe for the purpose of brushing, buffing and grinding the weld, they shall receive a wage rate \$1.00 per hour above the regular

helper rate for the days involved.

- Welders working on "hot work" shall be paid \$2.00 per hour above the regular rate for each day engaged in such work. "Hot work' is defined as work on lines in service where there is the danger of fire or explosion.

The regular workday shall be 8 hours, between 8:00 AM and 4:30 PM.

OVERTIME:

Hours in excess of 8 per day, and all hours on Sundays shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on holidays shall be paid at double the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, July 4th, Labor Day, Thanksgiving Day, and Christmas Day. Sunday holidays observed the following Monday.

Effective Dates:

06/01/2016

Rate	Fringe	Total
54.56	26.59	81.15

CLASSIFICATIONS:

Pipeline Journeyman Welder

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

PIPELINE - MAINLINE TRANSMISSION Rates Expiration Date: 06/04/2017

Effective Dates:

06/01/2016

Rate Fringe Total 54.56 26.59 81.15

CLASSIFICATIONS:

Pipeline Journeyman

Effective Dates:

06/01/2016

Rate Fringe Total 32.99 18.73 51.72

CLASSIFICATIONS:

Pipeline Helper

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

PIPELINE - GAS DISTRIBUTION Rates Expiration Date: 10/31/2017

These rates apply to the following: welding on gas line distribution systems (that portion of the gas distribution system placed in streets, roads, subways, tunnels, viaducts, highways and easements which serves the users of gas).

SHIFT DIFFERENTIALS:

An "irregular" shift may start any time from 5:00 PM to 12:00 AM, Monday through Friday, and shall receive an additional 15% of the regular rate per hour, inclusive of benefits.

OVERTIME:

Hours in excess of forty per week, and all hours on Saturdays shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the regular rate, inclusive of benefits.

RECOGNIZED HOLIDAYS: New Year's Day, Memorial Day, July 4th, Labor Day, Thanksgiving Day, and Christmas Day. Sunday holidays observed the following Monday.

Effective Dates:

11	10.1	1201	-
	/ 1 1 1	/201	h

Rate	Fringe	Total
57.58	21.55	79.13

CLASSIFICATIONS:

Pipeline Journeyman Welder

Effective Dates:

11/01/2016

Rate	Fringe	Total
57.58	21.55	79.13

CLASSIFICATIONS:

Pipeline Journeyman

Effective Dates:

11/01/2016

Rate	Fringe	Total
37.16	15.74	52.90

CLASSIFICATIONS:

Pipeline Helper

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ASPHALT LABORERS- NORTH Rates Expiration Date: 08/31/2017

THESE RATES APPLY IN THE FOLLOWING COUNTIES ONLY:

Bergen, Essex, Hudson, Hunterdon, Middlesex, Monmouth, Morris, Passaic, Somerset, Sussex, Union, Warren {For apprentice rates refer to "Laborer - Heavy & General" apprentice rates in any county rate package} The regular workday consists of 8 hours, starting at 7:00 AM or 8:00 AM.

SHIFT DIFFERENTIALS:

- Shifts must start at 3:00 PM, 4:00 PM, 12:00 AM, or 1:00 AM, to be considered shift work, except when the project owner mandates special hours of work in the job specifications, in which case those hours may be considered shift work.
- When such hours are mandated by the project owner, a shift that begins before midnight on Friday and ends on Saturday morning, or that begins at or after 8:00 PM on Sunday and ends on Monday morning may be paid at the shift differential rate.
- Shifts shall receive an additional \$2.50 per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, or outside of the regular workday that are not shift work, and all hours on Saturdays, shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with Friday used as a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday. Veterans Day may be substituted for the day after Thanksgiving. However, in the trading of Veterans Day for the day after Thanksgiving, if overtime is worked on Veterans Day, it shall be paid at double the hourly rate.

Hazardous Waste Work:

- -where Level A, B, or C protection is required: + \$3.00/hr
- -other Hazardous Waste site: + \$1.00/hr

Effective Dates:

	09/01/2016		03/01/2017
Rate	Fringe	Total	Total
39.85	27.78	67.63	70.03

CLASSIFICATIONS:

Asphalt Foreman

Effective Dates:

09/01/2016		6	03/01/2017	
Rate	Fringe	Total	Total	
38.55	27.78	66.33	68.73	

CLASSIFICATIONS:

Asphalt Screedman

Effective Dates:

	09/01/201	6	03/01/2017
Rate	Fringe	Total	Total
38.30	27.78	66.08	68.48

CLASSIFICATIONS:

Asphalt Raker or Lute Man

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ASPHALT LABORERS- NORTH Rates Expiration Date: 08/31/2017

Effective Dates:

	09/01/201	6	03/01/2017
Rate	Fringe	Total	Total
37.60	27.78	65.38	67.78

CLASSIFICATIONS:

Asphalt Laborer

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ELECTRICIAN- UTILITY WORK (NORTH) Rates Expiration Date: 12/03/2017

Electrician-Utility Work (North)

(For apprentice rates refer to Electrician-Utility Work (North) in any county rate package).

These rates apply to work contracted for by the following utility companies:

Public Service Electric & Gas Co. of NJ, GPU Energy, Borough of Madison Electric Department, Sussex Rural

Electric Cooperative, Rockland Utilities, and Butler Municipal Electric Co.

These rates do not apply to work on substations or switching stations.

For Utility work contracted for by a utility company other than those listed above or those listed under "Electrician-

Utility Work (South), see the "Outside Commercial Rates" for the county in which the jobsite is located.

* FOR OUTSIDE COMMERCIAL RATES PLEASE SEE COUNTY RATES

The regular workday is 8 hours, between 6:00 AM and 6:00 PM.

FOR EMERGENCY WORK ONLY: (emergency work is defined as work caused by storm, catastrophe, act of god, and circumstances beyond the control of the employer)-all hours of work shall be paid at double the hourly rate.

SHIFT DIFFERENTIALS:

Shift work must run for a minimum of 5 consecutive workdays.

2nd shift (between the hours of 4:30 PM and 1:00 AM): 8 hours of work + 17.3% of the regular rate, inclusive of benefits.

3rd shift (between the hours of 12:30 AM and 9:00 AM): 8 hours of work + 31.4% of the regular rate per hour, inclusive of benefits.

OVERTIME:

Hours in excess of 8 per day, or before or after the regular wokday Monday through Friday, that is not shift work, and all hours on Saturday shall be paid at time and one-half the regular rate, inclusive of benefits. All hours on Sundays and holidays shall be paid at double the hourly rate, inclusive of benefits.

Four 10-hour days may worked, at straight time, between 7:00 AM and 6:30 PM, Monday through Thursday.

RECOGNIZED HOLIDAYS:

New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day and Christmas Day, or day on which they are legally observed.

Effective Dates:

Rate	Fringe	Total
52.26	35.01	87 27

CLASSIFICATIONS:

Chief Lineman

Effective Dates:

12/04/2016

Rate	Fringe	Total
49.31	33.03	82.34

CLASSIFICATIONS:

Journeyman Lineman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ELECTRICIAN- UTILITY WORK (NORTH) Rates Expiration Date: 12/03/2017

Effective Dates:

12/04/2016

Rate Fringe Total 49.31 33.03 82.34

CLASSIFICATIONS:

Special License Operator

Effective Dates:

12/04/2016

Rate Fringe Total 48.81 32.70 81.51

CLASSIFICATIONS:

Transit Man

Effective Dates:

12/04/2016

Rate Fringe Total 47.33 31.71 79.04

CLASSIFICATIONS:

Line Equipment Operator

Effective Dates:

12/04/2016

Rate Fringe Total 41.42 27.75 69.17

CLASSIFICATIONS:

Dynamite Man

Effective Dates:

12/04/2016

Rate Fringe Total 58.18 38.98 97.16

CLASSIFICATIONS:

General Foreman

Effective Dates:

12/04/2016

Rate Fringe Total 56.70 37.98 94.68

CLASSIFICATIONS:

Assistant General Foreman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ELECTRICIAN- UTILITY WORK (NORTH) Rates Expiration Date: 12/03/2017

Effective Dates:

12/04/2016

Rate Fringe Total 55.22 36.99 92.21

CLASSIFICATIONS:

Line Foreman

Effective Dates:

12/04/2016

Rate Fringe Total 39.94 26.75 66.69

CLASSIFICATIONS:

Straight Light Mechanical Leader

Effective Dates:

12/04/2016

Rate Fringe Total 37.97 25.43 63.40

CLASSIFICATIONS:

Groundman Winch Operator

Effective Dates:

12/04/2016

Rate Fringe Total 37.97 25.43 63.40

CLASSIFICATIONS:

Groundman Truck Operator

Effective Dates:

12/04/2016

Rate Fringe Total 37.47 25.10 62.57

CLASSIFICATIONS:

Straight Light Mechanic

Effective Dates:

12/04/2016

Rate Fringe Total 37.47 25.10 62.57

CLASSIFICATIONS:

Line Equipment Mechanic

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ELECTRICIAN- UTILITY WORK (NORTH) Rates Expiration Date: 12/03/2017

Effective Dates:

12/04/2016

Rate Fringe Total 32.05 21.47 53.52

CLASSIFICATIONS:

Groundman 2nd Year

Effective Dates:

12/04/2016

Rate Fringe Total 29.58 19.81 49.39

CLASSIFICATIONS:

Groundman 1st Year

Effective Dates:

12/04/2016

Rate Fringe Total 48.81 32.70 81.51

CLASSIFICATIONS:

Line Equipment Foreman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ELECTRICIAN- UTILITY WORK (SOUTH) Rates Expiration Date: 12/02/2017

Electrician-Utility Work (South)

(For apprentice rates refer to Electrician-Utility Work (South) in any county rate package).

These rates apply to work contracted for by the following utility company:

Atlantic City Electric.

These rates do not apply to work on substations or switching stations.

For utility work contracted for by a utility company other than the one listed above or those listed under "Electrician-

Utility Work (North), see the "Outside Commercial Rates" for the county in which the jobsite is located.

* FOR OUTSIDE COMMERCIAL RATES PLEASE SEE COUNTY RATES

The regular workday is 8 hours, between 7:00 AM and 4:30 PM.

FOR EMERGENCY WORK ONLY: (emergency work is defined as work caused by storm, catastrophe, act of god, and circumstances beyond the control of the employer)- all hours of work shall be paid at double the hourly rate.

SHIFT DIFFERENTIALS:

Shift work must run for a minimum of 5 consecutive workdays.

When two (2) or three (3) shifts are worked the following shall apply:

1st shift (between the hours of 8:00 AM and 4:30 PM)

2nd shift (between the hours of 4:30 PM and 12:30 AM): 8 hours of work + 10% of the regular rate of pay for 7.5 hours worked.

3rd shift (between the hours of 12:30 AM and 8:00 AM): 8 hours of work + 15% of the regular rate of pay for 7 hours worked.

OVERTIME:

Hours in excess of 8 per day, or before or after the regular wokday Monday through Friday, that is not shift work, and all hours on Saturday shall be paid at time and one-half the regular rate. All hours on Sundays and Holidays shall be paid double the hourly rate.

Four 10-hour days may be worked, at straight time, between 6:00 AM and 6:00 PM, Monday through Thursday with Friday used as a make-up day.

RECOGNIZED HOLIDAYS:

New Year's Day, Memorial Day, July 4th, Labor Day, Veterans' Day, Thanksgiving Day and Christmas Day or on days celebrated.

WORKING RULES:

There shall be a Foreman in charge of each work crew. No crews are to exceed twelve (12) men, including Foremen.

There shall be a General Foreman designated for transmission work when three (3) or more crews are on the same job and for distribution work where there are are more than twenty (20) employees on site.

A small job crew shall consist of five (5) or less employees, one (1) of the Journeyman Linemen in the crew shall be designated as a Small Job Foreman.

Work performed from ladders and/or mechanical lift equipment shall be the work of Linemen and/or Apprentices.

On new construction, fitting and framing poles, towers or structures may be done by Journeymen and/or Apprentices. Groundmen may assist, but may not perform any work which would be performed by Linemen if assembled in the air.

There shall be a Journeyman Lineman in each pole setting, erection, grounding, wire and cable-pulling crew of more than three (3) men.

Effective Dates:

12/04/2016

Rate	Fringe	Total
58.38	45.19	103.57

CLASSIFICATIONS:

General Foreman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ELECTRICIAN- UTILITY WORK (SOUTH) Rates Expiration Date: 12/02/2017

Effective Dates:

12/04/2016

Rate Fringe Total 52.00 41.37 93.37

CLASSIFICATIONS:

Foreman

Effective Dates:

12/04/2016

Rate Fringe Total 49.26 39.74 89.00

CLASSIFICATIONS:

Small Job Foreman

Effective Dates:

12/04/2016

Rate Fringe Total 45.61 37.54 83.15

CLASSIFICATIONS:

Heavy Equipment Operator

Effective Dates:

12/04/2016

Rate Fringe Total 45.61 37.54 83.15

CLASSIFICATIONS:

Cable Splicer

Effective Dates:

12/04/2016

Rate Fringe Total 45.61 37.54 83.15

CLASSIFICATIONS:

Journeyman Lineman

Effective Dates:

12/04/2016

Rate Fringe Total 45.61 37.54 83.15

CLASSIFICATIONS:

Journeyman Welder

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

ELECTRICIAN- UTILITY WORK (SOUTH) Rates Expiration Date: 12/02/2017

Effective Dates:

12/04/2016

Rate Fringe Total 45.61 37.54 83.15

CLASSIFICATIONS:

Journeyman Painter

Effective Dates:

12/04/2016

Rate Fringe Total 36.49 32.08 68.57

CLASSIFICATIONS:

Light Equipment Operator

Effective Dates:

12/04/2016

Rate Fringe Total 31.93 29.37 61.30

CLASSIFICATIONS:

Groundman Truck Driver

Effective Dates:

12/04/2016

Rate Fringe Total 29.65 27.99 57.64

CLASSIFICATIONS:

Groundman 3rd Year

Effective Dates:

12/04/2016

Rate Fringe Total 27.37 26.66 54.03

CLASSIFICATIONS:

Groundman 2nd Year

Effective Dates:

12/04/2016

Rate Fringe Total 25.09 25.29 50.38

CLASSIFICATIONS:

Groundman 1st Year

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE PREVAILING WAGE RATE DETERMINA

ELECTRICIAN- UTILITY WORK (SOUTH) Rates Expiration Date: 12/02/2017

Effective Dates:

12/04/2016

Rate Fringe Total 20.07 22.27 42.34

CLASSIFICATIONS:

Flagman

TERRITORY ENTIRE STATE

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

HEAVY & GENERAL LABORERS- NEW TRANS HUDSON TUNNELS Rates Expiration Date: 08/31/2017

THESE RATES APPLY TO CONSTRUCTION ON NEW TRANS HUDSON TUNNELS ONLY

{For apprentice rates refer to "Laborer - Heavy & General" apprentice rates in any county rate package}

The regular workday consists of 8 hours, starting at 7:00 AM or 8:00 AM.

SHIFT DIFFERENTIALS:

- Shifts must start at 3:00 PM, 4:00 PM, 12:00 AM, or 1:00 AM, to be considered shift work, except when the project owner mandates special hours of work in the job specifications, in which case those hours may be considered shift work.
- When such hours are mandated by the project owner, a shift that begins before midnight on Friday and ends on Saturday morning, or that begins at or after 8:00 PM on Sunday and ends on Monday morning may be paid at the shift differential rate.
- Shifts shall receive an additional \$2.50 per hour.

OVERTIME:

- Hours in excess of 8 per day, Monday through Friday, or outside of the regular workday that are not shift work, and all hours on Saturdays, shall be paid at time and one-half the hourly rate. All hours on Sundays and holidays shall be paid at double the hourly rate.
- Four 10-hour days may be worked, Monday through Thursday, at straight time, with Friday used as a make-up day for a day lost to inclement weather. If Friday is not a make-up day, all hours on Friday shall be paid at time and one-half the hourly rate.

RECOGNIZED HOLIDAYS: New Year's Day, Presidents' Day, Memorial Day, July 4th, Labor Day, Presidential Election Day, Veterans' Day, Thanksgiving Day, Christmas Day. Sunday holidays observed the following Monday. Veterans Day may be substituted for the day after Thanksgiving. However, in the trading of Veterans Day for the day after Thanksgiving, if overtime is worked on Veterans Day, it shall be paid at double the hourly rate.

Hazardous Waste Work:

- -where Level A, B, or C protection is required: + \$3.00/hr
- -other Hazardous Waste site: + \$1.00/hr

Effective Dates:

09/01/2016		03/01/2017	
Rate	Fringe	Total	Total
60.53	27.78	88.31	91.28

CLASSIFICATIONS:

Walking Boss & Superintendent

Effective Dates:

09/01/2016		03/01/2017	
Rate	Fringe	Total	Total
60.08	27.78	87.86	90.83

CLASSIFICATIONS:

Heading Foreman, Shaft Foreman, Rod Foreman, Electrical Foreman, Rigging Foreman

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

ENTIRE STATE

HEAVY & GENERAL LABORERS- NEW TRANS HUDSON TUNNELS Rates Expiration Date: 08/31/2017

Effective Dates:

	09/01/201	6	03/01/2017
Rate	Fringe	Total	Total
59.33	27.78	87.11	90.08

CLASSIFICATIONS:

Iron Foreman, Caulking Foreman, Form Foreman, Cement Finishing Foreman, Concrete Foreman, Track Foreman, Clean-up Foreman, Grout Foreman

Effective Dates:

09/01/2016		03/01/2017	
Rate	Fringe	Total	Total
63.08	27.78	90.86	93.83

CLASSIFICATIONS:

Blaster

Effective Dates:

09/01/2016		03/01/2017	
Rate	Fringe	Total	Total
58.50	27.78	86.28	89.26

CLASSIFICATIONS:

Top Labor Foreman

Effective Dates:

09/01/2016		03/01/2017	
Rate	Fringe	Total	Total
57.98	27.78	85.76	88.73

CLASSIFICATIONS:

Skilled Men (including Caulker, Powder Carrier, all other skilled men)

Skilled Men (including Miner, Drill Runner, Iron Man, Conveyor Man, Maintenance Man, Safety Miner, Rigger, Block Layer, Cement Finisher, Rod Man)

Effective Dates:

09/01/2016		03/01/2017	
Rate	Fringe	Total	Total
57.75	27.78	85.53	88.51

CLASSIFICATIONS:

Semi-Skilled Men (including Bell or Signal Man top or bottom, Form Worker & Mover, Concrete Worker, Shaft Man, Tunnel Laborer, Caulker's Helper, all other semi-skilled)

Semi-Skilled Men (including Miner's Helper, Chuck Tender, Track Man, Nipper, Brake Man, Derail Man, Cable Man, Hose Man, Gravel Man, Form Man)

TERRITORY
ENTIRE STATE

NEW JERSEY DEPARTMENT OF LABOR AND WORKFORCE DEVELOPMENT PREVAILING WAGE RATE DETERMINATION

HEAVY & GENERAL LABORERS- NEW TRANS HUDSON TUNNELS Rates Expiration Date: 08/31/2017

Effective Dates:

09/01/2016		03/01/2017	
Rate	Fringe	Total	Total
57.00	27.78	84.78	87.76

CLASSIFICATIONS:

All others (including Powder Watchman, Change House Attendant, Top Laborer, Job Steward)

SECTION H

ENUMERATION OF PLANS AND SPECIFICATIONS

The following are plans (also called drawings) which form part of this contract:

GENERAL TITLE

COUNTY OF UNION, NEW JERSEY

SENSORY TRAIL IMPROVEMENTS - WATCHUNG RESERVATION

Contract No. BA #5-2017, UNION COUNTY ENGINEERING PROJECT #2016-006

OUR FILE NUMBER H-UN-00206-01

SHEET NUMBER	SPECIFIC TITLE
1	COVER & INDEX SHEET
2	EXISTING CONDITIONS & DEMOLITION PLAN
3	OVERALL SITE PLAN
4	SITE & LANDSCAPE PLAN ENLARGEMENTS
5	GRADING & DRAINAGE PLAN
6	SOIL EROSION & SEDIMENT CONTROL PLAN & DETAILS
7	SOIL EROSION & SEDIMENT CONTROL NOTES & DETAILS
8	CONSTRUCTION DETAILS (1 OF 2)
9	CONSTRUCTION DETAILS (2 OF 2)
10	LANDSCAPE NOTES & DETAILS

TECHNICAL SPECIFICATIONS

CONSIST OF DIVISIONS 1 - General Requirements

2 - Detailed Specifications

APPENDIX A - SENSORY PLAY COMPONENTS

APPENDIX B - PRELIMINARY GAZEBO STRUCTURE DRAWINGS

COUNTY OF UNION UNION COUNTY, NEW JERSEY

SENSORY TRAIL IMPROVEMENTS - WATCHUNG RESERVATION

SPECIAL PROVISIONS

1. Existing Utilities

The contractor shall coordinate all work with the utility companies in the areas of construction. Information regarding existing utilities has been collected from various sources and the contractor is advised that underground object locations, elevations, or types are not warranted to be approximately correct. Nor can they be assumed to be the only subsurface objects, proposed or existing, which may be encountered during the excavation of the work. The contractor shall make all necessary investigations prior to bidding to satisfy himself as to the existing conditions.

Specifically for this project, the Contractor shall coordinate with the appropriate gas utility to reset the existing gas valve to meet proposed grade.

2. Somerset-Union Soil Conservation District Certification

The contractor is advised that a Soil Erosion and Sediment Control Plan Certification is pending for this project. The contractor shall provide a minimum of 72 hours notice to the Somerset-Union Soil Conservation District at (609) 267-7410, prior to the start of ground disturbance.

3. Anticipated Trail Disturbance

The intent of the installation of this sensory trail is to provide minimum disturbance to the existing wooded area. The contractor shall pay specific attention to the overall width of the trail and minimize disturbance throughout the installation. At no time shall the contractor disturb an area greater than ten (10) feet wide unless otherwise noted on the plan set. Any disturbance or damaged trees shall be the responsibility of the contractor to repair and/or remove at no additional cost to the County. Should the excess disturbance result in any fines, penalties or additional work required by any regulating agencies, this also shall be the sole responsibility of the contractor at no additional cost to the County.

4. Contractor's Progress Schedule and Schedule of Values

The contractor shall submit a proposed schedule of operation for the project prior to commencement of construction that clearly indicates how he proposes to conduct the work to bring about the completion of the projects within the Contract Time.

The contractor shall also provide a Schedule of Values detailing an itemized breakdown of all lump sum bid items for progress payment purposes. Said Schedule shall be submitted to and approved by the Engineer prior to the first request for payment submittal.

5. Construction Contingencies

The contractor's attention is specifically directed to the fact that various items and extra quantities have been included in the bid form for contingency purposes in conjunction with this project.

Accordingly, the contractor is hereby advised prior to submitting his bid that he shall take into account the fact that contingencies have been included in the items and that portions of certain items or entire items may not be utilized by the Owner, depending upon the conditions encountered during the work.

To that end, the initial contract award amount may be higher than the final contract amount, depending upon the actual conditions installed.

The contractor should satisfy himself by personal examination of location of the proposed work and surroundings thereof, and by such other means that he prefers, and shall not at any time after submission of the bid, dispute the original estimate of the work, nor assert that there was any misunderstanding in regard to the contingencies included in the quantities.

6. Permits

The contractor shall be responsible for applying for and obtaining all sub-code permits necessary for any/all components of construction in accordance with existing local, county and state regulations.

The appropriate Building Sub-Code Officials shall inspect the construction of any items requiring permits. The presence of the Engineer or his representative shall not relieve the Contractor of his responsibility to call for inspections and/or install the structures in accordance with plans, specifications and codes and standards having jurisdiction.

7. Special Site Conditions

The contractor is advised that the major components of this contract take place in a public facility operated by Union County. It is the intentions of the County to have the adjacent areas remain open and usable during construction. Accordingly, special care shall be exercised to provide adequate safety to the general public, users and county personnel at all times.

Specific details and scheduling of any facility closures due to the proposed improvements shall be coordinated with the Engineer and the County. Work on Sundays and Holidays is prohibited, work on Saturdays and after 5 pm on weekdays must be authorized by the Owner and Engineer.

The contractor shall provide, install and maintain (on a daily basis) fencing, barricades or other suitable materials to protect all active construction areas, newly installed surfaces and construction equipment/supplies from unauthorized access and/or damage during the contract time.

Methods and materials for said protection measures shall be approved by, and coordinated with, the Owner and Engineer.

Separate payment for said protection measures will not be made. Cost of same shall be included in all contract items requiring protection.

8. Excess Topsoil and Fill Material

Contractor to coordinate with Union County for designated areas within Watchung Reservation to deliver excess topsoil and fill material removed from the project site.

SPECIFICATIONS

DIVISION 1 - GENERAL REQUIREMENTS

<u>1-0.1</u>	TABLE OF CONTENTS
1.0.0	SPECIFICATIONS USED
1-0.2 1-2.6	PROGRESS SCHEDULE
1-4.1	BOUNDARIES OF THE WORK
1-4.4	LINES AND GRADES
1-6.3	WORK IN BAD WEATHER
1-6.4.2	WATER AND ELECTRICITY
1-6.4.3	HEATING
1-6.4.4	TRAFFIC PROTECTION AND PARKING OF CARS
1-6.4.5	SURFACE DRAINAGE
1-6.5	DOMESTIC MATERIAL
1-6.17.1	SANITARY-REGULATIONS
1-6.17.2	FINAL CLEANING
1-6.20.2	PROTECTION OF WORK UNTIL COMPLETION
1-6.20.3.1	CARE OF PUBLIC AND PRIVATE PROPERTY
1-6.20.3.2	PROTECTION AND REPLACEMENT OF SUBSURFACE STRUCTURES
	AND UTILITIES
1-6.20.4	ACCIDENT PREVENTION AND FIRST AID
1-6.20.4.1	CONTRACTOR'S SIGNS
1-6.20.4.2	WATCHMEN & FLAGMEN
1-6.23.1	WORKING DRAWINGS
1-13.2	INSPECTION
1-13.3	NOTICE OF INSPECTION TO BE GIVEN BY THE CONTRACTOR
1-13.10	STOPPING WORK
1-18.1	PROJECT PHOTOGRAPHS
1-19.1	ABBREVIATIONS
1-20	EXISTING UTILITIES

SPECIFICATIONS

DIVISION 1 - GENERAL REQUIREMENTS

1-0.2 SPECIFICATIONS USED

THE 2007 STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION OF THE NEW JERSEY DEPARTMENT OF TRANSPORTATION AND AS AMENDED HEREIN, INCLUDING ALL BDC'S http://www.state.nj.us/transportation/eng/specs/2007/Division.shtml ISSUED UNTIL THE DATE OF THE ADVERTISEMENT OF THIS PROJECT SHALL GOVERN THE CONSTRUCTION OF THIS PROJECT AND BE SUPPLEMENTED BY DIVISION 2 OF THE TECHNICAL SPECIFICATIONS

1-2.6 PROGRESS SCHEDULE

Within ten (10) days after the award of the Contract, the Contractor shall submit in writing a proposed program of operation, showing clearly how he proposes to conduct the work so as to bring about the completion of his work within the time limit specified. This program shall outline the proposed sequence of operations, the rates of progress and the dates when each part of his work will be completed. The work under this Contract shall, in general, be so scheduled that the work will be coordinated with work by others on adjacent contracts, if any.

The Contractor shall accompany this schedule with a list of delivery dates for materials and equipment.

This plan of operation may be adjusted and revised as the work progresses, but such changes must have at all times the approval of the Engineer.

In any event it shall be the purpose of the progress schedule to guide the course of the work, and strict adherence to it will be demanded by the Engineer.

If all or part of the work of the Contract will be substantially delayed by the extremes of winter weather, the Contractor shall anticipate such delays, shall prepare his progress schedule in a manner that will minimize the overall effect of such anticipated weather delays, and shall periodically update said schedule in accordance with actual weather delays experienced to that date and anticipated for any subsequent period.

1-4.1 BOUNDARIES OF THE WORK

The Contractor shall obtain from the Owner all information regarding the areas that may be available for his operations and to what extent and for what period of time he may occupy them.

1-4.4 LINES AND GRADES

All work under this Contract shall be constructed in accordance with the lines and grades shown on the Plans or as given by the Engineer. The full responsibility for keeping alignment and grade shall rest upon the Contractor.

Primary reference points for the laying out of the work shall be provided by the Owner.

Lines and grades will be set by a N.J. Licensed Land Surveyor employed by, or retained by the Contractor as the work progresses and will be located to cause as little inconvenience to the prosecution of the work as possible.

The Contractor shall so place excavation and other materials so as to cause no inconvenience in the use of the lines and grades established. He shall remove any obstructions placed by him contrary to this provision.

The Contractor shall furnish and maintain at his own expense, stakes, and other such materials, and give such assistance, including qualified helpers, as may be required for setting line and checking grade marks.

The Contractor shall provide grade sheets at least two (2) working days in advance of the time same will be needed for review, and shall keep the Engineer informed of daily work schedules so that all necessary measurements may be made for record and payment with a minimum of inconvenience to the Engineer or of delay to the Contractor.

It is the intention not to delay the work for the giving of lines and grades, but, when necessary, working operations shall be suspended for such reasonable times as Contractor's surveyor may require for this purpose.

The Contractor shall safeguard all points, stakes, grade marks, monuments and bench marks made or established on the work, re-established them and bear the entire expense of rectifying work improperly installed due to not maintaining or protecting or for removing without authorization such established points, stakes, and marks. Replacement of disturbed or destroyed Principal reference points shall be completed by a N.J. Licensed Land Surveyor, acceptable to the Owner and Engineer, and at the Contractor's expense.

1-6.3 WORK IN BAD WEATHER

During freezing, stormy or inclement weather, the Contractor shall provide heat, shelter, and other facilities as directed and necessary to maintain the progress schedule and all work shall be done in a manner to secure first class construction throughout.

1-6.4.2 WATER AND ELECTRICITY

The Contractor shall unless specified, provide the necessary water supply at his own expense and shall pay for all water used.

The Contractor shall unless otherwise specified, provide, at his own expense, adequate temporary lighting and electrical power facilities if required for the proper prosecution and inspection of the work. If, in the opinion of the Engineer, these facilities are inadequate, the Contractor shall provide facilities which are satisfactory to the Engineer.

1-6.4.3 **HEATING**

The Contractor shall provide temporary heat, whenever required on account of work being carried on during cold weather and to prevent freezing of water pipes and other damage to the work. Heat shall be furnished when and as directed and at the Contractor's own expense.

1-6.4.4 TRAFFIC PROTECTION AND PARKING OF CARS

The Contractor shall protect all traffic and parked cars, when lawfully parked, and shall see to it that the cars belonging to his workmen are parked in areas permitted by the municipal authorities.

He shall take particular care to provide access to adjacent property, both for ordinary traffic and emergency vehicles. Access to fire hydrants shall be kept clear at all times. The Contractor <u>will be required</u> to prevent the formation and flying of dust to the satisfaction of the Engineer by the use of water or chemicals.

Unless expressly authorized in advance and in writing, the Contractor shall maintain a minimum of one lane of traffic through the project area controlled by competent Flagmen as necessary. IMMEDIATE clearance through the project area shall be furnished for Fire/Rescue/Police Vehicles and School Buses. If necessary, work shall be temporarily suspended to permit the immediate passage of Fire/Rescue/Police or other emergency vehicles and/or school buses.

Local and through traffic shall be maintained at all times unless the Owner approves a detour route for a duration of time.

Whenever it is necessary to maintain only a single line of traffic, the contractor shall furnish and employ sufficient competent traffic directors during the day and night to adequately guide and protect traffic.

The Contractor shall erect and maintain barricades, danger signals and warning signs at working sites, closed roads, intersections and other places of danger to traffic or to the completed work as directed and approved by the Engineer. Each barricade shall be provided with red flashing lights battery operated not more than five feet apart and not less than three lights shall be used.

Where specific detour routes or traffic protection signs and equipment are specified or required by the plans, the Contractor will provide same along with all other signage equipment and flagmen necessary to satisfactorily protect and safely coordinate traffic.

Vehicular and pedestrian traffic on streets shall be maintained and protected at all times, and all operations in or adjacent to streets, sidewalks, and walkways shall be conducted and controlled accordingly.

The Contractor shall, for the protection of the traveling public and his personnel, familiarize himself and adhere strictly to the requirements of these Specifications and to the requirements of Title 39, the Motor Vehicle Code of the State of New Jersey, wherever it shall pertain to necessary and required precautionary measures regarding the type of work being done.

The cost of protection of traffic as above described and in addition to uniformed traffic directors shall be as stated in the Division 2 Specifications and in the Proposal.

1-6.4.5 SURFACE DRAINAGE

The Contractor shall furnish all necessary equipment, shall take all necessary precautions, and shall assume the entire cost of handling any surface drainage occurring during the construction of the work. The manner of providing for these flows shall meet the approval of the Engineer and the entire cost of said work shall be deemed included in the unit or lump sum prices for the various items of work to be done under the Contract.

1-6.5 **DOMESTIC MATERIAL**

The contractor during the course of this contract agrees to use, supply or deliver only such manufactured articles, materials and supplies as have been manufactured in the United States substantially from articles, materials and supplies mined, produced or manufactured in the United States, wherever available.

1-6.17.1 SANITARY-REGULATIONS

Toilet accommodations properly secluded from observation shall be erected and maintained by the Contractor, in such a manner and in such locations as approved by the Board of Health, and their use shall be strictly enforced.

The building of shanties or other structures for housing the men, tools, machinery or supplies, will be permitted only at approved places and the sanitary conditions of the ground in and at such shanties or other structures must be at all times maintained in a satisfactory manner.

1-6.17.2 FINAL CLEANING

At the conclusion of the work, all erection plant, tools, temporary structures, and materials belonging to the Contractor shall be promptly taken away, and he shall remove and promptly dispose of all water, dirt, rubbish, or any other foreign substances.

The Contract shall thoroughly clean all equipment and materials installed by him and shall deliver over such materials and equipment undamaged in a bright, clean, polished, and new appearing condition.

1-6.20.2 PROTECTION OF WORK UNTIL COMPLETION

During performance and up to the date of final acceptance, the Contractor shall be under an absolute obligation to protect the finished and unfinished work against any damage, loss or injury. The Contractor shall take proper precautions to protect the finished work from loss or damage, pending completion and the acceptance of all the work included in the entire Contract, provided that such precaution shall not relieve the Contractor from any and all liability and responsibility for loss or damage to the work occurring before acceptance by the Owner. Such loss or damage shall be at the risk of and borne by the Contractor, whether arising from acts or omissions of the Contractor or others, or from floods, storms, high tides, or otherwise. In the event of any such loss or damage, the contractor shall forthwith repair, replace and make good the work without additional compensation or extension of time therefore, except as may be otherwise provided herein.

These provisions shall not be deemed to create any new right of action in favor of third parties against the Contractor or Owner.

The contractor shall provide for the removal of all dirt spilled from the trucks on existing pavements over which it is hauled, or which is washed or otherwise deposited thereon by reason of his work, whenever, in the opinion of the Engineer, the accumulation is sufficient to cause the formation of mud, interfere with drainage or to create a traffic hazard.

Costs incidental to the maintenance of existing roadways as herein described, shall not be paid for under any specific item but shall be included in the unit prices bid for other items scheduled in the Proposal. In the event that the contractor fails to maintain safe traffic conditions and job conditions, the Municipality may after failure of the

contractor to provide safe traffic conditions, hire guards or take such precautions to safeguard traffic, and the cost of same shall be deducted from payment due the contractor.

1-6.20.3.1 CARE OF PUBLIC AND PRIVATE PROPERTY

The Contractor shall preserve from damage all property along the line of the work, or which is in the vicinity of or is in any way affected by the work, the removal or destruction of which is not called for by the Plans. This applies to the public utilities, railroads, trees, monuments, fences, pipe and underground structures, public streets (except natural wear and tear of streets resulting from legitimate use thereof by the Contractor), and wherever such property is damaged due to the activities of the Contractor, it shall be immediately restored to a first class condition by the Contractor and at his own expense.

In case of failure on the part of the Contractor to restore such property, or make good such damage or injury, the Owner may, upon forty-eight hours notice, proceed to repair, rebuild, or otherwise restore such property as may be deemed necessary, and the cost thereof will be deducted from any moneys due or which may become due the Contractor under this Contract.

Nothing in this clause shall prevent the Contractor from receiving proper compensation for his costs incurred because of the removal or replacement of any public or private property, when this is made necessary by alteration of grade or alignment, or any such work authorized by the Owner, provided that such property has not been damaged through fault of the Contractor, his employees, or agents.

1-6.20.3.2 PROTECTION AND REPLACEMENT OF SUBSURFACE STRUCTURES AND UTILITIES

The plans may show certain but not all subsurface structures known to exist in the working area. The Contractor shall particularly note that the indicated locations of subsurface water, gas, electric, telephone, sewerage and drainage systems in the area may be quite different from their actual locations and that there may be some subsurface structure or utility encountered that is not shown on the plans. Therefore, it shall be his responsibility to proceed with caution in executing the work, so as to prevent undue interruptions of utility service to property owners and damage to structures or utilities, or injury to workmen or others.

The Contractor will be held responsible <u>FOR ALL DAMAGES</u> to all utilities or other underground or surface structures whether or not they are shown on the Contract Drawings, and he shall pay all costs for protecting them or for repairing and/or replacing them <u>IF THEY ARE DAMAGED AS A RESULT OF OPERATIONS UNDER THIS CONTRACT.</u>

In the event that <u>UNDERGROUND STRUCTURE OR UTILITIES</u> are disclosed by the Contractor's operations <u>THAT OCCUPY THE SAME SPACE AS REQUIRED BY INSTALLATIONS UNDER THIS CONTRACT</u>, the Contractor shall notify the Engineer and await his orders concerning the removal and replacement of said structures or utilities. The procedures regarding compensation in this event will be as follows:

- a. Where it develops that the utility company will remove and relocate the structure or utility at its own expense and with its own forces, no compensation therefore will be due the Contractor.
- b. Where the utility company will not assume the expense but exercises its right to perform the work with its own forces, the Contractor shall pay the cost incurred upon being presented with a bill for the same, and will in turn be reimbursed by the Owner for the amount paid thereon plus five percent (5%).
- c. Where the Contractor has to perform the work of removal and relocation with his own forces, he shall be reimbursed as set forth under Article G 10.1.1, entitled, "Extra Work Increased Compensation". This provision shall likewise apply to instances under (a) and (b) above, where the contractor's forces or equipment are required for only a portion of the work.

Wherever gas mains, petro-chemical mains, electrical or heating ducts, electric, telephone, or telegraph poles or ducts, private or municipal water mains are encountered and service may be interrupted, the Contractor shall keep the Owner utility company or department fully informed in advance of any changes he desires to make. The Contractor shall cooperate with the utility company or department in the removal, relocation, and replacement of such structures, so as to avoid all unnecessary interruption of service. He shall arrange with the owners of the utilities for this work to be done.

If, in the opinion of the Engineer, it is necessary to install temporary lines, to prevent interruptions in utility service to residents, the Contractor shall install or have installed the temporary lines necessary to provide service. He shall maintain and protect such lines during the course of the work and shall remove them when permanent connections have been made unless otherwise directed by the Engineer. The costs therefore shall be assumed by the Contractor in all cases excepting only where the structure or utility requiring such temporary replacement, occupies the same space as that needed for installations under this Contract, in which event the procedures for compensation listed under (a), (b) and (c) in this Article will be followed.

Such work shall be performed to the satisfaction of the Engineer.

Where the Owner's storm drains, sewer lines, or water mains are encountered and repair, replacement, or relocation is necessary before work can proceed, the Contractor shall carry out the work promptly as directed by the Engineer.

1-6.20.4 ACCIDENT PREVENTION AND FIRST AID

Precautions shall be exercised at all times for the protection of persons and property. The safety provisions and applicable laws, building and construction codes shall be observed. Machinery and equipment shall be guarded and all hazards eliminated in accordance with safety provisions of Construction Industry OSHA Safety and Health Standards (29CFR 1926/1910), including amendments and supplements to date, published by the U.S. Department of Labor, Occupational Safety and Health Administration, to the extent that such provisions are not in contravention of applicable law. The Contractor shall provide suitable barricades, red lights, "Danger" or "Caution" signs and watchmen at all places where the work constitutes in any way a hazard to the public, or workmen.

The Contractor shall keep upon the site, at each location where work is in progress, a completely equipped first-aid kit and shall provide ready access thereto at all times when men are employed on the work.

1-6.20.4.1 CONTRACTOR'S SIGNS

The Contractor shall erect and maintain safety signs, temporary barricades, temporary fences, and take all precautions to guard against all dangers and hazards, as are necessary in the opinion of the Engineer in the interest of the public health and safety.

Signs shall be of suitable size to be readily seen and shall be black letters on orange background. Barricades, drums and like items shall be standard orange and white stripped. Warning and detour signs and barricades and other safety devices shall be reflectorized painted or lighted, and maintained.

1-6.20.4.2 WATCHMEN & FLAGMEN

Watchmen and/or Flagmen shall be furnished and shall be on duty appropriate to carry out the Contractor's responsibility for safety and protection.

1-6.23.1 WORKING DRAWINGS

The Contractor shall promptly prepare and submit layout, detail, and shop drawings for such parts of the work as specified hereafter under the specifications for materials, workmanship and Contract Items. These drawings will be known as "Working Drawings."

The drawings shall be numbered to coincide with the Division and article of the specifications related to same, and consecutively numbered for all individual drawings for a particular item or items related to the particular division and article and shall accurately and distinctly present the following:

- a. All work and erection dimensions.
- b. Arrangement and sectional views.
- Necessary details, including complete information or making connections between work under this Contract and work under other Contracts.
- d. Kinds of materials and finishes.
- e. Parts list and description thereof.

Each drawing shall be dated and shall contain the name of the project, contract number, Contract Item and paragraph number, names of equipment or materials, and the locations at which the equipment or materials are to be installed in the work. The Engineer may decline to consider any working drawing that does not contain complete data on the work and full information on related matters.

If the working drawings show departures from the Contract requirements, the Contractor shall make specific mention thereof in his letter of submittal and on the subject drawing or drawings. Otherwise, approval of such submittals shall not constitute approval of the departures. Approval of the drawings shall constitute approval of the subject matter thereof only and not of any structure, material equipment or apparatus shown or indicated. The approval of drawings will be general and shall not relieve the Contractor of responsibility for the accuracy of such drawings, nor for the proper fitting and construction of the work, nor for the furnishing of materials or work required by the Contract and not indicated on the drawings. No work called for by working drawings shall be done until the said drawings have been approved by the Engineer.

The procedure in seeking approval of working drawings shall be as follows:

- a. The contractor shall submit for approval two prints and one reproducible sepia copy, or six prints in the case of manufacturer's catalogue "cuts" and similar items, of each of the drawings to the Engineer. The submission of drawings shall be accomplished by letter of transmittal in duplicate, containing the name of the project, the name of the Contractor, the number of drawings, titles, and other requirements.
- b. When a drawing is satisfactory to the Engineer, it will be stamped "NO EXCEPTIONS TAKEN", be dated, and two copies thereof will be returned to the Contractor by letter.
- c. Should a drawing be unsatisfactory to the Engineer, he will stamp thereon "REVISE AND RESUBMIT", or "REJECTED", and will return one copy thereof to the contractor with the necessary corrections and changes indicated. The Contractor must make such corrections and changes and again submit two prints and one reproducible sepia copy of the drawing for approval, within five (5) working days of the date of rejection.

The Contractor shall revise and resubmit the working drawings as required by the Engineer, until "NO EXCEPTIONS TAKEN" thereof is obtained.

1-13.2 INSPECTION

During the progress of the work and up to the date of final acceptance, the Contractor shall, at all times afford the representatives of the Owner every reasonable, safe and proper facility for inspecting the work done or being done at the site. The inspection of any work shall not relieve the Contractor of any of his obligations to perform proper and satisfactory work as herein specified. Finished or unfinished work found not to be in strict accordance with the Contract shall be replaced as directed by the Engineer, even though such work may have been previously approved and payment made therefore.

Failure or neglect on the part of the Engineer to condemn or reject bad or inferior work or materials shall not be construed to imply an acceptance of such work or materials, if it becomes evident at any time prior to the final acceptance of the work by the Owner, neither shall it be construed as barring the Owner at any subsequent time, from the recovery of damages or of such a sum of money as may be needed to build anew any portion of the work in which fraud was practiced or improper materials hidden, or used, wherever found.

1-13.3 NOTICE OF INSPECTION TO BE GIVEN BY THE CONTRACTOR

Certain items in the work will require special inspection by the Engineer and/or his inspectors. The Engineer will so specify these items to the Contractor during the course of the work; whereupon the Contractor, before proceeding with such specified items, shall give two working days written notice in advance to the Engineer, for the purpose of scheduling and providing such inspection service.

1-13.10 STOPPING WORK

The Engineer, acting as the Owner's representative, may stop, by written order, or a verbal order confirmed in writing within twenty-four hours, any work or any part of the work under the Contract if in his opinion the methods or materials employed are unsafe, improper or defective. No payment for downtime will be made. When work is

so stopped, it shall not be resumed until the methods or conditions are revised to the satisfaction of the Engineer, which must be signified in writing. Work may also be stopped by the Engineer or required to be postponed for an adequate period of time if the work interferes with, or unduly interrupts the operation of existing utilities. The Contractor is required to fully inform himself as to the nature and location of existing utilities within the project area, all locations of actual or potential interference, and coordinate the activities of affected utilities regarding any necessary temporary or permanent relocations to minimize possible or actual delay to planned progress.

1-18.1 PROJECT PHOTOGRAPHS

<u>IF REQUIRED BY THE TERMS OF THE PROPOSAL</u> and Contract Agreement, only, the Contractor shall provide three sets of acceptable, unretouched 8"x10" glossy, cloth mounted 8-1/2"x11" format, properly identified Preconstruction, Progress, and Final Construction Project Photographs comprising not less than the total number of individual prints stipulated in the proposal, with the cost of same included in the various prices bid. All project photographs shall conform with the following particulars and be delivered as required hereinafter.

1-19.1 ABBREVIATIONS

Where any of the following abbreviations are used in the Specifications they shall have the meaning set forth opposite each.

ACI	American Concrete Institute
ASTM	American Society for Testing Materials
ASCE	American Society of Civil Engineers
AWWA	American Water Works Association
ASME	American Society of Mechanical Engineers
NBS	National Bureau of Standards
AIEE	American Institute of Electrical Engineers
AASHO	American Association of State Highway Officials
NEMA	National Electrical Manufacturers Association
NEC	National Electric Code, latest edition
AISC	American Institute of Steel Construction
ASA	American Standards Association
AWS	American Welding Standards

FEDERAL SPECIFICATIONS

Federal Specifications issued by the Federal Supply Service of the General Services Administration, Washington, D.C.

125 LB. AMERICAN STANDARD

American Standard (ASA B16.1-1948) for Cast Iron Pipe Flanges and Flanged Fittings, Class 125

USS GAUGE United States Standard Gauge

N.J.D.O.T.S.S. New Jersey Department of Transportation Standard Specifications, 2007 (as amended)

GPD Gallons per day
MGD Million gallons per day
GPM Gallons per minute
CFS Cubic feet per second

SPECIFICATION ABBREVIATIONS

Omission in wording. For brevity, some sentences are incomplete and such words and phases as "the contractor shall", in conformity therewith", "shall be", "as noted on drawing", "according to the drawings", "a", "an", "the" and "all" which clutter up most specifications are sometimes omitted. They shall be supplied by the reader.

The contractor shall provide all items, articles, materials, operating methods lists, mentioned or scheduled on drawings or in specifications, including all labor, materials, equipment, incidentals necessary and required for their completion.

Approvals, etc., wherever the words "approved", "satisfactory", "direct", "submitted", "inspected" or similar words or phrases are used, it shall be assumed that the word "Engineer" or one of their representatives follows the verb as the object of the clause, such as "approved by the Engineer" and "submitted to the Engineer".

References to the Standard Specifications or manufacturer's installation directions shall mean to the latest edition thereof, as published prior to the date of the agreement unless otherwise indicated.

Terminology: Words which have well known technical or trade meanings are used herein in accordance with such recognized meanings.

- 1. "Acceptable", "equal to", "proper", and other qualifying terms imply the judgment by the Architect/Engineer.
- 2. "Approved", or "Approval" means any equipment, item or material approved by the Architect/Engineer.
- 3. "Approved equal" means any equipment, item or material approved by the Architect/Engineer as equivalent to the specified equipment, item or material.
- "Concealed" means work which is not exposed to view when the project is complete.
- "Exposed" means work which remains exposed to view when the project is complete.
- 6. "Delivery" means unloading and storing at the site.
- 7. "Furnish" means to supply and deliver to the job.
- 8. "Governmental" means all Municipal, County, State and Federal government agencies.
- 9. "Install" means complete erection and connection of work.
- 10. "Piping" includes piping and all fittings, valves, hangers and other accessories related to piping.
- 11. "Provide" means "furnish" and "install" as defined above.
- 12. Words in singular form shall include as many such devices as are required to complete the work.

1-20 EXISTING UTILITIES

Prior to the start of any excavation work, the contractor shall contact the various utility companies in order to obtain firsthand information of underground piping and conduits:

One recommended number to call for various private utilities is 1-800-272-1000.

SPECIFICATIONS

DIVISION 2 - SITE WORK

TABLE OF CONTENTS

SECTION	PAGE N	<u>۷0.</u>
2A	CLEARING AND PREPARATION OF SITE2-2	
2B	SOIL EROSION AND SEDIMENT CONTROL2-4	
2C	ENVIRONMENTAL PROTECTION MEASURES2-6	
2D	EXCAVATION, BACKFILL, AND GRADING2-8	
2E	STONE AND IMPORT FILL	
2F	ACCESSIBLE SENSORY TRAIL	
2G	CONCRETE SITEWORK2-17	
2H	CONCRETE PAVERS, STONE VENEER SEATWALL, AND FIRE PIT2-26	
21	TIMBER BOARDWALK2-28	
2J	GALVANIZED HANDRAIL SYSTEM2-33	
2K	BRAILLE TRAIL AND INTERPRETATIVE SIGNAGE2-37	
2L	SENSORY COMPONENTS AND SURFACING2-39	
2M	PREFABRICATED SHADE STRUCTURE2-41	
2N	DECORATIVE ARCHWAY2-47	
20	MISCELLANEOUS SITE AMENITIES2-50	
2P	PLANTINGS2-52	
2Q	TOPSOIL, LIME, FERTILIZER, AND SEED2-58	
2R	CLEANUP AND RESTORATION2-62	

SECTION 2A - CLEARING AND PREPARATION OF SITE

WORK INCLUDED

Clearing Site shall consist of removing all natural and artificial obstacles and material from the construction areas and such other areas as may be specified. The above work includes, if applicable, the removal and resetting of street and road signs, mailboxes, fences, guardrail, and any other structures as directed by the Engineer.

The Contractor will be responsible for removing and disposing of the existing park amenities, including but not limited to, the existing paver walkway and patio; flagpole; benches, picnic tables and trash receptacles; utilities; footbridges and foundations; and trees and landscaping.

Also specifically included in this item for this project is the removal and disposal of any existing trees scheduled to be removed.

Clearing and preparation of site shall also include provisions for mobilization, demobilization and general site clean-up during all phases of work *and* at the conclusion of the job.

Clearing limits or limits of disturbance shall be verified at a site meeting of the Engineer and Contractor a minimum of 48 hours prior to any disturbance is scheduled. Protection of trees to remain is to be in accordance with the details in the contract drawings. Any existing trees at or near the proposed edge of disturbance shall be evaluated and, at the discretion of the Engineer, either removed or protected and saved.

If required, existing tree pruning shall be consistent with a "Class 2, medium pruning" in accordance with ISA specifications which indicate the removal of any dead, dying, diseased, objectionable, obstructing and weak branches down to one (1) inch diameter. Field dressing of all tree trunks, limbs or roots following the cutting of same shall utilize approved tree pruning paint to the satisfaction of the Engineer.

If required, root pruning shall be completed along the perimeter of the trail to ensure a clean edge is present for the installation of trail material. Root pruning should be considered only when other options for correcting a conflict between roots and infrastructure are deemed not practical. For trees requiring excess root pruning, a tree assessment shall be conducted and a root-pruning plan shall be developed by a qualified arborist. Crown pruning prior to or following root pruning shall be done only in cases where the potential for structural failure may increase substantially because of root pruning. All root pruning shall be completed in accordance with acceptable practices and reviewed with the Engineer and Certified Tree Experts prior to proceeding.

Restoration, including filling, grading, and topsoil to meet adjacent grade shall be included in this item.

Existing improvements, adjacent properties, utilities and other facilities and trees or landscaping that are not to be removed shall be protected from injury or damage resulting from the Contractor's operations. Areas within the contract limits shall be cleared of all vegetation such as trees, logs, stumps, roots, downed trees, brush, grass, weeds and all other objectionable material as directed by the Engineer.

When or where any direct or indirect damage or injury is done to public, or private property, by or on account of any act or omission, neglect or misconduct, on the part of the Contractor in the execution of the work, such property shall be restored by the Contractor at his expense, to a condition equal to or better than existing before such damage or injury was done, or the Contractor shall provide compensation for the damage or injury in such other manner as may be acceptable to the Owner and/or Engineer.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

CLEARING AND PREPARATION OF SITE, MOBILIZATION AND DEMOBILIZATION

LUMP SUM

ROOT PRUNING (IF AND WHERE REQUIRED)

ALLOWANCE

Compensation for clearing and preparation of site, mobilization and demobilization including all labor, equipment and materials for the work described above shall be included in the lump sum price bid as listed in the bid form.

Compensation for labor and materials required for tree save measures, all pruning, tree and limb removal, field dressing, removal of dead vegetation, and disposal as required by the Engineer shall be included in the bid price for clearing and preparation of site, mobilization and demobilization.

A portion of the bid amount for clearing and preparation of site, mobilization and demobilization based on the approved schedule of values will be retained until final clean-up, restoration, punch lists and demobilization are complete.

Separate payment will not be made for the items associated with clearing and preparation of site for which individual pay items have not been provided in the contract. Payment shall be included in the lump sum price bid for clearing site, and/or the prices bid for all items requiring the same.

SECTION 2B - SOIL EROSION AND SEDIMENT CONTROL

WORK INCLUDED

"Soil Erosion and Sediment Control" shall include the furnishing of all materials, labor, and equipment necessary for implementing proper measures to reasonably control soil erosion from construction operations and prevent excessive flow of sediment from the construction site. Such work may include the installation of water diversion structures, diversion ditches and sediment basins, seeding and mulching, and sodding critical areas to provide temporary protection. All work shall be performed in accordance with the approved soil erosion plan and detail sheets.

MATERIALS

Materials shall conform to the requirements of appropriate articles of "Standard for Soil Erosion and Sediment Control in New Jersey" as revised and adopted January 2014, and the Standard Specification for Road and Bridge Construction of the New Jersey Department of Transportation, 2007 as added to and amended. Such standard specifications are made part of the specifications by this reference and will not be repeated herein. In case of conflict between the above-mentioned requirements, the standard requiring the higher in terms of quality of materials and workmanship shall prevail.

METHODS OF CONSTRUCTION

The work on soil erosion and sediment controls shall include, but not be limited to the following:

- 1. All soil erosion and sediment control practices on this project shall be constructed in accordance with the "Standards for Soil Erosion and Sediment Control in New Jersey", or as approved for this project.
- 2. The smallest practicable area of land shall be exposed at any one time during the project and wherever feasible, natural vegetation shall be retained and protected. Stripping of vegetation, grading or other soil disturbance shall be done in a manner which will minimize soil erosion.
- 3. A schedule of construction operations shall be submitted to the Engineer for his approval.
- 4. A 72-hour notice shall be given to the Engineer prior to the start of construction or grading. This notice can be verbal but must be followed by a written statement not less than forty-eight (48) hours prior to start-up.
- 5. All soil erosion and sediment control devices shall be in place prior to any major soil disturbance or installed and removed in their proper sequence to allow for further operations on the site.
- 6. All sediment control structures shall be checked and maintained on a regular basis and all basins shall be cleaned periodically when storage capacity is affected by siltation.
- 7. During construction, any additional control measures as deemed necessary to prevent erosion or control sediment beyond those measures shown on the approved plans shall be installed or employed at the direction of the Engineer.
- 8. After completion of construction, soil and sediment controls shall be left in place until all disturbed areas are stabilized.
- Disturbed areas including roadway embankments shall be maintained in a rough graded condition and temporarily seeded and/or mulched until proper weather conditions exist for the establishment of permanent vegetative cover.

- 10. All areas disturbed by grading on which permanent or semi-permanent seeding or temporary seeding have not been made and all slopes with a grade steeper than 2:1 shall be treated by mulching. The mulch shall be applied at a rate of 2 tons per acre or equivalent measure, according to State standards.
- 11. All areas disturbed by grading including soil stockpiles, which will not be used or constructed upon a period greater than thirty (30 days) shall be temporarily seeded and protected as required.
- 12. All areas disturbed by grading which will not be constructed upon within six (6) months are to be stabilized with a permanent type seeding and fertilizing.
- 13. All disturbed areas shall be topsoiled, limed and fertilized prior to both temporary and permanent seeding in conformance with charts and tables as set forth in the "Standards for Soil Erosion and Sediment Control in New Jersey".
- 14. Hay bales shall be deemed unacceptable filter material in areas greater than one-half (1/2) acre.
- 15. Access and haul roads shall be protected with stone access strips and coarse stone filters in appropriate locations.
- 16. Fording of streams shall be kept to a minimum and where frequent crossings are contemplated, temporary bridges or culverts shall be constructed.
- 17. Storm drainage inlets are to be either capped or protected by temporary filter devices to prevent the entry of sediment carried by run-off water until vegetation and/or paving is established as planned.
- 18. Wherever well points, pumps or other dewatering methods are used, care shall be taken to provide for the elimination of said dewatering.
- 19. All drainage swales shall be parabolic in shape unless otherwise noted and shall conform to SCS design and standards.
- 20. Drainage swales and other structures shall be located in the field so as to retain as much of the original vegetation as possible, especially large trees.
- 21. Soils having a pH of 4 or less or containing iron sulfide shall be covered with a minimum of 12 inches of soil having a pH of 5 or more before seed bed preparation. The added soil shall be limed as above.
- 22. Roadways shall be swept at the end of each working day by the Contractor. When deemed necessary by the Engineer, the Contractor shall have the roadways swept by a mechanical sweeper. Same shall be provided at no additional cost to the Owner.

MEASUREMENT AND PAYMENT

Separate payment for soil erosion and sediment control will not be made. Payment for Soil Erosion and Sediment Control, including all work and materials as detailed above and required by the soil erosion control plan, including the removal of such measures at completion of the construction project or at such time when all disturbed areas are stabilized, shall be included in the price bid for items requiring same.

SECTION 2C - ENVIRONMENTAL PROTECTION MEASURES

WORK INCLUDED

The Contractor shall install, perform and maintain all environmental protection measures as detailed herein and as shown on the drawings. This section shall apply to all areas of work requiring same and in cases of conflicts with other sections, this section shall govern.

SPILL PREVENTION, REPORTING AND CLEAN-UP

The Contractor shall take precautions to prevent hazardous materials spills. Should a spill occur, the Contractor shall immediately inform the Owner and his Engineer, and shall at Contractor's cost make such reports and complete such clean-up efforts as are required by Federal, State and local regulations. In the event of a spill, the Engineer will call the New Jersey Environmental Action Hotline at (609) 292-7172.

The Contractor shall supply and have on-site at all times, a supply of absorbent booms and other approved materials to isolate and contain possible spills and divert same from catch basins and water courses.

EROSION CONTROL

The Contractor shall install and maintain soil erosion and sediment control measures as indicated on the drawings and as directed by the Engineer.

STOCKPILING

The Contractor shall use environmentally suitable stockpiling sites for the purpose of storing materials, equipment and suitable backfill material. Environmentally suitable sites shall be level, devoid of mature stands of natural vegetation, and be removed from drainage facilities and features, wetlands, streams and stream corridors.

Portions of the construction sites within the construction area boundaries may be utilized as environmentally suitable stockpiling areas.

The Contractor shall use silt fence barriers and shall erect temporary fencing or other barriers to mark the boundary of the stockpile areas. Where fill is to be stored in excess of 14 days, the Contractor shall employ a suitable means of protecting excavated material from wind and water erosion. Erosion control methods may include one or more of the following: mulching, sprinkling, snow fencing, burlap fencing and gravel covering.

Proposed erosion control methods shall be submitted by the Contractor to the Engineer at the Pre-Construction Conference.

DUST CONTROL

The Contractor will furnish shall labor, water spray equipment and water, mechanical sweeping equipment, hand brooms, and any other equipment required for control of dust on the project streets and any adjacent streets used by the Contractor for access to the project.

As often as required during each working day and particularly prior to each working days conclusion, areas under immediate construction (including access roads and other area affected thereby) will be swept clean and wet down sufficiently to lay dust to the Engineer's satisfaction. In addition, these areas will be wet down during non-working hours (including weekends) as often as required to keep the dust under control.

The use of calcium chloride or petroleum products for dust control and soil stabilization is prohibited.

NOISE CONTROL

The Contractor shall be responsible for maintaining noise levels to within acceptable limits. To accomplish this he shall limit the number of machinery in operation to only those required, by requiring all equipment to have adequate mufflers, and by limiting construction activities to hours between 8:00 a.m. and 5:00 p.m. except for essential operations such as dewatering.

PROHIBITED CONSTRUCTION PROCEDURES

- 1. Dumping of spoil material into any stream corridor, any wetlands, any surface waters, or at unspecified locations;
- 2. Indiscriminate, arbitrary, or capricious operation of equipment in any stream corridors, any wetlands, or any surface waters;
- 3. Pumping of silt-laden water from trenches or other excavations into any surface waters, any stream corridors, or any wetlands;
- 4. Damaging vegetation adjacent to or outside of the access road or the right-of-way;
- 5. Disposal of trees, brush, and other debris in any stream corridors, any wetlands, any surface waters, or at unspecified locations;
- 6. Permanent or unspecified alteration of the flow line of the stream, and
- 7. Open burning of project debris.
- 8. Location of storage stockpile areas in ESA's.
- 9. Disposal of excess or unsuitable excavation material in wetlands or floodplains, even with permission of the property owner.

MEASUREMENT AND PAYMENT

Separate payment for environmental protection measures will not be made. Payment for environmental protection measures shall be included in the price bid for items requiring same.

SECTION 2D - EXCAVATION, BACKFILL, AND GRADING

WORK INCLUDED

The work includes all topsoil stripping/removal, excavation, cuts, fills, import material (if required), backfill, grading, compaction, and associated work necessary for the construction of the sensory trail, paver patio and walkways, and appurtenances as shown on the plans or required to complete the work per intent of the specifications.

The Contractor is responsible to establish earthwork quantities to complete all cuts and fills and in order to arrive at the lump sum bid prices for earthwork items listed in the proposal. **Under no circumstances** will additional payment be considered for earthwork bid items required to construct the improvements in accordance with the plans and specifications.

Excavation, fill and backfill work includes transportation, storage in temporary stock piles, backfill, selection, placing and compaction of the various classes of fill and the disposal of unsuitable or surplus materials at approved locations provided by the Contractor. This shall include any and all excavation.

The Contractor shall transport any excess fill derived from construction activities to areas within the Reservation as designated by the Owner.

TOPSOIL SEPARATION

The Contractor shall remove and stockpile all topsoil prior to commencing excavation unless he can demonstrate that he can satisfactorily separate the topsoil from other soils during the work. No topsoil shall be removed from the project site without written consent from the Owner.

All areas to be seeded shall be topsoiled with <u>approved</u> topsoil from onsite or imported if required, to the limits approved by the Engineer. Imported topsoil shall be inspected for approval by the Engineer prior to delivery to the site by representative samples or by visit to the material source. Separate payment for imported topsoil, if used, will not be made.

EXCAVATION AND CLEARANCES

The excavations shall be made to conform with the lines of the finished structures wherever practical. The excavations shall not be carried below the required subgrades. The trench in which pipe, manholes or inlets are to be constructed shall be excavated from the surface and to such depths, and widths (not less than 12 inches nor more than 24 inches greater than the maximum external dimension of the structure) as will give suitable room for bracing and supporting, pumping and draining, and for removing from the excavation any material which the Engineer may deem inadequate for foundation. Any surplus material shall be distributed on the site or removed as directed by the Owner. All excavations shall be of sufficient width to permit work to be done competently, and safely.

The length of the trench to be opened or the area of the surface to be disturbed and restored at any time will be limited by the Owner with regard both to expeditious construction and convenience to the Owner. New trenches will not be excavated if previous trenches are in need of backfilling or labor is needed to restore the surface of the ground to a safe and proper condition.

All excavations for pipelines shall be clear of boulders, rocks, masonry or other similar material which shall be excavated to a level at least six inches below the bottom of the pipe, and shall be fully refilled with approved material mechanically compacted to provide a stable subbase. Rock or boulders shall be removed from sides of trenches to 12 inches minimum outside the wall or the pipe, unless permission to do otherwise is expressly given. Gravel or stone bedding shall be provided, placed and compacted to the minimum depths when indicated on the plans or as ordered by the Engineer. The bottom of the trench shall be excavated where the earth is suitable for good foundation to the form and size of the lower portion of the pipe or other structure, so that there shall be full and adequate support for the structure

which is to be built on it. Ample excavation shall be made under and around the pipe joints for joining and to relieve the bell of shearing forces.

UNAUTHORIZED EXCAVATION

Special care will be taken with the final six inches of all excavations. In no case shall the excavation be carried below the required subgrade by machine and backfill used to establish the required grade. Where the excavation has been carried below subgrade, the Contractor shall, at his own expense refill such areas with compacted 3/4 inch graded gravel or crushed stone to insure the stability of the structure or pipe. If the Contractor excavates below the required subgrade for structures, the over-excavation shall be filled with material subject to the requirements of the Engineer and may include 2000 psi concrete if so ordered by the Engineer, at no additional cost to the Owner.

SHEETING AND BRACING

The Contractor shall fully comply with the applicable requirements of Federal and New Jersey OSHA.

Where necessary for safety or to prevent disturbance, damage or settlement of adjacent structures, pipelines utilities, improvements or paving, excavations shall be sheeted and braced. Any damage to new or existing structures occurring through settlement, water or earth pressure, or other causes due to inadequate construction procedures of the Contractor in any manner, shall be repaired by the Contractor at his own expense.

DEWATERING AND PROTECTION FROM FLOODING

The Contractor shall dewater the excavations promptly and continuously throughout the progress of the work and shall keep the excavations dry at all times until the structures to be built therein, are completed. Where work is to be performed below groundwater level, the Contractor shall provide, operate and maintain dewatering facilities sufficient to maintain the excavation free from groundwater for the time required to complete the work in the proper workmanlike manner.

The Contractor shall protect uncompleted work from flooding during storms or from other causes. All pipelines or structures not stable against uplift during construction or prior to completion shall be thoroughly braced or otherwise protected.

All necessary precautions shall be taken to prevent disturbance of, and to properly drain, the areas upon which concrete is poured, and upon which pipe is to be laid. All concrete shall be kept dry for one month after pouring.

BACKFILLING EXCAVATIONS

The Contractor shall backfill excavations around structures, underneath paved areas, sidewalks, and other areas sensitive to settlements with on site material, if acceptable, which shall be compacted to 90 percent of its modified proctor density determined in accordance with ASTM Specifications D-1557-72T.

All lumber, braces, construction articles, and rubbish shall be carefully removed from behind walls of structures and from other excavations to be backfilled. Unless otherwise specified, all trenches or excavations shall be backfilled and compacted to the original ground surface or to such grades as shall be required. The backfilling outside building walls shall be done in accordance with good practice to prevent after-settlement around all structures and pipelines, and with appropriate equipment to protect same from damage.

The Engineer reserves the right to make such selection of the material for various portions of the backfill as may be required for the satisfactory execution of the work.

Backfill shall not be placed on ground that is frozen, nor shall backfill material be permitted to freeze during placing and compaction.

As soon as practical after the pipe or masonry has been placed and the concrete has acquired satisfactory strength, as determined by the Engineer, the backfilling shall begin and shall be expeditiously completed.

The Contractor shall utilize approved mechanical vibratory compaction equipment to thoroughly consolidate backfill. The backfill shall be installed in approved lifts and compacted to achieve maximum consolidation and minimize subsequent settlement. All backfill in embankments shall be thoroughly compacted by rollers of approved size, type and weight for the particular fill materials.

SITE GRADING

All fill required to provide site grading in accordance with the construction plans shall be of clean material derived from general excavation as found suitable by the Engineer or imported material approved by the Engineer. In the event fill is required to be imported to the jobsite, the Contractor shall provide the Engineer proper certifications to ensure the fill material is free from contaminates. Application of this material shall be as noted in following section entitled "Additional Excavation and Fill". Clay core material shall be furnished and installed per the plans and/or as directed by the Engineer. Representative samples and permeability test results shall be submitted and approved prior to placement of the material. No separate payment will be made for import fill.

ADDITIONAL EXCAVATION AND FILL

Wherever undisturbed material found at the grades shown on the plans for the footings or pipe inverts is not satisfactory in the opinion of the Engineer, the Contractor shall make any additional excavations and disposal of excavated material as directed by the Engineer, and shall refill excavations to the required grade with compacted suitable fill material. The fill material shall be as specified under other applicable sections of these specifications.

Fill material shall be spread in uniform horizontal layers that when compacted shall not exceed 8 inches in thickness. Each lift shall be compacted to 95% of its modified proctor density in accordance with ASTM D-1557-72T. The moisture content of the fill material shall be changed when necessary to attain the specified density. Changing of the moisture content of the fill material shall be accomplished by aerating the soil or by adding water to the fill as required. If wetting or drying is required, each lift shall be thoroughly mixed to insure a uniform distribution of moisture. Compaction shall be accomplished by equipment designed for compacting the type of fill being used as approved by the Engineer. The Contractor shall establish operating procedures to obtain uniform coverage of the area being compacted. During construction, the surface of the fill shall be graded to permit runoff of surface water at all times.

NOTE: All excavated material shall be evaluated by the Engineer or his representatives for the suitability of its re-use within the project for fill material. If the excavated material is found suitable, same shall be used for fill and placed in other locations of the project and compacted in accordance with current NJDOT specifications. Payment for all costs associated with the removal, replacement and compaction of this material as directed by the Engineer shall be included in the unit price bid for all items requiring same.

If the material is deemed unsuitable, it will then become property of the Contractor to dispose of in accordance with applicable Local, State and Federal regulations. Payment for the removal and disposal of unsuitable material shall be included in the prices bid for all items requiring the excavation of the material.

BACKFILLING TRENCHES

No trench or other excavations shall be backfilled until the structure or pipeline in it has been examined and approved. Immediately after inspection and approval the trench or other excavation shall be carefully backfilled with the suitable select excavated material and/or other material as detailed or ordered. Whenever the Engineer deems the excavated material unsuitable for backfilling the Contractor shall furnish acceptable material as may be order by the Engineer. No large rock or frozen earth shall be put in the trench. Suitable material shall be used to fill evenly on both sides of the pipe and carefully tamped or rammed so as not to disturb the pipe joints, at the same time making the filled trench thoroughly compact until the filling reaches one foot above the top of the pipe. When the backfilling has been carried to one foot above the top of the pipe, it shall be thoroughly rammed with tools having faces of 25 to 36 square inches and weighing not less than 20 lbs. Rock in pieces weighing more than 50 lbs. shall not be put in the trench. All spaces between suitable pieces of rock shall be thoroughly filled by backfilling in alternative layers of rock and earth. All sheeting shall be withdrawn, unless otherwise ordered to remain in place in writing by the Engineer.

All pipelines and structures shall be maintained throughout the construction and same shall be left in an equivalent condition or improved condition after completion of construction.

Adequate precautions shall be taken to prevent settlement of existing improvements.

In case water, gas pipes, conduits, or other utilities become broken in the prosecution of the work, the Contractor shall give immediate notice to the proper authorities and shall be responsible for any damage to persons or property caused by such breaks.

If house connections or service pipes supplying water or gas are broken during construction, the Contractor shall immediately repair them at his own expense. Delays, such as would result in adjoining buildings having to do without water or gas for a needlessly long period, will not be tolerated. The municipality reserves the right to remedy such delays by ordering outside parties to make such repairs at the expense of the Contractor.

If directed in writing, the Contractor shall make permanent changes in the location of water and gas mains if they are obstructing the new structures to be built. The cost of such changes will be paid for as extra work based on the valuation made by the Engineer and depend on his decision as to whether the work done is or is not included in the work required and bid for by the Contractor under the contract. In rendering all such accounts the Contractor shall itemize both the labor and material involved and provide other information as may be required by the Engineer.

UNDERGROUND OBJECTS AND UTILITIES

Information as to the location of existing utilities has been collected from various sources, but the result of such investigations as shown on the contract drawings are not guaranteed as to accuracy. The Contractor is particularly directed to the fact that underground objects or material location, elevation, or type is not warranted to be approximately correct (nor can they be assumed to be the only subsurface objects or materials which may be encountered in the work). The Contractor shall make all necessary investigations to satisfy himself as to the existing conditions prior to bidding work. Any deviation in location and number of subsurface utilities and objects field determined by Contractor should be brought to the attention of the Engineer in accordance with Section F4.2 et. seq. of the Standard General Conditions of this contract.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

EARTHWORK AND SUBGRADE PREPARATION, INCLUDING ALL CUTS, FILLS, IMPORT FILL (IF REQUIRED), COMPACTION, GRADING, REMOVAL OF EXCESS/UNSUITABLE SOILS, AND ALL INCIDENTAL WORK

LUMP SUM

Payment for excavation, cuts, fills, compaction and import fill (if required) to achieve proposed grades of the new improvements and removal and disposal of all material deemed excess or unsuitable including all labor, equipment and material shall be included in the lump sum price bid for earthwork and subgrade preparation as listed in the bid form. Under no circumstances will additional payment be considered for earthwork bid items required to construct the improvements in accordance with the plans and specifications. Payments will be made commensurate with the percentage of work completed and in accordance with the approved schedule of values.

SECTION 2E -STONE AND IMPORT FILL

WORK INCLUDED

The Contractor shall furnish and install stone and import fill, if and where required, for miscellaneous purposes to complete the desired improvements. The work includes furnishing, installation and compaction of the material as required by the specifications.

The Contractor shall furnish and install import fill as required to meet the proposed grading plan. The Contractor shall provide a calculation of the import fill required to achieve the proposed grades and deliver to the engineer at the preconstruction meeting in order to determine the number of tests required to be provided by the contractor to the engineer.

MATERIALS

General import fill as required to achieve proposed grades shall consist of clean soil aggregate or soil aggregate and rock meeting the requirements of the New Jersey Department of Transportation Standard Specification for Road and Bridge Construction 2007 Subsection 203.03 for I-13 Soil Aggregate. Soil Aggregate shall conform to Subsection 901.11. Placement, lift thicknesses and compaction of all fill material shall be in accordance with current NJDOT Specifications and the construction details. The top eighteen inches (18") of fill placed shall not contain stones or similar objects larger than two inches (2") in any dimension.

The following shall also be required for import fill material to the site:

- Fill shall be compacted in 12" maximum lifts
- Each lift shall be compacted to 95% of its modified proctor density in accordance with ASTM D-1557-72T
- Delivery tickets shall be provided for all imported material
 - Tickets shall identify the source of the material and Cubic Yardage or Tonage of material provided
- Imported material shall be subject to the submission of gradation test results, priority
 pollutant plus forty test requirements, and material source. One set of test results shall
 be provided for every 10,000 cubic yards of imported material or a minimum of one per
 source. Further, any recycled material to be utilized must come from a state licensed
 recycling facility.

Gradation of I-13 soil aggregate shall conform to the following:

NJDOT I-13 Soil Aggregate

US Standard Sieve Size	Percent Finer By Weight
4"	100
No. 4	30-100
No. 200	0-12

Clean Stone for undercut areas, pipe bedding or surface treatment (only if ordered by the Engineer) shall be cleaned crushed trap rock (3/4") of a quality equal to that required by the New Jersey Department of Transportation "Standard Specification for Road and Bridge Construction - 2007".

Subbase shall be Dense Graded Aggregate (DGA) meeting the New Jersey Department of Transportation Standard Specifications for Road and Bridge Construction 2007, Section 901.10, installed at locations required by the plans or as ordered by the Engineer, graded and compacted to the lines and grades required.

MEASUREMENT AND PAYMENT

Separate payment for clearing, excavation, grading, disposal of excess material and compaction required to complete the work for the items described in this section will not be made. Compensation for said work shall be included in the prices bid for all items requiring same.

Separate payment for all materials described in this section will not be made. Payment for same shall be included in all items requiring same.

SECTION 2F - ACCESSIBLE SENSORY TRAIL

WORK INCLUDED

The Contractor shall provide all necessary labor, materials and equipment to construct the accessible sensory trail as shown on the Drawings or as directed by the Engineer, and as specified below and in other applicable sections of the Specification.

The intent of the installation of this sensory trail is to provide minimum disturbance to the existing wooded area. The contractor shall pay specific attention to the overall width of the trail and minimize disturbance throughout the installation. At no time shall the contractor disturb an area greater than ten (10) feet wide unless otherwise noted on the plan set. Any disturbance or damaged trees shall be the responsibility of the contractor to repair and/or remove at no additional cost to the County. Should the excess disturbance result in any fines, penalties or additional work required by any regulating agencies, this also shall be the sole responsibility of the contractor at no additional cost to the County.

EARTHWORK

The accessible sensory trail is to be constructed to approximately meet existing adjacent grades by removing topsoil/organic matter and 4" of the existing trail to accommodate the thickness of the trail section. Unless otherwise noted the trail shall not exceed five (5) running slope and two (2) percent cross slope. Contractor will be responsible for ensuring final trail construction meets ADA requirements.

Any areas ordered to be over-excavated due to existing conditions shall receive additional thickness of dense graded aggregate, or imported fill (bankrun), or 1½" clean crushed stone as ordered by the Engineer. The work shall include excavation, removal and transport by the contractor of any excess material.

In grassed areas adjacent to the path, restoration shall include a minimum of 4" of topsoil, fertilizer, lime, seed and mulch shall be installed to an appropriate finish grade as directed by the Engineer. Topsoiling shall be in accordance with other applicable sections of these Specifications.

In areas where the trail is installed throughout the wooded area, leaf litter shall be spread in the clear area adjacent to the trail to blend in with the existing conditions.

MATERIALS

Clean Stone for undercut areas or bedding (only if ordered by the Engineer) shall be cleaned crushed trap rock of a quality equal to that required by the New Jersey Department of Transportation "Standard Specification for Road and Bridge Construction" for 1½" crushed stone. Installation of this stone shall include full wrapping of the stone with an approved, permeable filter fabric.

Quarry process crushed stone dust conforming to NJDOT size designation No. 10, red in color, shall be used for the accessible sensory trail and installed at the thickness shown on the plan and underlain with a durable, water permeable filter fabric. Filter fabric catalog cut/specification to be submitted to the Engineer for approval prior to installation. Recycled concrete will not be accepted for this item. Quarry process crushed stone dust shall be adequately compacted ensure stability for the intended use and to meet ADA standards for an accessible trail. The contractor shall submit a physical sample for approval during the shop submittal process to ensure it meets the proper gradation.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

EXCAVATE, 4" THICK, COMPACT SUBGRADE AND CONSTRUCT STONE DUST WALKWAY, 4" THICK, INCLUDING FILTER FABRIC

SQUARE YARD

Payment for constructing the accessible sensory trail to include excavation 4" thick, compacting subgrade, quarry process stone dust surface, 4" thick and permeable filter fabric in accordance with the Contract Drawings, shall be made at the square yard price bid for the quantity actually installed for said items as listed in the bid form. Said prices shall include all materials, labor and incidentals required to complete the installation.

SECTION 2G - CONCRETE SITEWORK

WORK INCLUDED

The work shall consist of the construction of Portland cement concrete structures as shown on the contract drawings and all other incidental concrete work as directed by the Engineer.

The Contractor shall provide all labor, materials and equipment required to construct concrete pads, concrete sidewalks and all concrete work for the modular block walls with solid brick at the locations shown on the plans. Appropriate expansion and construction joints shall be installed under the direction of the Engineer.

QUALITY ASSURANCE

Construction of concrete structures shall comply with provisions of the latest editions of the following codes, specifications and standards, except where more stringent requirements are shown or specified:

- 1. ACI 301 "Specifications for Structural Concrete for Buildings".
- 2. ACI 318 "Building Code Requirements for Reinforced Concrete".
- 3. Concrete Reinforcing Steel Institute, "Manual of Standard Practice".

The Contractor shall employ, at Contractor's expense, a testing laboratory acceptable to Engineer to design concrete mixes and perform material evaluation tests related to the concrete mixes. Materials and installed work may require testing and retesting, as directed by Engineer, at any time during the progress of work. The Contractor shall allow free access to material stockpiles and facilities. Tests, not specifically indicated to be done at Owner's expense, including retesting of rejected materials and installed work, shall be done at Contractor's expense, including retesting and rejected materials and installed work shall be done at contractor's expense.

SUBMITTALS

The Contractor shall submit the manufacturer's product data with application and installation instructions for proprietary materials and items, including reinforcement and forming accessories, admixtures, patching compounds, joint systems, curing compounds, and others as requested by Engineer.

The Contractor shall submit shop drawings for fabrication, bending, and placement of concrete reinforcement. Comply with ACI 315 "Manual of Standard Practice for Detailing Reinforced Concrete Structures" showing bar schedules, stirrup spacing, diagrams of bent bars, arrangement of concrete reinforcement. Include special reinforcement required and openings through concrete structures.

The Contractor shall submit samples of materials as specified and as otherwise requested by Engineer, including names, sources and descriptions. Laboratory test reports for concrete materials and mix design tests shall be submitted if requested by the Engineer.

The Contractor shall provide materials certificates for cement, aggregates, admixtures, reinforcing, welded wire fabric, non-shrink grout, curing compounds and non-slip aggregates. Material certificates shall be signed by manufacturer and Contractor, certifying that each material item complies with, or exceeds, specified requirements.

FORM MATERIALS

Formwork for exposed concrete surfaces shall be plywood, metal, metal-framed plywood faced or other acceptable panel-type materials, to provide continuous, straight, smooth, exposed surfaces. Furnish in

largest practicable sizes to minimize number of joints and to conform to joint system when shown on drawings. Provide form material of sufficient thickness to withstand pressure of newly-placed concrete without bow or deflection.

Formwork for unexposed concrete in finished structure shall be with plywood, lumber, metal or other acceptable material. Provide lumber dressed on at least 2 edges and one side for tight fit.

All forms shall be provided with commercial formulation form-coating compounds that will not bond with, stain nor adversely affect concrete surfaces, and will not impair subsequent treatments of concrete surfaces.

REINFORCING MATERIALS

Reinforcing materials for all concrete structures shall comply with the following:

- 1. Reinforcing Bars: ANSI/ASTM A 615, Grade 60, deformed.
- 2. Steel Wire: ANSI/ASTM A 82, plain, cold-drawn, steel.
- 3. Welded Wire Fabric (WWF): ANSI/ASTM A 185, welded steel wire fabric.
- 4. Supports for Reinforcement: Provide supports for reinforcement including bolsters, chairs, spacers and other devices for spacing, supporting and fastening reinforcing bars and welded wire fabric in place. Use wire bar type supports complying with CRSI recommendations, unless otherwise acceptable.

CONCRETE MATERIALS

Concrete materials for all concrete structures shall comply with the following:

- 1. Portland Cement: ANSI/ASTM C 150, Type I, unless otherwise acceptable to Engineer.
- 2. Normal Weight Aggregates: ANSI/ASTM C 33, and as herein specified. Provide aggregates from a single source for exposed concrete.
- 3. Water: Potable.
- 4. Air-Entraining Admixture: ANSI/ASTM C 260, and shall be an aqueous solution of completely neutralized vinsol resin.
- 5. Water-Reducing Admixture: ANSI/ASTM C 494, Type A, and contain not more than 0.05% chloride ions.
- 6. High-Range Water-Reducing Admixture (Super Plasticizer): ASTM C 494, Type F or Type G and contain not more than 0.05% chloride ions.
- 7. Non-Corrosive, Non-Chloride Accelerator Admixture: ASTM C 494, Type C or E, and contain no more chloride ions than are present in municipal drinking water. The manufacturer must have long-term test data (at least a year), from an independent testing laboratory, concerning corrosion using an acceptable accelerated corrosion test method such as that using electrical potential measures.
- 8. Water Reducing, Retarding Admixture: ASTM C 494, Type D, and contain not more than 0.05% chloride ions.
- 9. Calcium chloride, or admixtures containing more than 0.05% chloride ions are not permitted.

- 10. Certification of conformance to the above mentioned requirements and the chloride content of the admixture will be required from the admixture manufacturer prior to review of mix design.
- 11. Non-Shrink Grout: CRD-C-621-89a, Grade "C" (equipment grouting) or Grade "B" (Construction Grouting), Corps of Engineers Specification for Non-Shrink Grout, Type D, Non-metallic. In addition, the manufacturer shall furnish data from an independent laboratory indicating that the grout, when placed at a fluid consistency shall achieve 95% bearing under a 4'x4' base plate.
- 12. Evaporation Control: Monomolecular film-forming compound applied to exposed concrete slab surfaces for temporary protection from rapid moisture loss.
- 13. Liquid Membrane-Forming Curing and Sealing Compound: Water-based acrylic type, 30% solids content minimum, and have test data from an independent testing laboratory indicating a maximum moisture loss of 0.55 kg per sq m in 72 hours when applied at the coverage rate recommended by the manufacturer.
- 14. Patching Mortar: Free-flowing, polymer-modified cemetitious coating.
- 15. Bonding Admixture: The compound shall be a latex, non-rewettable type.

PROPORTIONING AND DESIGN OF MIXES

The Contractor or Contractor's representative shall prepare design mixes for each type and strength of concrete by either laboratory, the trial batch, or field experience methods as specified in ACI 301. If trial batch method is used, use an independent testing facility acceptable to Engineer. The testing facility shall not be the same as used for field quality control testing unless otherwise acceptable to Engineer. If trial batch mixes are used, the mix design shall achieve an average compressive strength 1200 psi greater that the specified strength.

The Contractor shall submit written reports to the Engineer of each proposed mix for each class of concrete at least 15 days prior to start of work. The Contractor shall not begin concrete production until the Engineer has reviewed mixes. Design mixes shall provide normal weight concrete as indicated on contract drawings.

Mix design adjustments may be requested by the Contractor when characteristics of materials, job conditions, weather, test results, or other circumstances warrant, at no additional cost to Owner and as accepted by Engineer. Laboratory test data for revised mix design and strength results must be submitted to and accepted by Engineer before using in work.

The mix design shall use water-reducing admixture or high range water-reducing admixture (super plasticizer) in all concrete. High range water-reducing admixture shall be used in all concrete to be pumped and all concrete containing synthetic fiber additive.

Non-corrosive accelerating admixture shall be used in concrete slabs placed at ambient temperatures below 50°F (10°C). Air-entraining admixture shall be used in exterior exposed concrete, unless otherwise indicated. Add air-entraining admixture at manufacturer's prescribed rate to result in concrete at point of placement having air content within following limits:

Concrete structures and slabs exposed to freezing and thawing or subjected to hydraulic pressure:

- 1. 5.5% for 1 ½" 2" aggregate.
- 2. 6% for $\frac{3}{4}$ " 1" aggregate.
- 3. 8% for $3/8" \frac{1}{2}"$ aggregate.

All interior slabs subject to vehicular abrasion shall have a maximum air content not greater than 3%. Other Concrete: 2% to 4% air.

Slump Limits: Proportion and design mixes to result in concrete slump at truck as follows:

- 1. Ramps and sloping surfaces: Not more than 3".
- 2. Reinforced foundation systems: Not less than 1" and not more than 3".
- 3. Concrete containing HRWR admixture (super plasticizer): Not more than 8" after addition of admixture nor more than 3" prior to addition of admixture.
- 4. Other concrete: Not less than 1" and not more than 4".

CONCRETE MIXES

Ready-Mix Concrete shall comply with requirements of ANSI/ASTM C94 and as herein specified. Addition of water to the batch will not be permitted. During hot weather, or under conditions contributing to rapid setting of concrete, a shorter mixing time than specified in ANSI/ASTM C 94 may be required. When air temperature is between 85°F (30°C) and 90°F (32°C), reduce mixing and delivery time from 1-1/2 hours to 75 minutes, and when air temperature is above 90°F (32°C), reduce mixing and delivery time to 60 minutes.

FORMS

The Contractor shall design, erect, support, brace and maintain formwork to support vertical and lateral loads that might be applied until such loads can be supported by concrete structure. Construct formwork so concrete members and structures are of correct size, shape, alignment, elevation and position. Construct forms to sizes, shapes, lines and dimensions shown, and to obtain accurate alignment, location, grades, level and plumb work in finished structures. Provide for openings, offsets, sinkages, keyways, blocking, screeds, bulkheads, anchorages and inserts, and other features required in work. Use selected materials to obtain required finishes. Solidly butt joints and provide back-up at joints to prevent leakage of cement paste.

Forms shall be fabricated for easy removal without hammering or prying against concrete surfaces. Provide crush plates or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces where slope is too steep to place concrete with bottom forms only. Kerf wood inserts for forming keyways, reglets, recesses, and the like, to prevent swelling and for easy removal.

Temporary openings shall be provided where interior area of formwork is inaccessible for cleanout, for inspection before concrete placement, and for placement of concrete. Securely brace temporary openings and set tightly to forms to prevent loss of concrete mortar. Locate temporary openings if forms at inconspicuous locations.

Chamfer exposed corners and edges, using wood, metal, PVC or rubber chamfer strips fabricated to produce uniform smooth lines and tight edge joints.

Form Ties shall be factory-fabricated, adjustable-length, removable or snapoff metal form ties, designed to prevent form deflection, and to prevent spalling concrete surfaces upon removal. Unless otherwise indicated, provide ties so portion remaining within concrete after removal is at least 1-1/2" inside concrete and will not leave holes larger than 1" diameter in concrete surface.

Thoroughly clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt or other debris just before concrete is placed. Retighten forms and bracing after concrete placement is required to eliminate mortar leaks and maintain proper alignment.

PLACING REINFORCEMENT

Comply with Concrete Reinforcing Steel Institute's recommended practice for "Placing Reinforcing Bars", for details and methods of reinforcement placement and supports, and as herein specified.

Clean reinforcement of loose rust and mill scale, earth, ice, and other materials which reduce or destroy bond with concrete. Accurately position, support and secure reinforcement (including welded wire fabric) against placement by formwork, construction, or concrete placement operations. Locate and support reinforcing by metal chairs, runners, bolsters, spacers, and hangers, as required.

Reinforcement shall be placed to obtain at least minimum coverages for concrete protection. Arrange, space and securely tie bars and bar supports to hold reinforcement in position during concrete placement operations. Set wire ties so ends are directed into concrete, not toward exposed concrete surfaces.

Install welded wire fabric in as long lengths as practicable. Lap adjoining pieces at least one full mesh and tie splices with wire. Offset end laps in adjacent widths to prevent continuous laps in either direction.

JOINTS

Locate and install construction joints, which are not shown on drawings, so as not to impair strength and appearance of the structure, as acceptable to Engineer.

Provide keyways at least 1-1/2" deep in construction joints in walls, slabs and between walls and footings; accepted bulkheads designed for this purpose may be used for slabs.

Place construction joints of members perpendicular to the main reinforcement. Continue reinforcement across construction joints or structural members.

Isolation Joints in Slabs-on-Ground: construct isolation joints in slabs-on-ground at points of contact between slabs on ground and vertical surfaces, such as column pedestals, foundation walls, grade beams and elsewhere as indicated.

PREPARATON OF FORM SURFACES

Contact surfaces of forms shall be coated with a form-coating compound before reinforcement is placed. Thin form-coating compounds only with thinning agent of type, and in amount, and under conditions of form-coating compound manufacturer's directions. Do not allow excess form-coating material to accumulate in forms or to come into contact with concrete surfaces against which fresh concrete will be placed. Apply in compliance with manufacturer's instructions.

Steel forms shall be coated with a non-straining, rust-preventative form oil or otherwise protect against rusting. Rust-stained steel formwork is not acceptable.

CONCRETE PLACEMENT

Before placing concrete, the Engineer shall inspect formwork installation, reinforcing steel, and items to be embedded or cast-in. The Contractor shall notify other crafts to permit installation of their work and shall cooperate with other trades in setting such work. Moisten wood forms immediately before placing concrete where form coatings are not used.

The Contractor shall coordinate the installation of joint materials and moisture barriers with placement of forms and reinforcing steel.

Concrete shall be deposited continuously or in layers of such thickness that no concrete will be placed on concrete which has hardened sufficiently to cause the formation of seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as herein specified. Deposit concrete as nearly as practicable to its final location to avoid segregation. Deposit concrete in forms in horizontal layers not deeper than 24" and in a manner to avoid inclined construction joints. Where placement consists of several layers, place each layer while preceding layer is still plastic to avoid cold joints.

When placing concrete in cold weather, protect concrete work from physical damage or reduced strength which could be caused by frost, freezing actions, or low temperatures, in compliance with ACI 306 and as herein specified. When air temperature has fallen to or is expected to fall below 40°F (4°C), uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50°F (10°C), and not more than 80°F (27°C) at point of placement. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.

Only the specified non-corrosive non-chloride accelerator shall be used. Calcium chloride, thiocyanate or admixtures containing more than 0.05% chloride ions are not permitted.

When placing concrete in hot weather, low humidity or dry winds or other conditions suitable for plastic cracking, the evaporation retarder "Eucobar" by The Euclid Chemical Co. or "Confilm" by Master Builders may be required to be applied by spray one or more times during the finishing operation. Cool ingredients before mixing to maintain concrete temperature at time of placement below 90°F (32°C). Mixing water may be chilled, or chopped ice may be used to control temperature provided water equivalent of ice is calculated to total amount of mixing.

Cover reinforcing steel with water-soaked burlap if it becomes too hot, so that steel temperature will not exceed the ambient air temperature immediately before embedment in concrete.

Forms shall be wetted thoroughly before placing concrete.

Use water-reducing retarding admixture (Type D) when required by high temperatures, low humidity, or other adverse placing conditions.

FINISH OR FORMED SURFACES

Rough form finish shall be used for formed concrete surfaces not exposed-to-view in the finish work or by other construction, unless otherwise indicated. This is the concrete surface having texture imparted by form facing material used, with tie holes and defective areas repaired and patched and fins and other projections exceeding ½" in height rubbed down or chipped off.

Smooth form finish shall be used for formed concrete surfaces exposed-to-view, or that are to be covered with a coating material applied directly to concrete, or a covering material applied directly to concrete, such as waterproofing, dampproofing, painting or other similar system. This is as-cast concrete surface obtained with selected form facing material, arranged orderly and symmetrically with a minimum of seams. Repair and patch defective areas with fins or other projections completely removed and smoothed.

Smooth rubbed finish shall be used, where indicated, which have received smooth form finish treatment, not later than on day after form removal.

At tops of walls, horizontal offsets and surfaces occurring adjacent to formed surfaces, strike-off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces, unless otherwise indicated.

MONOLITHIC SLAB FINISHES

Float finish shall be applied to monolithic slab surfaces to receive trowel finish and other finishes as hereinafter specified and slab surfaces which are to be covered with membrane or elastic waterproofing, membrane or elastic roofing, or sand-bed terrazzo, and as otherwise indicated.

After screeding, consolidating, and leveling concrete slabs, do not work surface until ready for floating. Begin floating when surface water has disappeared or when concrete has stiffened sufficiently to permit operation to power driven floats, or both consolidate surface with power-driven floats, or by hand-floating is area is small or inaccessible to power units. Check and level surface plane to a tolerance of F_f20/F1₁17. Cut down high spots and fill low spots, refloat surface to a uniform, smooth, granular texture.

Trowel finish shall be applied to monolithic slab surfaces to be exposed-to-view, and slab surfaces to be covered with resilient flooring, carpet, ceramic or quarry tile, paint or other thin film finish coating system. After floating, begin first trowel finish operation using a power-driven trowel. Begin final troweling when surface produces a ringing sound as trowel is moved over surface. Consolidate concrete surface by final hand-troweling operation, free of trowel marks, uniform in texture and appearance, and with a surface leveled to a tolerance of $F_f25/F1_120$. Surface defects which would telegraph through applied floor covering system are to be ground smooth.

Non-slip broom finish shall be applied to exterior concrete platforms, steps and ramps, and elsewhere as indicated. Immediately after trowel finishing, slightly roughen concrete surface by brooming with fiber bristle broom perpendicular to main traffic route. Coordinate required final finish with Engineer before application.

CONCRETE CURING AND PROTECTION

The Contractor shall protect freshly placed concrete from premature drying and excessive cold or hot temperatures. In hot, dry, and windy weather, protect concrete from rapid moisture loss before and during finishing operations with an evaporation-control material. Apply in accordance with manufacturer's instructions after screeding and bull floating, but before power floating and troweling.

Initial curing shall be started as soon as free water has disappeared from concrete surface after placing and finishing. Weather permitting, keep continuously moist for not less than 7 days. Perform curing of concrete by curing and sealing compound, by moist curing, by moisture-retaining cover curing, and by combinations thereof, as herein specified.

Concrete surfaces shall be covered with moisture-retaining cover for curing concrete, placed in widest practicable width with sides and ends lapped at least 3 inches and sealed by waterproof tape or adhesive. Immediately repair any holes or tears during curing period using cover material and waterproof tape.

The specified curing and sealing compound shall be applied to concrete slabs as soon as final finishing operations are complete (within 2 hours and after surface water sheen has disappeared). Apply uniformly in continuous operation by power spray or roller in accordance with manufacturer's directions. Recoat areas subjected to heavy rainfall within 3 hours after initial application. Maintain continuity of coating and repair damage during curing period.

Membrane curing compounds shall be used that will not affect surfaces to be covered with finish materials applied directly to concrete.

Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces, by moist curing with forms in place for full curing period or until forms are removed. If forms are removed, continue curing by methods specified above, as applicable.

Cure unformed surfaces, such as slabs, floor topping, and other flat surfaces, by application of appropriate curing method.

REMOVAL OF FORMS

Formwork not supporting weight of concrete, such as sides of beams, walls, columns, and similar parts of the work, may be removed after cumulatively curing at not less than 50°F (10°C) for 24 hours after placing concrete, provided concrete is sufficiently hard to not be damaged by form removal operations, and provided curing and protection operations are maintained.

Formwork supporting weight of concrete, such as beam soffits, joints, slabs and other structural elements, may not be removed until concrete has attained design compressive strength (f'c) but in no case shall the

forms be removed in less than 14 days. Determine potential compressive strength of in-place concrete by testing field-cured specimens representative of concrete location or membrane.

REUSE OF FORMS

The Contractor shall clean and repair surfaces of forms to be re-used in work. Split, frayed, delaminated or otherwise damaged form facing material will not be acceptable for exposed surfaces. Apply new form coating compound as specified for new formwork.

When forms are extended for successive concrete placement, thoroughly clean surfaces, remove fins and laitance, and tighten forms to close joints. Align and secure joint to avoid offsets. Do not use "patched" forms for exposed concrete surfaces, except as acceptable to Engineer.

CONCRETE SURFACE REPAIRS

All defective areas shall be repaired and patched with cement mortar immediately after removal of forms, when acceptable to Engineer.

Cut out honeycomb, rock packets, voids over ¼ inch in any dimension, and holes left by tie rods and bolts, down to solid concrete but in no case to a depth of less than 1 inch. Make edges of cuts perpendicular to the concrete surface. Thoroughly clean, dampen with water, and brush-coat the area to be patched with specified bonding agent. Place patching mortar before bonding compound has dried.

For exposed-to-view surfaces, blend white portland cement and standard portland cement so that, when dry, patching mortar will match color surrounding. Provide test areas at inconspicuous location to verify mixture and color match before proceeding with patching. Compact mortar in place and strike-off slightly higher than surrounding surface.

The Contractor shall remove and replace concrete having defective surfaces if defects cannot be repaired to satisfaction of Engineer. Surface defects, as such, include color and texture irregularities, cracks, spalls, air bubbles, honeycomb, rock pockets, fins and other projections on surface, and stains and other discolorations that cannot be removed by cleaning. Flush out form tie holes, fill with dry-pack mortar, or precast cement cone plugs secured in place with bonding agent.

The Contractor shall repair concealed formed surfaces, where possible, that contain defects that affect the durability of concrete. If defects cannot be repaired, remove and replace concrete.

Unformed surfaces, such as monolithic slabs, shall be tested for smoothness and verify surface lane to tolerances specified for each surface and finish. Correct low and high areas as herein specified. Test unformed surfaces sloped to drain for trueness of slope and smoothness by using a template having required slope.

The Contractor shall repair finished unformed surfaces that contain defects that affect durability of concrete. Surface defects, as such, include crazing and cracks in excess of 0.01 inch wide or that penetrate to reinforcement or completely through nonreinforced sections regardless of width, spalling, popouts, honeycomb, rock pockets, and other objectionable conditions.

High areas in unformed surfaces shall be corrected by grinding after concrete has cured at least 14 days. Low areas in unformed surfaces shall be corrected during or immediately after completion of surface finishing operations by cutting out low areas and replacing with patching compound. Repaired areas shall be finished to blend into adjacent concrete. Proprietary underlayment compounds may be used when acceptable to Engineer.

The Contractor shall repair defective areas, except random cracks and single holes not exceeding 1 inch in diameter, by cutting out and replacing with fresh concrete. Remove defective areas to sound concrete with clean, square cuts and expose reinforcing steel with at least ¾-inch clearance all around. Dampen

concrete surfaces in contact with patching concrete of same materials to provide concrete of same type or class as original concrete. Place, compact, and finish to blend with adjacent finished concrete. Cue in same manner as adjacent concrete.

The Contractor shall perform structural repairs with prior approval of Engineer for method and procedure, using specified epoxy adhesive and mortar. Repair methods not specified above may be used, subject to acceptance of Engineer.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

CONCRETE DEPRESSED CURB

LINEAR FOOT

Causes for Rejection of Concrete Walks / Pads and Driveways

Concrete walks and pads shall be rejected and ordered replaced by the Engineer if any or all of the following should occur or exist:

- A. Staining or discoloration of concrete sidewalk.
- B. Walk / pad or driveway is out of alignment.
- C. Walk / pad or driveway is out of grade.
- D. Joints and surfaces are improperly finished.
- E. Expansion joints protrude from concrete.
- F. Cracks, chips, or other damages occur during construction or maintenance period.
- G. Settlement of walk or driveway.
- H. Inspection not asked for prior to pouring of concrete.
- I. Improper vibration of concrete.
- J. Vandalism during initial setup of concrete.

Payment for the depressed concrete curb will be made at the linear foot bid price for said items as listed in the bid form. Said prices shall include all materials, labor and incidentals required to complete the installation.

Separate payment will not be made for removal, disposal, and replacement of walks and driveways rejected due to the causes of rejection listed above.

Separate payment for the all items requiring footings / foundations will not be made. Compensation for these items shall be included in the bid price for said items.

SECTION 2H - CONCRETE PAVERS, STONE VENEER SEATWALL AND FIRE PIT

WORK INCLUDED

The contractor shall construct concrete paver walkways, patio areas, stone veneer seatwalls and fire pit as designated on the plans, including all excavation, sub-base material, foundations, reinforcement, edging and labor necessary.

MATERIALS

CONCRETE PAVER WALKWAY AND PATIO

The concrete pavers shall be 'Brickstone' as manufactured EP Henry (800-444-3679), or an approved equal. Colors shall be 'Dakota Blend' for the field and 'Harvest Blend' for the soldier course.

The pavers shall be installed in accordance with the manufacturer's instructions and with the construction details.

Bedding sand shall conform to Subsection 901 of the NJDOT Standard Specifications for Road and Bridge Construction, Latest revision.

Aggregate base shall conform to Subsection 901 of the NJDOT Standard Specifications for Road and Bridge Construction, Latest revision.

Edge restraint along the paver areas is required. The type of edge restraint shall be as approved by the Engineer. No separate payment will be made.

21" HIGH STONE VENEER RETAINING WALL

Construction of the 21" high stone veneer seatwall shall utilize precast concrete masonry units. Stone veneer shall be utilized for all vertical faces of the seatwall and shall be 'Ledgestone' Style 'Aspen', as manufactured by EP Henry (800-444-3679), or an approved equal.

Caps shall be a 2" thick Bluestone, 1'-0" wide, adhered to top of concrete masonry units/ stone veneer. Bluestone caps shall be cut to fit around the exact design of the concrete masonry units of the seatwall, maintaining a 1" overhang for a clean appearance.

FIRE PIT KIT AND STORAGE RACK

The fire pit kit shall be 'Cast Stone Wall Fire Pit Kit' and shall be 'Breckenridge' in color as manufactured EP Henry (800-444-3679), or an approved equal. The kit is comprised of the necessary components to construct a 47" wide circular fire pit with stone cap. Fire Pit Kit shall be set upon a twelve (12) inch compacted aggregate base.

Aggregate base shall conform to Subsection 901 of the NJDOT Standard Specifications for Road and Bridge Construction, Latest revision.

The fire wood storage rack shall be 'The Woodhaven ¼ Cord Plus Rack' provided by The Woodhaven and manufactured by Alexander Manufacturing (888-421-5010) or approved equal. The rack shall measure 4'H, 5'W and 14"D and be set upon a 4" thick concrete slab. The rack shall also be provided with a cover for the appropriate size.

The fire pit kit and storage rack shall be installed in accordance with the manufacturer's instructions and with the construction details.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

CONCRETE PAVER PATIO,

INCLUDING SUB-BASE SQUARE YARD

CONCRETE PAVER WALKWAY,

INCLUDING SUB-BASE SQUARE YARD

STONE VENEER SEATWALL, 21" HIGH, INCLUDING

CONCRETE FOOTING LINEAR FOOT

FIRE PIT KIT, INCLUDING SUB-BASE UNIT

FIRE WOOD STORAGE RACK WITH COVER, INCLUDING 4" THICK CONCRETE PAD

UNIT

Payment for construction of the concrete paver patio and walkways will be made at the square yard price bid as listed in the bid form for the quantity actually installed. No separate payment will be made for labor, materials, sub-base, or any appurtenances necessary for a complete installation.

Payment for construction of the stone veneer seatwall will be made at the linear foot price bid as listed in the bid form for the quantity actually installed. No separate payment will be made for labor, materials, sub-base, or any appurtenances necessary for a complete installation.

Payment for the Fire Pit Kit will be made at the unit bid price for said items as listed in the bid form. Said prices shall include all materials, hardware, aggregate base, labor, and incidentals necessary for a complete and functioning system.

Payment for the Fire Wood Storage Rack will be made at the unit bid price for said items as listed in the bid form. Said prices shall include all materials, hardware, concrete base, anchoring, and incidentals necessary for a complete and fully functioning system.

SECTION 2I – TIMBER BOARDWALK

WORK INCLUDED

The Contractor shall provide all labor, materials and equipment necessary to furnish and install the timber boardwalk in accordance with the contract drawings and as directed by the Engineer or Engineer.

SECTION INCLUDES

- A. Coordination of boardwalk framing work with the foundation installation.
- B. Fabrication, galvanizing and furnishing of metal bolts, assemblies and fittings as indicated on the drawings and specified herein;
- C. Furnishing of pressure treated structural lumber framing members of the grades and dimensions as indicated on the drawings and specified herein.
- D. Setting and connecting structural timber girders on foundation posts in accordance with the plans and details and as specified herein.
- E. Installing and anchoring the treated timber deck framing including girders, stringers, and supplementary connections for railing systems (where required).
- F. Installation of fascia boards as indicated on the plans and specified herein.
- G. Furnishing and installing pressure treated cedar decking conforming to the grade and dimensional criteria indicated on the plans and specified herein.
- H. Cleanup of debris both beneath and alongside the boardwalk related to the deck framing construction and disposal of treated lumber materials in accordance with all Municipal, County, State, and Federal Regulations having jurisdiction.

REFERENCES

- A. Occupational Safety and Health Administration Construction Standards and Interpretations Construction Industry Standards Related to excavation safety and heavy construction.
- B. New Jersey Department of Transportation Standard Specifications for Road and Bridge Construction (2007)
- C. BOCA Building Code
- D. ASTM Construction Standards
 - 1) ASTM A36 Structural Steel
 - 2) ASTM A307- Carbon Steel Externally Threaded Fasteners
 - 3) ASTM A325-High Strength bolts for Structural Steel
 - 4) ASTM A163- Hot dip galvanizing
 - ASTM D5456 Standard Specification for Evaluation of Structural Composite Lumber Products.
 - 6) ASTM D-2559 for Glueline Quality
- E. Structural Steel Painting Council
- F. American Welding Society- AWS D1.1 Structural Welding Code

- G. American Forest Products Association- National Design Specification for Wood Construction.
- H. Timber grading rules for applicable species used in the construction.
- I. American Wood Preservers Association treatment standards
 - 1) AWPA Standard C2-Lumber, Timbers, Bridge and Mine Ties and timbers.

QUALITY ASSURANCE

- A. Fabricating, and galvanizing steel connection hardware and in accordance with approved shop drawings, codes and standards;
- B. Furnishing treated structural lumber in accordance with the design plans and specifications;
- C. Connecting and aligning girders and substructure frame in accordance with the plans and details.
- D. Preboring of holes for large nails, and lag screws and deck screws as required to prevent splitting if the decking and framing.
- E. Application of field applied preservatives to drill holes, cut ends etc.
- F. Furnishing standard treated lumber conforming to grading rules for specified grades and species.
- G. Framing and connecting deck systems in accordance with details and inspections.

SUBMITTALS

The following material submittals shall be made prior to performing the related items of work:

- A. Overall layout, material connections, concrete foundations and anticipated execution
- B. Galvanizer's certificates for steel fabrications, and hardware.
- C. Submit galvanizing certificates and catalog details for galvanized fasteners.
- D. Submit manufacturers catalog data for stainless steel screws, galvanized wire nails etc.
- E. Submit bolt manufacturers catalog data and head type and thread length for steel bolts.
- F. Submit timber grading certificates for each grade of decking and structural framing.
- G. Submit manufacturer's certificates for Parallel Strand Lumber Framing and beams including material treatment certificates.
- H. Submit treatment certificates for standard lumber in accordance with AWPI standards

DELIVERYAND STORAGE

A. Store and handle materials to prevent physical damage.

ENVIRONMENTALLY APPROVED TREATMENT PROCESS

At the time of these specifications it is understood that environmental guidelines have been issued concerning the use of CCA wood treatment in areas accessible to the public. Restrictions could be instituted during the course of the project. Verify prior to ordering decking material the

material that CCA treatment is currently acceptable for use. Notify the Engineer, the Owner and the Owner's Design Engineer, if restrictions prevent further use and provide submittal criteria for substitute equivalent AWPA treatment process.

INSPECTION

A. All members shall be subject to the initial inspection by the Engineer in order to confirm compliance with the drawings, specifications and specified standards.

TIE AND CONNECTION COMPONENTS

- A. All nails, spikes, fasteners, bolts, screws and hardware shall be hot dipped galvanized in accordance with ASTM A307. All structural steel shall conform with ASTM A36.
- B. Spikes for securing stringers to girders shall be 40d, common and "Teco" nails for "Teco" Straps.
- C. Bolts for securing girders to the support posts shall be ½" diameter bolts; stringer to scab plates shall be ½" diameter bolts; and scab plates to girders shall be ½" diameter bolts, all with 1/8' x 2-1/2" minimum washers at each end.
- D. Screws for securing decking to stringers shall be a minimum of three (3") inches long.
- E. "Teco" tie-down straps for fastening the stringers to the girders shall be provided at the 4th, 6th, 12th, and 14th stringers.
- F. The Contractor shall field power plane the top of all stringers prior to the installation of decking by the Owner.

FRAMING LUMBER

- A. All required timbers for stringer and girder members shall be Southern Yellow Pine, square four sides (S4s) dense structural grade No. 2 in accordance with the current grading rules for southern pine lumber approved by the American Lumber Standards Committee as issued and copyrighted by the Southern Pine Lumber Association, New Orleans, LA. All timber stringer and girder members shall conform with ASTM-D24-81 and shall be solid sawn southern pine structural grade #2. Timbers for stringer and girders shall be as shown on the plans.
- B. All timbers, dimension lumber and boards shall be graded and carry an identifiable grade mark in the accordance with the Grading Rules of the Southern Pine Inspection Bureau. The minimum in-place length of lumber shall be as shown on the drawings.
- C. All timber stringers and girders shall be treated in accordance with the American Wood Preservers Association as follows: C1-C6 "Standards for Preservative Treatment by Pressure Process – All Timber Products" and C2 "Standard for the Preservative Treatment of Lumber, Timbers and Ties by Pressure Process".
- D. All timbers shall be treated with a 1.0 pounds per cubic foot CCA (chromated copper arsenite).

DECKING LUMBER

- A. Decking material shall be cedar decking conforming to the grades and dimensions as indicated on the drawings and specified herein.
- B. All decking shall be treated in accordance with the American Wood Preservers Association

SAFETY PROCEDURES

- A. Perform all operations in accordance with OSHA procedures for job health and safety.
- B. Control dust, coating residues and debris in accordance with permit requirements and environmental regulations having jurisdiction.

GENERAL TIMBER FRAMING REQUIREMENTS

- A. Verify that lumber has been stamped and/or tagged for grading and treatment prior to using the material in the work.
- B. Discard wood that is damaged or has excessive splits and checks.
- C. Verify that lumber is of proper size and length for the location in the structure.
- D. Whenever possible, precut lumber to size before assembly. Prebore and treat bore holes with field applied preservative.
- E. Apply field preservative to all cuts prior to assembly.
- F. Accurately set and assemble substructure framing in accordance with the design drawings and details. Report any inconsistencies to the Engineer prior to proceeding with framing for further evaluation.
- G. Pre-bore holes for nail, lag screw, bolts and drift pin holes as required to prevent splitting of the wood.

SUBSTRUCTURE FRAMING

- A. All moving, handling, transporting, hauling and placing of the stockpiled materials within and around the site of work shall be done by the Contractor. The Contractor shall provide all equipment, tools, machines, vehicles and labor required to prepare, haul and place all materials and construct the boardwalk structures in accordance with the Contract Plans and Specifications. The Contractor will transport and install all cedar decking material.
- B. The Contractor shall be responsible to secure all materials and equipment at the site of work and protect them from trespass and vandalism. Any material that is damaged, lost or stolen after it has been received and accepted by the Contractor shall be the sole responsibility of the Contractor.
- C. Verify that support posts have been treated with approved preservative coating.
- D. Drill support posts and girders accurately to permit through bolting of support post connection plates. Bolt holes shall be of the minimum diameter so that bolts are installed using light tapping.
- E. Install and tighten connecting bolts and washers.
- F. The boardwalk structure shall be constructed to the dimensions, lines, and grades, as shown on the drawings or as directed by the Engineer.
- G. 15# bituminous felt paper shall be stapled or nailed securely in place over the top of the girder members prior to the placement of the stringer members.
- H. Stringers shall be connected to the girders to the spacing as shown on the plans for the appropriate sections involved. Every stringer shall be tow spiked in place to the girders using a

minimum of two (2) galvanized 40d spikes to the girder and four (4) galvanized 40d spikes to the adjacent stringers. In addition, the 4th, 6th, 12th, and 14th stringers shall be fastened to the girder using a galvanized "Teco" tie-down strap and "Teco" nails.

- I. Contractor to field power plane top of all stringers to within 1/8" in ten (10) feet with maximum variation 1/16" in any one (1) foot prior to the Owner's placement of the decking.
- J. Decking construction shall be performed by the Contractor. Decking shall be secured to the stringer at 90° angles. A pattern of two (2)/one (1), three inch (3") long galvanized screws shall be used to fasten each decking board to every other stringer and two (2), three inch (3") screws to fasten all decking board ends. All screw holes shall be pre-drilled through the decking, as required, to properly set and countersink all screws. Decking shall have no seams within the limits of the walkway width (6"). Decking shall be spaced at one-quarter inch (1/4") between boards. All decking shall run in the same direction continuous throughout. Screws shall be finish set below the deck surface. No screws shall be permitted to extend above the deck surface. Deck edging that abuts access ramps or other transverse decking shall be chamfered to minimize tripping hazard.

CLEANUP

- A. Cleanup and remove all wood cuts, trash and debris from beneath and alongside the boardwalk.
- B. Rake area adjacent to the boardwalk and remove wood pieces nails, trash and debris.

PERMITS AND INSPECTION

The contractor is responsible for obtaining all necessary permits for the construction of the boardwalk structure, footbridge and handicapped accessible ramp.

The County and Building Sub-Code Official shall review shop drawings and inspect the construction. The presence of the Engineer or his representative shall not relieve the Contractor of his responsibility to install the structures in accordance with plans, specifications and codes and standards having jurisdiction.

MEASUREMENT AND PAYMENT

Pay Item Pay Unit

TIMBER BOARDWALK, INCLUDING VERTICAL POSTS AND CONCRETE FOUNDATIONS

SQUARE FOOT

Payment for furnishing and installation of the timber boardwalk, including, but not limited to all necessary decking, materials, hardware, labor and equipment, preparation of shop drawing submittals, permits, and all incidentals, will be included in the square foot price bid for said item as listed in the bid form for the quantity actually installed.

SECTION 2J - GALVANIZED HANDRAIL SYSTEM

WORK INCLUDED

The contractor shall provide all labor, materials and equipment necessary to furnish and install galvanized handrails on all boardwalk sections and ramps exceeding a five (5) percent running slope. The galvanized handrail shall be securely attached to the upright wooden boardwalk support posts.

The railings should be built in accordance with ADA requirements for height and diameter of railing required to meet these guidelines. In addition, the railings shall meet all requirements set forth in the latest edition of the building code.

PERFORMANCE REQUIREMENTS

- A. Structural Performance: Engineer, fabricate, and install handrail system to withstand the structural loading required by applicable loads.
- B. Thermal and Corrosion Control:
 - Allow for thermal action resulting from the maximum range (change) in ambient temperature in the design, fabrication, and installation of rail systems, to prevent opening of joints, buckling, and other detrimental effects, including overstressing of connections and components.
 - 2. Prevent galvanic action and other forms of corrosion by isolating dissimilar metals, preventing direct contact with each other.

SUBMITTALS

- A. Product Data: Manufacturer's specifications and installation instructions for all components of each product type specified.
- B. Shop Drawings: Prepared specifically for this project.
 - 1. Show complete layout; plan views, elevations, connections, details for fabrication and attachment to other elements, and other installation details.

QUALITY ASSURANCE

A. Manufacturer/Installer Qualifications: Provide handrails from one source, produced by a manufacturer and craftsmen having resources to provide consistent quality in appearance and physical properties, without delaying the work.

DELIVERY, STORAGE, AND HANDLING

- A. Deliver handrail systems and related components in protective packaging. Inspect materials to ensure that specified products have been received.
- B. Store components to avoid damage from moisture, abrasion, and other construction activities.

MANUFACTURERS

- A. Manufacturer: RTB Fabricators 14 Cartier Drive, Franklin Park, NJ 08823 (732) 422-9743; or approved equal.
- B. Provide handrail system from a single manufacturer.

MATERIALS

- A. General: Provide material free from surface blemishes where exposed to view in the finished installation. Materials used to fabricate and mount the railing shall be in accordance with the contract drawings and with the standard and supplementary specifications. Shop drawings shall be submitted to the Engineer for approval prior to fabrication. The railing shall be properly prepared for finishing.
- B. Galvanized Steel: Railing shall be Schedule 40 Seamless Galvanized Steel pipe conforming to ASTM A53.
- C. Base Flanges, Anchors, and Inserts:
 - 1. Anchors and inserts as required to support work specified, in accord with approved shop drawings.
 - 2. All components to be comprised of Galvanized Steel.
- D. Fittings and Fasteners: Same basic material and alloy as parts being joined, unless otherwise indicated. Do not use metals that will be corrosive or incompatible with materials being fastened; do not utilize pop-rivets, sheet metal screws, adhesives, or cast fittings.

1. Fasteners: Galvanized Steel

2. Component Fittings: Galvanized Steel

E. Terminal safety returns shall be provided at all ramp terminal handrails.

FABRICATION

- A. Fabricate handrail system to comply with Engineer's and manufacturer's printed requirements, project design requirements, ADA requirements, details, dimensions, finish and member sizes, including post spacing and anchorage, but not less than the structural requirements to support loading. The railing shall meet the quality requirements of NAAMM's Pipe Railing Manual.
 - 1. Clearly mark component units for site assembly and installation.
 - 2. Use connections that maintain structural capacity of joined members.
- B. Provide weep holes or other means to exit entrapped water from hollow sections of railing members exposed to exterior, condensation, or moisture from other sources.
- C. Railings shall be prefabricated and preassembled in the factory or shop as far as practical.

FINISHES

- A. Galvanized Steel:
 - 1. Hot-Dipped Galvanized Coating in accordance with ASTM A123 and ASTM A385.

EXAMINATION

A. Examine system components, substrate, and conditions where railing systems are to be installed.

B. Notify Engineer in writing of unsatisfactory conditions. Do not proceed with the work until unsatisfactory conditions have been corrected.

PREPARATION

- A. Prepare surrounding construction to receive railing system installations to comply with manufacturer's requirements.
- B. Review and coordinate setting drawings, shop drawings, templates, and instructions for assembly and installation of railing system and related items to be embedded in concrete and masonry.

INSTALLATION

- A. Fabricate and install railing system and related components in strict accordance with manufacturer's printed installation instructions, project shop drawings, and Engineer's orders.
- B. Preassemble railing system, including posts, in easy to lift sections whenever possible.
 - 1. Align rails so that variations from level horizontal members, and from parallel with rake of steps and ramps for sloping members, do not exceed 1/4 inch in 12 feet (6.3mm in 3.657m).
- C. Adjust, level, and securely install railing system components.
 - 1. Avoid springing assembled components of system into place.
- D. Provide for water to drain from the railing system hollow sections by drilling weep holes at bottom locations or other approved methods.
- E. Field welding shall not be permitted.
- F. Galvanized surfaces damaged from handling or installation shall be removed and replaced at no additional cost to the Owner.
- G. No improvements shall be installed prior to the Owner's written acceptance of shop drawings.
- H. No improvements shall be installed prior to a mutually agreed upon final location by the Township, Engineer, and Contractor.

CLEANING

- A. Immediately upon completion of installation, clean all railing system surfaces using clean water and mild soap or detergent.
- B. Do not use abrasive agent or harsh chemicals.

PROTECTION

A. Provide adequate protection for all surfaces of completed installations to prevent damage during remainder of construction activities

MEASUREMENT AND PAYMENT

Pay Item Pay Unit

GALVANIZED STEEL HANDRAIL, INCLUDING VERTICAL POSTS AND CONCRETE FOUNDATIONS

LINEAR FOOT

GALVANIZED STEEL HANDRAIL

LINEAR FOOT

Payment for furnishing and installation of the galvanized handrail, including, but not limited to all necessary materials, hardware, labor, and equipment for a complete installation will be made at the linear foot price bid for said item as listed in the bid form for the quantity actually installed.

SECTION 2K - BRAILLE TRAIL AND INTERPRETATIVE SIGNAGE

WORK INCLUDED

The Contractor shall provide all labor, materials and equipment necessary to furnish and install the braille trail, talking informational sensory kiosk and braille trail sensory touch signs in accordance with the contract drawings and as directed by the Engineer or Engineer.

All materials, labor, and equipment required for the construction and installation of the sign faces and supporting structure, as required by the plans and specifications shall be included under these items.

BRAILLE TRAIL

The contractor shall construct a section of the overall project as a braille trail. The trail shall have a ¼" marine grade nylon guide rope installed along the perimeter. The rope shall pass through 4"x4" southern yellow pine, pressure treated wooden posts at 10' intervals. An indicator knot should be provided directly before the braille signage.

TALKING INFORMATIONAL KIOSK

The wooden sign face with cedar roof structure shall be constructed in accordance with the contract drawings, with good construction practice and with all applicable building codes. Working/design drawings shall be submitted to the Engineer for review and approval. Said working drawings shall also be suitable and used for sub-code permit application purposes. It is the intent of the owner to have constructed a single-sided wooden sign face with full color interpretative signage and an audio box as depicted in the contract drawings. The sign shall be constructed fully of cedar and capable of supporting the necessary signage and audio box. Specifications, samples and materials shall be provided by the Contractor for selections to be made by the owner.

It is the responsibility of the Contractor to provide all engineering drawings, apply for and secure sub-code permits and to secure all sub-code inspections and final approval certificates from the local Construction Official's Office. Any signed and sealed engineering/working drawings or other certifications required for the permit process, other than the contract drawings, must be obtained and provided by the Contractor.

AUDIO BOX

The contractor shall install the U-Turn Audio Box Through Mount with Rear Casing, manufactured by Digital Audio Technologies (800-261-3199) or approved equal within the center of the kiosk. The audio box shall be capable of eight (8) audio selections and be inset flush within the kiosk center panel.

The Owner will provide the required script for each audio selection. As part of this contract, the contractor will be responsible for coordinating the necessary narrative between the Owner and manufacturer to create a studio recording for each sign face installed (10 total).

SIGNAGE

The contractor is responsible for the creation and installation of all interpretative signage as depicted within the contract drawings as directed by the Owner.

The kiosk signage shall be 2'H x 3'W High Pressure Laminate 1/8" thick panels carrying a 10 year guarantee. These sign faces shall be full color and contain a variety of text and images for the necessary subject material.

The braille trail signage shall be 12"H x 18"W High Pressure Laminate 1/8" thick panels carrying a 10 year guarantee. These sign faces shall be full color and contain a variety of text and images. The text will be transcribed into braille on alternating lines. In addition, carved sections of the sign will be created

on each sign face to provide a sensory experience.

The Owner will provide all required information for each sign face. As part of this contract, the contractor will be responsible for coordinating the necessary information, graphics, vector files and any other materials required for sign creation between the Owner and manufacturer. A proof of each sign face shall be provided to the Owner for approval prior to ordering and installation. All sign faces shall be designed and produced by Loumarc Signs (908-575-4000) or an approved equal.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

TALKING INFORMATIONAL SENSORY KIOSK,

INCLUDING CONCRETE FOUNDATIONS UNIT

BRAILLE TRAIL LOOP NYLON ROPE, INCLUDING

VERTICAL POSTS AND GRAVEL FOUNDATIONS LINEAR FOOT

BRAILLE TRAIL LOOP NYLON ROPE LINEAR FOOT

BRAILLE TRAIL LOOP SIGN, INCLUDING CONCRETE FOUNDATION

UNIT

Payment for the talking informational sensory kiosk will be made at the unit bid price for said items as listed in the bid form. Said prices shall include construction of the kiosk, signage, roof structure, audio box, all hardware, foundations, anchoring, and incidentals necessary for a complete and fully functioning system.

Payment for the Braille Trail Loop nylon rope will be made at the linear foot bid price for said items as listed in the bid form. Said prices shall include all materials, hardware, foundations, labor, and incidentals necessary for a complete and fully functioning system.

Payment for the Braille Trail Loop informational signage components will be made at the unit bid price for said items as listed in the bid form. Said prices shall include all hardware, foundations, anchoring, and incidentals necessary for a complete and fully functioning system.

SECTION 2L - SENSORY COMPONENTS AND SURFACING

WORK INCLUDED

The contractor shall furnish and install safety surface and sensory components at the locations indicated on the plans or as directed by the owner. All materials, labor, and equipment required to complete fine grading of stone base course, and all other associated work, as required by the plans and specifications shall be included under this item.

SENSORY COMPONENTS

The contractor shall furnish and install sensory components at the locations indicated on the plans or as directed by the owner. The contractor shall provide a survey stake out for sensory component layout prior to installation, to ensure all components and safety use zones are in accordance with the plans and manufacturer recommendations. All materials, labor, and equipment required to complete the construction including component installation and all incidental items required by the plans and specifications shall be included under this item.

All sensory components shall be installed with a direct burial concrete foundation, in strict conformance with the manufacturer's instructions and recommendations and with all applicable governmental regulations. This shall include any grading required for ADA compliant access to the designated barrier free components.

Sensory components shall be as shown on the detail drawings within Appendix A, as manufactured by Landscape Structures, Inc. and provided by General Recreation (800-726-4793) or an approved equal.

Shop drawings for all equipment shall be submitted to the Engineer for review and approval prior to ordering of materials. Shop drawing submittal shall include component layout in the areas designated on the plans along with specifications and warranty information for all components. Component layout shall be in accordance with the plan detail or as directed by the Engineer.

WOOD ENGINEERED FIBER SAFETY MULCH

Wood engineered fiber safety mulch shall be 'GT Impax' as manufactured by GameTime and provided by MRC (800-922-0070) or approved equal. The mulch shall be placed in the locations and thickness as shown on the contract drawings. The mulch shall be manufactured of size controlled softwoods and/or hardwoods that average 1"-2" in length and contain a maximum of 15% fine particles to aid in knitting. The mulch shall be non-toxic and not contain paint, chemicals, or additives. The mulch shall contain minimal bark and be free of twigs, leaf debris, and other organic material. Submittal of the material's certification is required prior to deliver and placement onsite. A permeable filter fabric shall be installed on the approved sub grade under the fiber mulch.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

ENGINEERED WOOD FIBER SAFETY MULCH, 6" THICK SQUARE FOOT

CHITTER-CHATTER NOODLE,

INCLUDING CONCRETE FOUNDATIONS PAIR

SENSORY PLAY CENTER,

INCLUDING CONCRETE FOUNDATIONS UNIT

LOG CRAWL TUNNEL, INCLUDING CONCRETE FOUNDATIONS

LOG BALANCE BEAM,

INCLUDING CONCRETE FOUNDATIONS UNIT

LOG STEPPER,

INCLUDING CONCRETE FOUNDATION UNIT

MUSHROOM STEPPER,

INCLUDING CONCRETE FOUNDATION UNIT

GOBLET DRUM,

INCLUDING CONCRETE FOUNDATION UNIT

KUNDO DRUM,

INCLUDING CONCRETE FOUNDATION UNIT

KETTLE DRUM,

INCLUDING CONCRETE FOUNDATIONS UNIT

VIVO METALLOPHONE,

INCLUDING CONCRETE FOUNDATIONS UNIT

Payment for the engineered wood fiber safety mulch will be made at the square foot bid price for said items as listed in the bid form. Said prices shall include all materials, labor, and incidentals necessary for a complete and fully functioning system. No separate payment will be made for the required sub-base, drainage, and any fine grading within the sensory area.

Payment for the sensory components will be made at the unit bid prices for said items as listed in the bid form. Said prices shall include all hardware, foundations, anchoring, and incidentals necessary for a complete and fully functioning system.

SECTION 2M - PREFABRICATED SHADE STRUCTURE

WORK INCLUDED

The contractor shall furnish and install the 30' Wide Prefabricated Shade Structure at the location indicated on the plan or as directed by the owner. All materials, labor, permitting, and equipment required to complete the installation, including all foundations, connections and all incidental items required by the plans, specifications, or manufacturer's recommendations shall be included under this item.

The contractor shall provide shop submittals detailing layout, concrete foundations, reinforcement and execution for review and approval prior to construction. The contractor is responsible for the preparation of plans and details signed and sealed by a N.J. Licensed Engineer for submittal to the construction department for all permitting. All construction shall comply with applicable codes. Any required soil borings and testing for bearing capacity determination is the responsibility of the contractor.

Installation of all components shall be in strict conformance with the detail drawings and/or with the manufacturer's instructions and recommendations, or as directed by the Engineer.

MATERIALS

The 30' Wide Prefabricated Shade Structure (Model #: HX30M2C-P6) shall be as shown on the detail drawings and manufactured by Icon Shelter Systems, Inc. (800-748-0985) and provided by Ben Shaffer Recreation, Inc. (800-953-2021) or approved equal.

The structure shall be a 2-Tier 30' Hexagonal Structure with a 24 gauge precut multi-rib metal roof. The roof shall have a 6:12 roof slope and a steel frame cupola. The manufacturer will provide anchor bolts, column base covers, anchor templates and engineering drawings. The engineering drawings shall include all structure components and connections as well as foundation design appropriate for the structure.

The metal roof shall be 'Patina Green', the steel frame powder coat shall be 'Surrey Beige' and the ornamentation powder coat shall be 'Fence Brown'. All final color selections to be approved by the Owner.

PART 1 - GENERAL

1.01 DESCRIPTION OF PRODUCT

- A. Shelter Type: 30' Hexagonal style shelter with Multi-Rib roof panels.
- B. Roof Slope: 6:12
- C. Clear height under Tie Beam (UTB): 8'-0". This is the clearance under the tie beam which spans between the columns.

1.02 REFERENCES

A. REFERENCED STANDARDS

- 1. AISC American Institute of Steel Construction
 - a. AISC Steel Construction Manual 14th edition
 - b. AISC 360-10 Specification for Structural Steel Buildings
- 2. ASTM American Society for Testing and Materials
 - a. ASTM A36/A36M Standard Specification for Carbon Structural Steel: 2008
 - ASTM A325 Standard Specification for Structural Steel Bolts, Heat Treated, 120/105 ksi Minimum Tensile Strength; 2010
 - c. ASTM A563 Standard Specification for Carbon and Alloy Steel Nuts; 2007a
 - d. ASTM A500 Standard Specification for Cold-Formed Welded and Seamless Carbon Steel Structural Tubing in Rounds and Shapes; 2010a

- e. ASTM A653/A653M Standard Specification for Sheet Steel, Zinc-Coated (Galvanized) or Zinc-Iron Alloy Coated (Galvanealed) by the Hot Dip Process; 2010
- f. ASTM A792/A792M Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy Coated by the Hot-Dip Process; 2010
- g. ASTM F1554 Standard Specification for Anchor Bolts, Steel, 36, 50 and 105 ksi Yield Strength; 2007a
- 3. AWS American Welding Society
 - a. D1.1
 - b. D1.3
 - c. D1.8
- 4. OSHA Occupational Safety and Health Administration
 - a. Steel Erection Standard 29 CFR 1926.750 Part R
- 5. SSPC Steel Structures Painting Council
 - a. SSPC-SP 2 Hand Tool Cleaning; 2004
 - b. SSPC-SP 10/NACE No. 2 Near White Blast Cleaning; 2007
- 6. LEED Leadership in Energy and Environmental Design
- 7. ISO International Organization for Standardization

1.03 SYSTEM DESCRIPTION

A. The structure shall be a pre-engineered package and shall be shipped as a pre-cut (excluding standing seam roof panels) and pre-fabricated package that shall include the structural framing members, roof panels, fasteners and roof trim as well as job specific installation instructions. The structure will be shipped in an un-assembled package for ease of shipment and minimum shipping charges.

1.04 SUBMITTALS

A. Submit a minimum of four (4) sets of submittal drawings and (2) sets of structural calculations signed and sealed by a Professional Engineer licensed in the state of New Jersey.

B. PRODUCT DESIGN REQUIREMENTS:

1. The structure shall meet all national, state or local Building Codes, Ground Snow Loads, Live Loads, Wind Speeds, and Seismic Design Standards for the projects specific location.

C. SUBMITTAL REQUIREMENTS

- 1. Calculations:
 - a. Design according to the requirements of the national, state or local building codes.
 - b. Calculations shall include all member design for each different member type.
 - c. Connection design for each different connection that will determine the design of the bolts, welds, plate thickness and anchorage to the foundation.
 - d. Foundation design shall be for the loads applied and not a generic foundation design, taking into account all soils information.
- 2. Submittal Drawings:
 - a. Anchor bolt layout with all appropriate dimensions for installation.
 - b. Site specific foundation design.
 - c. Isometric as well as elevation and plan views of the farming members along with the member sizes and locations indicated on the drawings.
 - d. Connection details for every connection on the frame.
 - e. Roof panel connections and trim installation details.
 - f. All accessories on the structure shall have an installation detail as well as connection details.

D. FOUNDATION DESIGN

1. The foundation design shall be supplied by the manufacturer.

- 2. Anchor bolts shall be supplied by the manufacturer.
- 3. Foundation materials and labor shall be provided by the structure contractor.
- 4. Owner should provide site specific soils information for proper foundation design, if that data is not provided the foundation will be design for the minimum soil values allowed by code.

1.05 QUALITY ASSURANCE

A. MANUFACTURER QUALIFICATIONS

- 1. The product shall be designed, engineered and fabricated at a facility operated and directly supervised by the manufacturer.
- 2. The manufacturer shall have a minimum of 9 years in steel shelter fabrication.
- 3. Full Time on Staff Quality Assurance Manager.
- 4. All welders must be AWS certified for welding steel structures.
- 5. Membership in the American Welding Society (AWS).
- 6. Membership in the American Institute of Steel Construction (AISC).
- 7. Full Time on Staff Licensed Engineer.
- 8. Published Quality Control System manual.
- 9. Quality Control System must pass an annual audit by a Third Part Agency.
- 10. ISO 9001 certification for Powder Coating System.

1.06 FIELD OR SITE CONDITIONS

- A. Foundations shall be installed per the ICON installation drawings.
 - 1. All foundations shall be cast at the same elevation unless specifically noted on the ICON installation drawings.
- B. Anchor bolts shall be placed in the foundation as per the ICON installation drawings utilizing the anchor bolt template supplied with the anchor bolts.
 - 1. Anchor bolts shall be installed per the dimensions and orientation shown on the drawings.

1.07 MANUFACTURER WARRANTY

- A. Shelter shall have a 10 year limited warranty on the steel framing members.
- B. Shelter shall have a 10 year limited warranty on the powder-coated elements.
- C. For all Metal Roofing there will be a pass through warranty direct from the metal Roofing supplier, warranty shall be provided on request.

PART 1 - MATERIALS

2.01 SHELTER SYSTEM AND MATERIALS

A. PRODUCT REQUIREMENTS AND MATERIALS:

- 1. GENERAL:
 - a. The pre-engineered and pre-fabricated package of parts shall be pre-cut and packaged unless noted otherwise. These packages will include all parts and pieces necessary to field assemble the shelter at the jobsite. The shelter shall be shipped in knocked down format to minimize shipping expenses. Field labor will be kept to a minimum with no on-site welding required.

2. CONCRETE FOR FOUNDATIONS:

- a. Concrete shall have a minimum 28-day compressive strength of 2,500 psi unless noted otherwise on the foundation detail.
- b. Reinforcing steel shall be ASTM A615, Grade 60.

3. COLUMNS:

- a. Hollow Structural Section (HSS) columns shall meet ASTM A500, Grade B with a minimum wall thickness of 3/16" (0.1875").
- b. Unless the columns are direct buried in the foundation the columns shall attach to the foundation with a minimum of four (4) anchor rods and shall meet OSHA Steel Erection Standard 29 CFR 1926.755(a)(1)

4. STRUCTURAL FRAMING

 All Hollow Structural Sections (HSS) shall meet ASTM A500, Grade B. "I" Beams, tapered columns or open channel sections shall not be accepted for primary members.

5. COMPRESSION RINGS:

a. Compression rings shall be made of ASTM A36 structural plate or of structural channel welded together to form the ring. All connections not requiring compression rings shall use ASTM A500, Grade B HSS sections for these connections.

6. CONNECTION REQUIREMENTS:

- a. Anchor rods shall be ASTM F1554, Grade 36 unless otherwise noted.
- b. Structural fasteners shall be ASTM A325 high strength bolts and A563 nuts.
- c. All structural fasteners shall be hidden within the framing members whenever possible.
- d. No field welding shall be required to finish the construction of the shelter.
- e. Manufacturer shall supply extra fasteners.

7. ROOFING MATERIALS:

- a. PRIMARY ROOF DECK MULTI-RIB METAL ROOFING
 - 1) Roofing shall be a minimum of 24 gauge Galvalume steel sheet with ribs that are 1 3/16" tall and 12" on center. Ribs shall run with the slope of the roof for proper drainage.
 - 2) Roof outside surface shall be a baked on Kynar 500 paint finish and shall be supplied in one of the manufacturer's standard colors: TBD Ceiling color to be a "wash coat" primer.
 - Roof panels shall have the roof angles factory pre-cut to size to provide ease of installation.
 - 4) Metal roofing trim shall match the color of the roof and shall be factory made from 26 gauge Kynar 500 painted Galvalume sheet steel.
 - 5) Trim includes panel ridge caps, hip caps, eave "J" trim, splice channels, rake trim, roof peak cap and corner trim as applicable for the model selected. Trim may need to be field cut to length. Please refer to the installation drawings for additional information and detail.
 - 6) Ridge, hip and valley caps shall be pre-formed with a single central bend to match the roof slope and shall be hemmed on both edges.
 - 7) Roof peak caps shall be pre-fabricated with no field assembly required.
 - 8) Manufacturer shall supply roof screws painted to match the roof.

8. FACTORY FRAME FINISH:

- a. All structural steel shall be cleaned, pre-treated and finished in the following manner:
 - 1) The steel shall be shot-blasted to the specification of SSPC-SP10 near white blast cleaning. SSPC-SP2 hand tool cleaning will not be an acceptable alternative.
 - The shot-blasted parts are then washed with zinc-phosphate in an eight (8) stage washer.
 - 3) The steel is then immersed in a liquid epoxy and coated through an electrodeposition process (E-coat), this is coated both inside and out to a uniform cover

- of 0.7-0.9 mils. The E-coat totally encapsulates the part for superior corrosion protection.
- 4) The parts are then coated with a color coat of TGIC polyester powder and then one clear coat for a final finish thickness of 8 to 12 mils.

9. FACTORY PRIME PAINT

a. All steel shall be cleaned to the specification of SSPC-SP2 (Hand Tool cleaning) or better. This removes all loose mill scale, loose rust and any other loose foreign matter. The clean steel will then be primed with a quick dry, lead and chromate free alkyd primer.

10. ACCESSORIES

a. ELECTRICAL ACCESS

1) Standard in all column bases is a 1 3/4" diameter hole, located in the center of the plate. This allows electrical wiring into the column base.

PART 3 - EXECUTION

3.01 STORAGE AND HANDLING

- A. When the shelter arrives at the jobsite protect the products from weather, sunlight and damage.
- B. When unloading, pad the forks and use other precautions to protect the powder-coated finish. Do not use chains to move the materials, use straps. Handle all materials carefully in the field to avoid scratching the powder-coat finish.
- C. Contractor shall store the product elevated from the soil to allow full air circulation around the materials as do not introduce mold, decay, fungi or insects into or on the materials. One end of the materials shall be elevated higher than the other end if storage will be longer than a few days as to allow the water to run off the materials.

3.02 INSTALLATION OF MATERIALS

- A. The shelter shall be placed on prepared foundations. Foundation shall be constructed to all local building code requirements and per good construction practices for the specific site conditions.
 - In accordance with <u>OSHA Steel Erection Standard 29 CFR 1926.750 Part R</u>, anchor rods shall be installed for proper column stability and shall have a minimum of four (4) anchor bolts per column. Therefore no single anchor rod column base connections shall be allowed.
- B. The contractor shall install all parts and pieces per the manufacturer's supplied installation instructions and these specifications.
- C. The interface with other work required is to be coordinated by the customer or the customer's agent. Some design may have electrical or plumbing requirements that are not supplied by ICON.
- D. Tolerances on structural steel members are set according to <u>AISC Code of Standard Practice for Steel Buildings and Bridges</u> and have been used for the fabrication of this product. These tolerances will not and cannot be increased. No field slotting or opening of holes will be allowed without proper guidance from the ICON Engineering Department.

3.03 REPAIR

A. No field modifications or corrections are allowed without authorization from the ICON Engineering Department.

MEASURE AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

GAZEBO, 30' WIDE, INCLUDING CONCRETE FOUNDATIONS

UNIT

Payment for the furnish and installation of the Prefabricated Shade Structure will be made at the unit bid price as listed in the Bid Form. Said bid prices shall include all materials, labor and incidentals required to complete the installation. No separate payment will be made for signed and sealed drawings.

Separate payment for all items requiring construction permits will not be made. Compensation for these items shall be included in the bid price for said items.

SECTION 2N - TRAILHEAD ENTRY SIGN

WORK INCLUDED

The contractor shall furnish and install the trailhead entry sign where designated on the plans, including all materials, excavation, foundations, reinforcement, and labor necessary for a complete installation.

MATERIALS

Custom Pedestrian Entry Sign, 12' Long

PART 1 GENERAL

1.1 SECTION INCLUDES

A. CFI Custom Pedestrian Trailhead Entry Sign

1.2 REFERENCES

Specifier Notes: List standards referenced in this section, complete with designations and titles. This article does not require compliance with standards, but is merely a listing of those used.

- A. ASTM Testing Standards:
 - 1. ASTM B 117 Standard Practice for Operating Salt Spray (Fog) Apparatus.
 - 2. ASTM D 522 Standard Test Methods for Mandrel Bend Test of Attached Organic Coatings.
 - 3. ASTM D 523 Standard Test Method for Specular Gloss.
 - 4. ASTM D 2247 Standard Practice for Testing Water Resistance of Coatings in 100% Relative Humidity.
 - 5. ASTM D 2794 Standard Test Method for Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact).
 - ASTM D 3359 Standard Test Methods for Measuring Adhesion by Tape Test.
 - 7. ASTM D 3363 Standard Test Method for Film Hardness by Pencil Test.
 - 8. ASTM G 155 Standard Practice for Operating Xenon Arc Light Apparatus for Exposure of Non-Metallic Materials.
- B. ISO Testing Standards:
 - 1. ISO 1520 Paints and Varnishes Cupping Test.
 - 2. ISO 2815 Paints and Varnishes Buchholz Indentation Test.
- C. ANSI/BIFMA Testing Standards:
 - 1. ANSI/BIFMA X5.4-2005 Standard Test for Lounge Seating.

1.3 SUBMITTALS

- A. Product Data: Submit manufacturer's product data, storage and handling requirements and recommendations, installation methods and available colors, styles, patterns and textures.
- B. Shop Drawings: Submit manufacturer's shop drawings, including plans and elevations, indicating overall dimensions.
- C. Samples: Submit manufacturer's samples of materials, finishes, and colors.
- D. Warranty: Manufacturer's standard warranty.

1.4 QUALITY ASSURANCE

- A. Manufacturer's Qualifications: Manufacturer regularly engaged in manufacture of site furnishings since 1995.
- B. Product Support: Products are supported with complete engineering drawings and design patents.
- C. Base Worth: An installed base of products worth in excess of thirty million dollars.
- D. Assets: Excess of ten million dollars in assets.
- E. Production: Standard orders are filled within a 40-day schedule.
- F. Facility Operator: Welders and machine operators are certified.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Delivery: Deliver materials to site in manufacturer's original, unopened containers and packaging, with labels clearly identifying product name and manufacturer.
- B. Storage: Store materials in clean, dry area in accordance with manufacturer's instructions. Keep materials in manufacturer's original, unopened containers and packaging until installation.
- C. Handling: Protect materials and finish during handling and installation to prevent damage.

1.6 WARRANTY

- A. Warranty Information:
- -Products will be free from defects in material and/or workmanship for a period of one year from the date of delivery.
- -The warranty does not apply to damage resulting from accident, alteration, misuse, tampering, negligence, or abuse.
- CFI shall, at its option, repair, replace, or refund the purchase price of any items found defective upon inspection by an authorized CFI service representative.
- -Purchasers should be aware that normal use of these high quality products can result in superficial damage affecting the finish. Scratches, nicks, and dents are to be considered normal wear and tear, and are not the responsibility of the manufacturer.

PART 2 PRODUCTS

2.1 MANUFACTURER

A. CFI 2903 NY RT7, HARPURSVILLE, NY, 13787 / PH: (607)-693-3223 FX: (607)-693-3226 / KKILLMEIER@ECHOES.NET OR APPROVED EQUAL

2.2 ITEM

ARCH 'CUSTOM' STYLE

2.3 MATERIALS

- A. PRESSURE TREATED POSTS
- B. LASER TEMPLATED LETTER OVERLAY SND BLASTED INTO LOGO PLATE
- C. ALL GALVANIZED HARDWARE
- D. 1" DIA. WEATHER RESISTANT HEMP ROPE
- -Recycled Material Content: Minimum 25 percent. Alum. generally 75%
- -Recyclable: 100 percent.

2.4 FINISHES

- A. Finish on Metal: CFI POWDERCOAT FINISH
 - 1. White metal blast surface preparation
 - 2. Primer: Rust inhibitor (zinc primer / or e-coat when specified)
 - 2. Topcoat: Thermosetting TGIC polyester powder coat. UV, chip, and flake resistant.
 - 3. Test Results: ASTM Cross hatch for adhesion and MEK rub for cure test
 - a. Gloss Consistency, Gardner 60 Degrees, ASTM D 523: Plus or minus 5 percent from standard.
 - b. UV Resistance, Color and Gloss, ASTM G 155, Cycle 7: Delta E less than 2 at 2.0 mils and less than 20 percent loss.
 - c. Cross-Hatch Adhesion, ASTM D 3359, Method B: 100 percent pass.
 - d. Flexibility Test, Mandrel, ASTM D 522: 3 mm at 2 mils.
 - e. Erichsen Cupping, ISO 1520: 8 mm.
 - f. Impression Hardness, Buchholz, ISO 2815: 95.
 - g. Impact Test, ASTM D 2794: 60 inch-pounds at 2.5 mils.
 - h. Pencil Hardness, ASTM D 3363: 2H minimum.
 - i. Corrosion Resistance, 1,500-Hour Test, ASTM B 117: Max. undercutting 1 mm.
 - j. Humidity Resistance, 1,500-Hour Test, ASTM D 2247: Max. blisters 1 mm. Specifier Notes: Specify color of metal. Consult CFI. for selection of standard colors and availability of custom colors.

4. Color: Natural wood with accent colors to be selected by owner.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Examine area to receive entry sign.
- B. Notify Engineer of conditions that would adversely affect installation or subsequent use.
- C. Do not begin installation until unacceptable conditions are corrected.

3.2 INSTALLATION

- A. Install *ARCH* in accordance with manufacturer's instructions / dimensions and locations indicated on the drawings.
- B. ARCH plumb and level.

Specifier Notes: Specify anchoring method.

- C. Anchoring Method:
 - 1. Arch to have full length post to be supplied and anchored to a 4'x4'x5' deep footer minimum with cast in "J" bolts on required 4 bolt pattern. J bolts to be 18" deep. Please see Engineers specific detail for exact construction and size to accommodate stone face

3.3 ADJUSTING

- A. Finish Damage: Repair minor damages to finish in accordance with manufacturers Instructions and as approved by Engineer.
- B. Component Damage: Remove and replace damaged components that cannot be successfully repaired as determined by Engineer.

3.4 CLEANING

- A. Clean promptly after installation in accordance with manufacturer's instructions.
- B. Do not use harsh cleaning materials or methods that could damage finish.

3.5 PROTECTION

A. Protect installed product to ensure that, except for normal weathering, product will be Without damage or deterioration at time of Substantial Completion.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

TRAILHEAD ENTRY SIGN, INCLUDING CONCRETE FOUNDATIONS

UNIT

Payment for furnishing and installing the trailhead entry sign will be made at the unit bid price as listed in the bid form. No separate payment will be made for materials, excavation, foundations, reinforcement, and labor necessary for a complete installation.

SECTION 20 - MISCELLANEOUS SITE AMENITIES

WORK INCLUDED

The Contractor shall provide all labor, materials, and equipment necessary to install the Log Benches, Acorn Seats, Trash and Recycling Receptacles, Decorative Table and Raised Garden Bed as specified.

Submittal and approval of shop drawings/catalog cuts for the above items and all appurtenances is required prior to installation/acceptance.

LOG BENCHES

Log Benches shall be Model 173595, as manufactured by Landscape Structures, Inc. and provided by General Recreation (800-726-4793) or an approved equal. Permanent direct burial installation shall be in accordance with the detail drawing and manufacturer's recommendations. Contractor shall submit shop drawings for approval prior to ordering. Concrete footings shall be buried a minimum of 2" beneath the mulch to provide a clean finished installation.

ACORN SEATS

Acorn Seats shall be Model 186579, as manufactured by Landscape Structures, Inc. and provided by General Recreation (800-726-4793) or an approved equal. Permanent direct burial installation shall be in accordance with the detail drawing and manufacturer's recommendations. Contractor shall submit shop drawings for approval prior to ordering. Concrete footings shall be buried a minimum of 2" beneath the mulch to provide a clean finished installation.

TRASH AND RECYLING RECEPTACLE

Trash and Recycling Receptacles shall be Models 186584 (Wood Grain Litter Receptacle) and 186585 (Wood Grain Recycling Receptacle), as manufactured by Landscape Structures, Inc. and provided by General Recreation (800-726-4793) or an approved equal. Permanent direct burial installation shall be in accordance with the detail drawing and manufacturer's recommendations. Contractor shall submit shop drawings for approval prior to ordering. Concrete footings shall be buried a minimum of 2" beneath the mulch to provide a clean finished installation. Liners for each receptacle shall be provided by the Contractor.

DECORATIVE TABLE

Decorative Table shall be 6' long (Custom Model 100-60-1PL), as manufactured by Dumor, Inc. and provided by General Recreation (800-726-4793) or an approved equal. The contractor shall coordinate ordering with the product representative to supply only the table portion. The table height and supporting legs shall be increased from the standard thirty (30) inches to a height of thirty-four (34) inches. Permanent direct burial installation shall be in accordance with the detail drawing and manufacturer's recommendations. Contractor shall submit shop drawings for approval prior to ordering. Concrete footings shall be buried a minimum of 2" beneath the mulch to provide a clean finished installation.

Table structure shall be powder coated black and table top shall be Walnut recycled plastic. Final color selections to be approved by Owner prior to ordering.

RAISED GARDEN PLANTER

Raised Garden Planter shall be Model 'Traditional' as manufactured by Accessible Gardens and provided by Ben Shaffer Recreation, Inc. (732-840-1060) or approved equal. The Raised Garden Planters shall be constructed of red cedar and meet all ADA accessible and NJ Structural Standards.

Overall dimensions of the Raised Garden Bed shall be 32" x 48" and provide a 28" clearance beneath the

lowest horizontal member. The box shall be constructed of 2"x12" lumber for the sides and 2"x6" lumber for the bottom of the garden bed and all braces. The legs shall be 4"x4" material. An integral drainage system shall be provided. All connections shall be pre-drilled and made with stainless steel or ceramic fasteners.

The Contractor shall apply an oil based outdoor finish to the planters prior to installation. The Contractor shall provide samples of a minimum of three (3) different oil based finishes for approval by the Owner.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item	Pay Unit
LOG BENCH, 6' LONG, INCLUDING CONCRETE FOUNDATIONS	UNIT
ACORN SEAT, INCLUDING CONCRETE FOUNDATION	UNIT
TRASH AND RECYCLING RECEPTACLE, INCLUDING CONCRETE FOUNDATIONS	PAIR
DECORATIVE TABLE, INCLUDING CONCRETE FOUNDATIONS	UNIT
RAISED GARDEN PLANTER	UNIT

Payment for furnishing and installing the log bench will be made at the unit price bid as listed in the bid form. No separate payment will be made for materials, excavation, foundations, reinforcement, and labor necessary for a complete installation.

Payment for furnishing and installing the acorn seat will be made at the unit price bid as listed in the bid form. No separate payment will be made for materials, excavation, foundations, reinforcement, and labor necessary for a complete installation.

Payment for furnishing and installing the trash and recycling receptacles will be made at the unit price bid for the pair as listed in the bid form. No separate payment will be made for materials, excavation, foundations, reinforcement, and labor necessary for a complete installation.

Payment for furnishing and installing the decorative table will be made at the unit price bid as listed in the bid form. No separate payment will be made for materials, excavation, foundations, reinforcement, and labor necessary for a complete installation.

Payment for furnishing and installing the raised garden planter will be made at the unit price bid as listed in the bid form. No separate payment will be made for materials, oil finish, reinforcement, and labor necessary for a complete installation.

SECTION 2P - PLANTINGS

WORK INCLUDED

The Contractor shall be required to purchase the appropriate specimens of plant material as identified on the construction drawings from a certified nursery in a USDA plant hardiness Zone 6. All plant material shall be grown and dug in the Zone 6 area and verification of same shall be provided to the Engineer upon request.

All plant material shall be purchased, transported, and installed where indicated on the construction drawings and as directed by the Engineer in a healthy, vigorous, and undamaged condition. The planting contractor will provide the Owner with a guarantee for the health and survival of all trees planted in this contract throughout the period of the Maintenance Bond (2 years) following the final acceptance of the contract. Stakes must be removed after one (1) year.

MATERIALS

All plant materials used shall be true to name and size in conformity with the American Standard of Nursery Stock and shall be typical of their species or variety. All plants shall have normal well-developed branches, a strong central leader free of defects and vigorous root systems. They shall be sound, healthy, vigorous and free from defects, disfiguring knots, stress, drought abrasions of the bark, sunscald injuries, plant diseases, insect eggs, borers and all other forms of infection. All plants must be accompanied by a Nursery Certificate or Plant Dealer certificate to confirm nursery stock certification by the New Jersey Department of Agriculture (NJSA4: 7-15 et seq.) for the Owner's files.

- A. Standard #1 (Ed Gilman University of Florida) shall be used to evaluate the minimal acceptable diagram outlines of the following: *
 - 1. Rootball soil firmness
 - 2. Good/strong, straight tree trunk taper
 - 3. Good quality tree crown shapes
 - 4. The highest quality tree trunk forms
 - 5. Good quality tree branch scaffold spacing
- B. Standard #1 diagrams outlines of the following: *
 - 1. Unacceptable tree trunk forms
 - Unacceptable loose rootball soil
 - 3. Unacceptable poor quality crown shapes
 - 4. Unacceptable poor/weak tree trunk taper
 - 5. Unacceptable poor quality tree branch scaffold spacing

All plants are to be protected during storage period and not allowed to dry out. Plants shall be installed on the day of arrival at the site.

Contractor is to provide the Engineer with the location of nurseries where plants are to be purchased from or stored and plants to be purchased are to be tagged for inspection by the Engineer (if feasible) prior to digging and <u>delivery</u> to the site. All plant material is subject to review and approval by the Engineer upon arrival at the site, prior to installation.

All plant material and sizes are specified on the landscaping plan. <u>No substitutes shall be made without specific approval of the Engineer.</u>

Topsoil used in planting pits and for backfilling for trees and shrubs shall be fertile agricultural soil, capable of sustaining vigorous plant growth and shall have a pH of five point five (5.5) to six point five (6.5). It shall have uniform composition, be free from large stones, wood and other foreign objects and

shall not contain substances toxic to plant growth. Planting pit and backfilling material shall not be used unless it meets this requirement. All planting pit backfill material shall be in compliance with same as identified on the set of construction drawings.

A backfill soil amendment is required to be added to each tree's planting pit as follows:

A. Granular form or tablets:

- 1. Bio-stimulants
- 2. Organic matter
- 3. Hydrogel type
- 4. Ectomycorrhizal fungi
- 5. Endomcorrhizal fungi
- 6. The approved soil amendment formula (granular or tab) will be layered into planting pit soil backfill at 1/3 to1/2 the depth of the root ball. The manufacturer's label description of the soil amendment and hydrogel must be submitted for review and approval prior to planting. Deviations from the mandated soil amendment specifications noted above in Soil Amendment A, one through five will not be permitted.

Planting Season

Planting shall normally be undertaken when the soil is free of frost and friable, unless otherwise specified. No planting shall be done during abnormally hot weather. The time of planting, however, shall be agreed upon at the conference between the Engineer, Project Engineer and the contractor, and a specific schedule shall be set up.

Deciduous trees and all evergreens over six (6) feet tall shall be staked according to current Nursery and Arboricultural standards as indicated on the construction drawings and used in the following manner.

- A. Two (2) stakes shall be driven a minimum of two (2) feet into the soil and outside the planting pit if possible.
- B. Stakes, when driven, must be one-half (1/2) to two-thirds (2/3) the height of the tree measured from ground level.
- C. Stakes shall be a minimum of two (2) inches in diameter at the thick end, two-by-two hardwood or cedar posts.
- D. Stakes shall be placed in line with the prevailing winds when possible.
- E. Stakes shall be attached to the tree with any of the commercially available material designed specifically for trees such as plastic tree chain.
- F. All stakes and ties shall be removed by the contractor not less than twelve (12) months nor more than eighteen (18) months from the time of planting. No portion of any maintenance bond will be released until the contractor has removed all the stakes and ties.

Protection during Transportation

Trees shall be protected from dying and breakage due to wind during transportation. Trees may be transported in a covered van or on an open flatbed with tarp tightly tied so that the tarps do not flap or rebound more than four (4) inches at highway speeds.

Tree root balls shall be thoroughly watered immediately prior to transport.

Tree root balls shall be thoroughly watered immediately upon completion of unloading.

Trees shall be sufficiently watered daily until planted to prevent desiccation.

Plant Installation

- 1. The diameter of all planting pits shall be at least one and two-thirds (1 2/3) larger than the ball diameter. In areas of poor soil or where trees are placed between sidewalk and curb the planting pit is to be four (4) times greater than the ball diameter. Topsoil meeting the requirement of the section labeled (soil) shall be provided at a minimum depth of six (6) inches below the ball or root system. The pit for bare root trees and shrubs must be at least six (6) inches deeper than existing roots and twelve (12) inches wider.
- 2. Plants shall be planted at exactly the same depth as previously grown. All soil in the planting pits shall be firmed to prevent air pockets and settling.
- 3. After balled and burlapped plants are set at the proper level in the holes, all cord and burlap shall be untied from the trunk and turned down into the planting pit. Synthetic non-biodegradable ties shall be removed from the ball and planting pit prior to backfill. All wire baskets shall be completely removed from the planting pit prior to backfill. All plants shall be backfilled with topsoil that meets the requirements noted above. All plants shall be thoroughly watered in at the time of planting to prevent air pockets and settling. Watering for plant survival shall be the contractor's responsibility until final acceptance of the project by the Owner.
- 4. After materials are planted, all damaged branches shall be removed by pruning utilizing the current standards of the American Association of Nurserymen and the National Arborist Association recommendations. No other pruning is permitted. All nursery tags should be removed following inspection and approval by the Engineer.
- 5. All nylon, burlap, wire, wire baskets, string, and containers shall be entirely removed at the time of planting.
- 6. All newly planted trees shall be fertilized as directed by the Engineer or Owner.

Caliper indicates diameter of a tree trunk measured, in inches, six (6) inches above ground level for trees up to four (4) inches, and at twelve (12) inches above ground level for larger trees over four (4) inches. Ground level refers to the ground level of the tree or plant at the time of digging in the nursery, otherwise known as the "root collar."

A four (4) inch minimum layer of organic mulch shall be applied around each individual tree, <u>except next</u> to the trunk where <u>no</u> mulch is to be placed. The mulch around the tree must be saucer-shaped with the concave depression located nearest the trunk as indicated on the construction drawings.

All "mulch" shall be considered any material, organic in nature, composted, that is not readily subject to movement by wind or water.

Wood chips, partially decayed or nitrogen enriched, may be used. New chips are not acceptable due to the nitrogen depletion by bacteria from the soil preventing use of nitrogen by the plant. Treated triple shredded hardwood mulch is recommended.

Deer protection shall be provided around the trunks of all single stem deciduous trees as per the Deciduous Tree Planting Detail within the plans, if and when directed by the Engineer. The deer protection shall be A.M. Leonard Rigid Mesh Tree Bark Protectors, Model: BG48, (48" high), from A.M. Leonard Horticultural Supply Company, or approved equal. Tree bark protectors shall not be required on any multi-stem deciduous ornamental trees or shrubs. The tree bark protectors shall be cut down to size if necessary and shall be affixed with jute in three (3) locations: top, bottom and center.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item	Pay Unit
SUGAR MAPLE, 2" – 2 ½" CALIPER (IF AND WHERE ORDERED)	UNIT
GOLDEN RAIN TREE, 7' – 8' HEIGHT (IF AND WHERE ORDERED)	UNIT
FOREST PANSY EASTERN REDBUD, 7' – 8' HEIGHT (IF AND WHERE ORDERED)	UNIT
CHEROKEE BRAVE DOGWOOD, 7' – 8' HEIGHT (IF AND WHERE ORDERED)	UNIT
PINK CHIMES JAPANESE SNOWBELL, 7' – 8' HEIGHT (IF AND WHERE ORDERED)	UNIT
GOLDILOCKS HINOKI FLASE CYPRESS, 8' – 10' HEIGHT (IF AND WHERE ORDERED)	UNIT
BLUE COLORADO SPRUCE, 8' – 10' HEIGHT (IF AND WHERE ORDERED)	UNIT
GREEN GIANT ARBORVITAE, 8' – 10' HEIGHT (IF AND WHERE ORDERED)	UNIT
LO & BEHOLD ICE CHIP BUTTERFLY BUSH, 12" – 18" HEIGHT (IF AND WHERE ORDERED)	UNIT
RUBY SPICE SUMMERSWEET, 24" – 30" HEIGHT (IF AND WHERE ORDERED)	UNIT
SUNSHINE BLUE BLUEBEARD, 18" – 24" HEIGHT (IF AND WHERE ORDERED)	UNIT
BLUE MIST DWARF FOTHERGILLA, 18" – 24" HEIGHT (IF AND WHERE ORDERED)	UNIT
HOOGENDORN JAPANESE HOLLY, 18" – 24" HEIGHT (IF AND WHERE ORDERED)	UNIT
HENRY'S GARNET VIRGINIA SWEETSPIRE, 24" – 30" HEIGHT (IF AND WHERE ORDERED)	UNIT
GOLD STAR JUNIPER, 24" – 30" SPREAD (IF AND WHERE ORDERED)	UNIT
BIRD'S NEST SPRUCE, 18" – 24" HEIGHT (IF AND WHERE ORDERED)	UNIT
SUMMER WINE NINEBARK, 24" – 30" HEIGHT (IF AND WHERE ORDERED)	UNIT

ANTHONY WATERER SPIREA, 18" – 24" HEIGHT (IF AND WHERE ORDERED)	UNIT
BLOOMERANG PURPLE LILAC, 24" – 30" HEIGHT (IF AND WHERE ORDERED)	UNIT
COMPACT KOREANSPICE VIBURNUM, 24" – 30" HEIGHT (IF AND WHERE ORDERED)	UNIT
COMMON MILKWEED, 2 GALLON (IF AND WHERE ORDERED)	UNIT
PINK GRAPEFRUIT YARROW, 2 GALLON (IF AND WHERE ORDERED)	UNIT
OVERDAM FEATHER REED GRASS, 2 GALLON (IF AND WHERE ORDERED)	UNIT
ZAGREB TICKSEED, 2 GALLON (IF AND WHERE ORDERED)	UNIT
MAGNUS PURPLE CONEFLOWER, 2 GALLON (IF AND WHERE ORDERED)	UNIT
HIDCOTE ENGLISH LAVENDER, 2 GALLON (IF AND WHERE ORDERED)	UNIT
MORNING LIGHT MAIDEN GRASS, 2 GALLON (IF AND WHERE ORDERED)	UNIT
WALKER'S LOW CATMINT, 2 GALLON (IF AND WHERE ORDERED)	UNIT
HAMELN DWARF FOUNTAIN GRASS, 2 GALLON (IF AND WHERE ORDERED)	UNIT
KARLEY ROSE ORIENTAL FOUNTAIN GRASS, 2 GALLON (IF AND WHERE ORDERED)	UNIT
RUSSIAN SAGE, 2 GALLON (IF AND WHERE ORDERED)	UNIT
NORTHWIND SWITCHGRASS, 2 GALLON (IF AND WHERE ORDERED)	UNIT
ALEXANDRA GARDEN PHLOX, 2 GALLON (IF AND WHERE ORDERED)	UNIT
GOLDSTURM BLACK-EYED SUSAN, 2 GALLON (IF AND WHERE ORDERED)	UNIT
MAY NIGHT GARDEN SAGE, 2 GALLON (IF AND WHERE ORDERED)	UNIT

CAROUSEL LITTLE BLUESTEM, 2 GALLON (IF AND WHERE ORDERED)

UNIT

HELENE VON STEIN LAMB'S EAR, 2 GALLON (IF AND WHERE ORDERED)

UNIT

Payment for the furnishing and installation of plant materials in accordance with the plans and specifications will be made at the unit prices bid for the various plant items as listed in the Bid Form for the quantity actually installed. Said bid price shall include excavation, backfill, soil amendments, staking, mulching, deer protection, area restoration, and all other associated work.

SECTION 2Q - TOPSOIL, LIME, FERTILIZER, AND SEED

WORK INCLUDED

The Contractor shall provide all labor, materials, and equipment necessary to re-spread amended topsoil, lime, fertilizer and seed tack in accordance with the Contract Documents.

It is intended to provide topsoil, fine grading, lime, fertilizer, seed and mulch in all those areas of the site that have been disturbed during construction activities and designated for turf stabilization within the contract documents.

The Contractor shall install topsoil throughout the site as required to complete the work as intended by the plans or required by the Engineer. The work also includes the furnishing and placement of imported topsoil, if required, to provide the required covering throughout the area to be seeded and throughout those areas disturbed by the Contractor.

Proposed topsoil thickness shall be a minimum of 4" unless otherwise indicated on the plans or required by the Engineer.

TOPSOIL

It shall be the responsibility of the Contractor to determine, during the pre-bid due diligence, if imported topsoil will be required to satisfactorily complete the scope included within the contract.

Import Topsoil: (if and where deemed necessary)

Topsoil to be spread within the project areas as designated by the contract or Engineer shall be imported, screened material of high quality. The topsoil to be used shall be approved by the Engineer prior to delivery to the site. The source and representative samples shall be submitted for review and approval prior to even materials being delivered or placed. Manufactured "topsoil" from recycling facilities will be well scrutinized. All topsoil shall be absolutely free of non-organic material, thoroughly cleared of all sticks, roots, branches, coarse sods and other deleterious matter, and all stones larger than 1" in diameter before it is spread. A minimum thickness of topsoil of 4" will be required. Topsoil shall not be handled or spread when it is in a frozen or muddy condition, or otherwise unsuitable for handling.

Specifications for Imported Topsoil:

- Unacceptable Topsoil Sources: Do not obtain topsoil from the following sources:
 - 1. Areas containing chemically contaminated soils
 - 2. Areas from which the original surface has been stripped or covered over, such as borrow pits, open mines, demolition sites, dumps, and landfills
 - 3. Wet excavations
 - 4. Acid producing soils
- Provide topsoil that conforms to the pH requirements specified below, when tested according to ASTM D 4972.

pH Range Acceptability / Remediation
pH < 4.1 Topsoil is UNACCEPTABLE

4.1 <u><</u> pH < 5.8	Add pulverized lime to increase the pH to 6.5 before use
5.8 <u><</u> pH < 7.0	Topsoil is acceptable. No remediation needed
7.0 <u><</u> pH < 7.2	Decrease pH to at least 6.8 before use
pH <u>></u> 7.2	Topsoil is UNACCEPTABLE

- Organic Content requirement shall be between the range of 3 to 8 percent by weight. The
 organic content shall be determined according to AASHTO T 194, except that the sample is to
 be taken from oven-dried soil passing a No. 10 sieve. Any soil additives being considered to
 increase the organic content of selected import topsoil needs to be reviewed and approved by
 the Engineer prior to the amending process.
- Gradation / particle Size: Provide topsoil conforming to the following particle size requirements and that has no more than 20 percent retained on a No. 10 sieve when mechanically graded.

Particle Size	<u>Percent</u>
Sand (2.0mm to 0.05 mm)	50 – 80
Silt (0.05 mm to 0.005mm)	5 – 15
Clay (0.005 mm to smaller)	5 – 10*

^{* -} If more than 50 percent of the sand portion is larger than 0.5 millimeters, the allowable range for clay is 10 to 20 percent.

No topsoil shall be spread before the completion of all construction in the area or before all fills are fully compacted.

Before spreading topsoil, the subgrade shall be cleared of all stones more than 2" in diameter, all coarse roots, sticks, and debris. Any portions of the subgrade that have been compacted to a hard surface shall be pulverized to a depth of 3" by plowing, or other methods acceptable to the Engineer.

If applicable, particular attention to fine grading tolerances shall be required for the athletic fields in general and especially the grass infield areas. The topsoil finish grade shall properly complement the "skin" infield allowing for proper runoff, ridges (or lips) where grassed areas meet the infields on all fields are unacceptable.

FERTILIZING AND SEEDING

Ground limestone shall be evenly applied to all areas to be seeded at the rate of 4.5 pounds to every 100 square feet of surface, and shall be thoroughly and evenly mixed with the soil to a depth of 5" below finished grade.

All areas to be seeded shall be fine graded as described above to remove all ridges and depressions and the surface shall be cleaned of all stones greater than 1" in diameter, and other debris.

After preparation for seeding, and at least nine days before seeding, an approved commercial fertilizer with a minimum content of 5% nitrogen, 10% phosphoric acid, and 5% potash, or as approved by the Engineer, shall be incorporated into the soil at a rate of two pounds per 100 square feet, to a depth of two

inches. The soil shall then be thoroughly watered.

Seed shall later be spread and raked (or slice seeded) into the prepared soil at a rate of 0.5 lbs. per 100 sq. ft. or 220 lbs. per acre Seed shall be rolled with a water ballast roller, and shall be watered, protected, and tended until there is a hardy stand of grass.

All dates and schedules for seeding operations shall be as approved by the Engineer. Seeding shall be done in favorable weather, in the fall, where possible, and in early spring, if necessary, to complete unfinished areas. Unsatisfactory coverage will require overseeding and appropriate soil supplements at no additional cost to the Owner.

When seeding has been completed, fiber mulch tack shall be installed in accordance with industry standards.

Seed mix to be furnished and installed shall be "Team Mates Plus" as distributed by John Deere Landscapes (Lesco Inc.), or equivalent.

The above seed mix consists of:

70% Turf Type Tall Fescue Blend

20% Perennial Ryegrass

10% Premium Kentucky Bluegrass

The seed shall contain practically no seeds of noxious weeds and shall be delivered mixed in uniform sealed bags with tags/labels showing weights, analysis and vendor's name. Bags and labels shall be saved and given to the Engineer or Owner

WATERING AND CUTTING LAWNS

The contractor shall take all necessary steps to produce a satisfactory lawn covering. Such steps may include the thorough watering of the new lawn until it has received its second cutting.

The cost of such watering shall be borne by the contractor, and the equipment and manpower required, shall be furnished by the contractor.

The contractor shall also be held responsible for all lawn cuttings until the project is accepted and closed out. Any lawn areas that have not developed after two (2) cuttings shall be cut and re-seeded, fertilized, watered, and cut until a full lawn is produced. Should crab grass or broadleaf weed prevention be deemed necessary by the engineer, same shall be applied at no additional cost.

The cuttings of lawn shall not occur closer than 7 to 10 days, or as directed by the Engineer.

Lawn areas must be hearty and uniform prior to acceptance by the owner.

MEASUREMENT AND PAYMENT

Measurement and payment will be made under:

Pay Item Pay Unit

EXCAVATE EXISTING WALKWAY TO BE REMOVED, 2" THICK, TOPSOIL, LIME, FERTILIZE, AND SEED

SQUARE YARD

Payment for the removal of the existing walkway, topsoil, lime, fertilize and seed will be made at the square yard price bid for said items as listed in the bid form. Said bid prices shall include all materials, labor, restoration and incidentals required to complete the installation.

Separate payment for the furnishing, delivery and installation of suitable, screened topsoil for the project areas will not be made. Compensation for said materials shall be included in the price bid for said items as listed in the Bid Form.

SECTION 2R - CLEANUP AND RESTORATION

WORK INCLUDED

The Contractor shall throughout the course of the work maintain the site in a presentable condition to the satisfaction of the Engineer. The Contractor shall be responsible for all periodic clean-up and coordination or cooperative efforts of all subcontractors. All contractors involved in the work shall cooperate fully with direction by the Engineer.

Periodic clean-ups shall include, but is not necessarily restricted to, storage of equipment and material, removal of rubbish, and any material which may either become unsightly or impede progress of the work or cause unsafe conditions. In general, the site shall be maintained in the neat and orderly fashion at all times.

At the conclusion of the workday, the Contractor shall restore all areas damaged due to construction activity. Each contractor shall be responsible for damage due to his operations; however, the general contractor shall assume the overall responsibility for any damage. All contractors and subcontractors shall cooperate with the general contractor in this regard.

Grass, shrubs, walks and other site related work damaged during construction shall be restored to the satisfaction of the Engineer.

The Contractor is responsible to leave the site in a condition intended by the plans and all areas shall be left in a state equal to or better than that existing prior to the start of the contract.

MEASUREMENT AND PAYMENT

Separate payment for restoration and clean-up will not be made. Payment for all clean-up and restoration related work shall be included in the prices bid for all items requiring same.

APPENDIX A SENSORY PLAY COMPONENTS








SAFETY NOTE

Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM F1487.)

DETAIL

16432700

TALK TUBE HOSE ATTACHMENT



Weevos®

164177 ChitterChatter® Noodle

Weevos® 164177 ChitterChatter® Noodle



Parts List

Part#	Description	Qty.
173612	1.75" O.D. Plastic Tube	50 Ft
164826	Chatter Noodle Plate, Specify Color	2
163903	Chatter Ball, Specify Color	2
164155	Chatter Post, Specify Color	2
164987	ChatterNoodle Hardware Package	
100610	¹ / ₄ " x ⁵ / ₈ " Drive Rivet, AL/SST	6
127872	#14 x ³ / ₄ " BHCS Torx, SST	6
156845	Welcome Label, 2-5 Years	1
125528	Tubing Attachment Hardware Package	1
	8	
100671	Hose Clamp	2

Specifications

Chatter Ball: Rotationally molded from U.V. stabilized linear low density polyethylene, color specified.

Chatter

Weldment comprised of 1.250" O.D. x 11 GA. (120") Noodle Plate:

black steel tube and 12 Ga. (.105") HRPO flat steel.

Finish: ProShield®, color specified.

Fabricated from 3.500" O.D. RS20 (.125" Wall) gal-**Chatter Post:**

vanized steel tube. Finish: ProShield, color specified.

Talk Tube Hose: Made from HDPE conduit.

Hose Clamp: Band and housing made from 300 series stainless

steel. Slotted screw with hex head and safety collar

is cadmium-plated carbon steel.

Fasteners: Primary fasteners shall be socketed and pinned tam-

perproof in design, stainless steel (SST) per ASTM F

879 unless otherwise indicated (see specific product

installation/specifications).

Installation Time: Approx. 3 man hours **Concrete Req.:** Approx. 3 cu. ft.

83 Îbs. Weight:

Installation Instructions

- (Direct Bury) Refer to the Site Plan to determine placement of Chatter 1) Posts. Maximum distance apart is 40 feet.
- Dig footings to width and depth shown. Dig a trench into subgrade between the two footings for placement of plastic tubing.
- Set posts into footings and temporarily brace in plumb position.
- Insert talk tube through lower hole in post and out the top of post, as shown.
- Place chatter ball over talk tube hose, and onto post. Drill through holes in chatter ball and into chatter post with a $\frac{1}{4}$ or "F" (only) drill bit. Insert $\frac{1}{4}$ " x $\frac{5}{8}$ " drive rivets into holes and hammer rivet pins in until flush with head.
- Attach talk tube hose to chatter noodle plate using hose clamp, as shown. Refer to the Talk Tube Hose Attachment Detail.
- Push chatter noodle plate tight against chatter ball, and attach using $#14 \times \frac{3}{4}$ " torx screws.
- Lay plastic tubing flat and cut to correct length for your installation. Attach talk tube hose to remaining chatter post following steps 3, 4, 5 & 6.
- 9) Mix and pour concrete into footing holes, up to, but not above trench level.
- 10) Backfill footings and trench to top of subgrade.
- 11) Install protective surfacing before users are allowed to play on the structure.








SAFETY NOTE

Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM F1487.)

18384200

TOP VIEW



Sensory Play

Sensory Play Center®

Sheet 1 of 2

Parts List

Part#	Description Qty.
166888	Model #168100
166757	Sensory Roto Main Wall, Specify Color
167219	Wall Mount Plate Footer, (DB), Specify Color*
	Model #168101
166758	Sensory Roto End Wall, Specify Color1
167219	Wall Mount Plate Footer, (DB), Specify Color*
	Model #168661
167186	Sensory Wall Plate, Specify Color1
169036	Attachment Plate Hardware Package1
100353	³ / ₈ " Flange Nuts w/Pin, SST4
100365	³ / ₈ " SAE Flat Washer, SST4
100173	³ / ₈ " x 2" BHCS w/Pin, SST4
169179	2-Hole Play Center End (DB) Hardware Pkg1
100321	³ / ₈ " Patch Hex Nut, SST
100362	³ / ₈ " Flat Washer, SST4
123224	³ / ₈ " x 1 ¹¹ / ₁₆ " BHCS w/Pin, SST2
183890	4-Hole Play Center Wall (DB) Hardware Pkg1
100321	³ / ₈ " Patch Hex Nut, SST4
100362	³ / ₈ " Flat Washer, SST8
123224	³ / ₈ " x 1 ¹¹ / ₁₆ " BHCS w/Pin, SST4
156846	Play Safe Label 2-12 Yrs1
183064	Warning Label1
169174	2-Hole Play Center End (SM) Hardware Pkg1
100263	³ / ₈ " x 2 ³ / ₄ " Expansion Anchors
100264	³ / ₈ " x 5" Expansion Anchors
100327	³ / ₈ " Standard Hex Nut, SST2
100362	³ / ₈ " Flat Washer, SST
169172	1 ¹ / ₈ " O.D. x 2" Long Spacer Tube, AL
183891	4-Hole Play Center Wall (SM) Hardware Pkg1
100263	³ / ₈ " x 2 ³ / ₄ " Expansion Anchors
100264	³ / ₈ " x 5" Expansion Anchors
100327	³ / ₈ " Standard Hex Nut, SST
100362	³ / ₈ " Flat Washer, SST
169172	1 ¹ / ₈ " O.D. x 2" Long Spacer Tube, AL
156846	Play Safe Label 2-12 Yrs1
183064	Warning Label1
* = Quantity	Determined By Your Order

* = Quantity Determined By Your Order

DB = Direct Bury SM - Surface Mount

Specifications

Walls: Rotationally molded from U.V. stabilized linear low-density polyethylene, color specified.

Wall Plate: Fabricated from 1/4" HRPO steel plate. Finish: Pro-

Shield®, color specified.

Wall Mount

Plate Footer: Weldment comprised of 2.375" O.D. RS20 (.095"-

.105") wall galvanized steel tubing and 1/4" HRPO

steel plate. Finish: ProShield, color specified.

Fasteners: Primary fasteners shall be socketed and pinned tam-

perproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see specific product

installation/specifications).

Installation Time: Main Wall **(DB)** 1 ¹/₄ man hours

End Wall (**DB**) 3/4 man hour

Main Wall (SM) $1^{-1}/_4$ man hours

End Wall (SM) $^{3}/_{4}$ man hour

nt: Main Wall (DB) 88 lbs.

Main Wall **(SM)** 54 lbs. End Wall **(DB)** 38 lbs.

End Wall (SM) 21 lbs.

Concrete: (DB) Approx. 1.31 cu. ft. per hole

Installation Instructions

(Direct Bury)

- 1) Refer to the Site Plan for footing locations.
- 2) Insert wall plate into main wall and attach, using ${}^3/{}_8$ " x 2" BHCS w/pin with ${}^3/{}_8$ " SAE flat washers and ${}^3/{}_8$ " flange nuts w/pin. Connect end wall to wall plate, using ${}^3/{}_8$ " x 2" BHCS w/pin with ${}^3/{}_8$ " SAE flat washers and ${}^3/{}_8$ " flange nuts w/pin.
- 3) Attach wall mount plate footers to wall sections, using ³/₈" x 1 ¹¹/₁₆" BHCS w/pin with ³/₈" flat washers and ³/₈" patch hex nuts with ³/₈" flat washers. Refer to the Direct Bury Detail. NOTE: Pull end wall and main wall sections together before tightening bolts.
- 4) With Sensory wall sections in position and plumb, pour concrete footings. Allow concrete to cure a minimum of 72 hours before allowing users to play on the structure.
- 5) Apply labels as shown.
- 6) Install protective surfacing before users are allowed to play on the structure. NOTE: When a Sensory Play Center is installed in a playground environment, protective surfacing is required.

(Surface Mount Without Protective Surfacing)

- 1) Insert wall plate into main wall and attach, using ³/₈" x 2" BHCS w/pin with ³/₈" SAE flat washers and ³/₈" flange nuts w/pin. Connect end wall to wall plate, using ³/₈" x 2" BHCS w/pin with ³/₈" SAE flat washers and ³/₈" flange nuts w/pin. **NOTE:** *Pull end wall and main wall sections together before tightening bolts*.
- 2) With Sensory wall sections in position, mark anchor bolt locations on the concrete slab (through wall section holes). Move wall sections aside. Drill ³/₈" x 3" deep holes, using a hammer drill and ³/₈" masonry bit
- 3) Reposition wall sections. Tap $\frac{3}{8}$ " x 2 $\frac{3}{4}$ " expansion anchors into drilled holes. Fasten wall sections to $\frac{3}{8}$ " x 2 $\frac{3}{4}$ " expansion anchors, using $\frac{3}{8}$ " standard hex nuts with $\frac{3}{8}$ " flat washers. Refer to the Surface Mount Without Protective Surfacing Detail.
- 4) Apply labels as shown.

(Surface Mount With Protective Surfacing)

- 1) Insert wall plate into main wall and attach, using ³/₈" x 2" BHCS w/pin with ³/₈" SAE flat washers and ³/₈" flange nuts w/pin. Connect end wall to wall plate, using ³/₈" x 2" BHCS w/pin with ³/₈" SAE flat washers and ³/₈" flange nuts w/pin. **NOTE:** *Pull end wall and main wall sections together before tightening bolts.*
- With Sensory wall sections in position, mark anchor bolt locations on the concrete slab (through wall section holes). Move wall sections aside. Drill ³/₈" x 3" deep holes, using a hammer drill and ³/₈" masonry bit
- 3) Reposition wall sections with 1 ¹/₈" O.D. x 2" long spacer tubes in between bottom of wall sections and concrete slab. Tap ³/₈" x 5" expansion anchors into drilled holes. Fasten wall sections to ³/₈" x 5" expansion anchors, using ³/₈" standard hex nuts with ³/₈" flat washers. Refer to the Surface Mount With Protective Surfacing Detail.
- 4) Apply labels as shown.
- 5) Install protective surfacing before users are allowed to play on the structure. NOTE: When a Sensory Play Center is installed in a playground environment, protective surfacing is required.




SAFETY NOTE


Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM F1487.)

168712a


DETAILDIRECT BURY



DETAIL SURFACE MOUNT (WITHOUT PROTECTIVE SURFACING)



DETAIL SURFACE MOUNT (WITH PROTECTIVE SURFACING)



Sensory Play

Sensory Play Center®

Sheet 2 of 2








SAFETY NOTE

Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM F1487.)

17437300

PS = Playshaper LW = Learning Wall - Mounted 10 ³/₄" Above The Playing Surface.



NOTE:

The Marble Panel is preassembled at the factory.



PlayShaper® 173572/184897 Marble Panel®

Parts List

Part# 172697	Description Marble Panel Assembly, Specify Color	Qty.
106480	Panel Hardware Package	1
100195	³ / ₈ " x ⁵ / ₈ " BHCS w/Pin, SST	6
100353	3/8" Flange Nut w/Pin, SST	6

Specifications

Marble Panel Assy.: (Panels) Two color Permalene®, color specified. (Poly

Panel) Fabricated from .236" thick clear polycarbon-

ate. (Marbles) 2" Diameter glass.

Primary fasteners shall be socketed and pinned tam-**Fasteners:**

perproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see specific product

installation/specifications).

on Time: Approx. ¹/₄ man hour **Weight:** 54 lbs. **Installation Time:**

Installation Instructions


- Attach panel to post flanges using 3/8" x 5/8" BHCS w/pin and 3/8" flange nuts w/pin as shown.
- Install protective surfacing before users are allowed to play on the structure.







18428100



© 2012 by Landscape Structures. All rights reserved.

Sensory Play 177715 Color Splash Panel[™]



Parts List

Part# 178123-00	Description Color Splash Panel Assy., Specify Color	Qty 1
178144-00	Color Splash Wheel Hardware Package	1
100175-00	³ / ₈ " x 2 ³ / ₄ " BHCS w/Pin, SST	6
100353-00	³ / ₈ " Flange Nut w/Pin, SST	6
100365-00	³ / ₈ " SAE Flat Washer, SST	6

Specifications

Color Splash

Panel Assy.: Assembly comprised of (Permalene® Panels), color specified (Layan Panel) 1/ " (6.35 mm) thick v 26.3/ "

specified. (Lexan Panel) $^{1}/_{4}$ " (6,35 mm) thick x 26 $^{3}/_{4}$ " (679,45 mm) diameter. (Acrylic Panel) $^{1}/_{8}$ " (3,18 mm) thick x 26 $^{3}/_{4}$ " (679,45 mm) diameter clear. (Color Wheel) .1875" (4,76 mm) thick x 23 $^{7}/_{16}$ " (595,30 mm) diameter aluminum sheet. Finish: ProShield®, image is transferred into paint by the process of infusion. (Shaft) 300 Series stainless steel. (Thrust Oilite Bearing) .125" (3,18 mm) thick x 2.875" (73,03 mm) diameter. (Sleeve Oilite Bearing) 1.25" (31,75 mm)

diameter x .750" (19,05 mm) long.

Fasteners: Primary fasteners shall be socketed and pinned

tamperproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see spe-

cific product installation/specifications).

Installation Time: $\frac{1}{2}$ man hour

Weight: 38 lbs.

Installation Instructions

Attach color splash panel assembly to sensory wall, using ³/₈" x 2 ³/₄" BHCS w/Pin with ³/₈" SAE flat washers and ³/₈" flange nuts with pin. NOTE: Color splash panel assembly can be attached on either side of the Sensory Wall. Remove protective layer from lexan before installation.








SAFETY NOTE

Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM F1487.)

18432900



Sensory Play

168104 Optigear Panel®

Sensory Play 168104 Optigear Panel®



Parts List

Part#	Description	Qty
181247-00	Optigear Panel Assembly, Specify Color	1
167014-00	Ring Panel, Specify Color	1
169035-00	Optigear Panel Hardware Package	1
100200-00	³ / ₈ " x 3 ¹ / ₂ " BHCS w/Pin, SST	6
100353-00	3/8" Flange Nut w/Pin, SST	6
100365-00	3/8" SAE Flat Washer, SST	6

Specifications

Optigear

(Panels) Two color Permalene®, color specified. (Poly Panel Assy.:

Panel) .236" thick clear polycarbonate, ${}^3/_8$ " threaded rod and ${}^3/_{16}$ " SST plate.

Ring Panel: Two color Permalene, color specified.

Primary fasteners shall be socketed and pinned **Fasteners:**

tamperproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see specific prod-

uct installation/specifications).

Installation Time: 1/2 man hour

Weight: 41 lbs.

Installation Instructions


1) Attach Optigear panel assembly to sensory wall, using ring panel, ³/₈" x 3 1/2" BHCS w/Pin with 3/8" SAE flat washers and 3/8" flange nuts with pin. NOTE: Optigear panel assembly can be attached on either side of the Sensory Wall.







216985



Sensory Play

214441 Vivo™ Metallophone








216985a

DETAILDIRECT BURY



DETAILPROPPED IN FINAL POSITION



Sensory Play

214441 Vivo™ Metallophone






204303



216985b

Low C Tube, 32 5/8"



214441 Vivo™ Metallophone

Sensory Play

Sheet 2 of 3

CERTIFIED landscape structures° 216985c NOTE: Assembly shown has been rotated for clarity. (2) 3/8" Hex Nuts w/Patch w/ 3/8" SAE Flat Washers (6) ³/₈" Flange Nuts w/Pin Metallo Tube Permalene Bottom Metallophone Tube Base (2) 3/8" x 7/8" -BHCS w/Pin w/ 3/8" SAE Flat Washers Cradle **Bracket DETAIL CRADLE BRACKET ATTACHMENT** Metallophone Tube Base 6

Sensory Play

214441 Vivo™ Metallophone

(15) #14 x 1"

BHCS Torx w/ 1/4" Nylon

Washers

(6) 3/8" x 7/8" BHCS w/ Pin w/ 3/8" SAE

Flat Washers

DETAIL

PERMALENE BOTTOM

ATTACHMENT

IMPORTANT! Do not

use an impact wrench to tighten BHCS Torx

bolts. Hand tighten


only.







216985d



Sensory Play

214441 Vivo™ Metallophone

Sheet 3 of 3

Sensory Play 214441 Vivo™ Metallophone



Part#	Description	Qty
211013	Metallophone Tube Base, Specify Color	
211018	Metallo Tube Permalene Bottom, Specify Color .	1
211030	Metallo Tube Permalene Top, Specify Color	1
213638	Metallophone Leg, (DB), Specify Color	2
211033	Metallophone Leg, (SM), Specify Color	2
215141	Mallet Cradle Bracket, Specify Color	1
215142	Mallet Cradle Permalene Top, Specify Color	1
215735	Mallet Cradle Permalene Bottom, Specify Color.	1
213630	Mallet Assembly, Grey	1
214056	Mallet Assembly, Black	1
218900	Vivo TM Chimes Kit	
204303	Low C Tube, 32 5/8"	1
204304	Low D Tube, 30 11/16"	1
204305	Low E Tube, 29"	1
204306	Low F Tube, 28 3/16"	1
204307	Low G Tube, 26 5/8"	1
204308	Low A Tube, 25 1/8"	
204309	Low B Tube, 23 11/16"	
204310	Middle C Tube, 23"	1
204311	High D Tube, 21 11/16"	1
204312	High E Tube, 20 1/2"	1
204313	High F Tube, 19 13/16"	1
204314	High G Tube, 18 11/16"	1
204315	High A Tube, 17 5/8"	
204316	High B Tube, 16 5/8"	
204317	High C Tube, 16 3/16"	1
216993	Animato TM /Vivo TM Chimes Hardware Package	
211443	Node Block w/Insert	
162374	1/4" x 3/4" BHCS w/Pin, SST	66
100364	¹ / ₄ " SAE Flat Washer, SST	
212291	Node Spring Pin Cap	
213980	Music Belt Wedge	
216761	#14 x 1" BHCS (Torx), SST	26
216762	#14 x 1 ³ / ₄ " BHCS (Torx), SST	37
100365	³ / ₈ " SAE Flat Washer, SST	11
100196	³ / ₈ " x ⁷ / ₈ " BHCS (Torx), SST	
100353	³ / ₈ " Flange Nut w/Pin, SST	
100321	³ / ₈ " Hex Patch Nut, SST	
216777	¹ / ₄ " Hex Nut, SST	
127463	T-27 TPP Hex Bit (Torx), SST	
100611	¹ / ₄ " x ³ / ₈ " Drive Rivet, AL/SST	5
133368	¹ / ₄ " Nylon Washers	62
121348	4-Hole Surface Mount Hardware Package	
100266	¹ / ₂ " x 2 ³ / ₄ " Standard Hex Nut, SST	
100322	1/2" Standard Hex Nut, SST	
100363	¹ / ₂ " Flat Washer, SST	8
DB = Direct B		
SM = Surface	Mount	

Specifications

Tube Base: Weldment comprised of 3.500" (88,9 mm) O.D.

RS20 (.125")(3,17 mm) wall galvanized steel tubing, and 1/4" (6,35 mm) thick HRPO steel sheet. Finish:

ProShield®, color specified.

Bar Top & Bottom: Permalene®, color specified.

Leg: Weldment comprised of 3.500" (88,9 mm) O.D.

RS20 (.125")(3,17 mm) wall galvanized steel tubing.

Finish: ProShield®, color specified.

Tubes: Made from 1.250" (31,75 mm) diameter (.125") (3,17

mm) wall aluminum tube.

Cradle Bracket: Made from 1/4" (6,35 mm) thick HRPO steel sheet.

Finish: ProShield®, color specified.

Cradle

Top & Bottom: Permalene®, color specified.

Mallet: Comprised of 2" (50,8 mm) diameter grey & black

polyurethane, $\frac{1}{2}$ " (12,7 mm) diameter aluminum handle and $\frac{3}{16}$ " (4,74 mm) diameter stainless steel

cable with nylon coating.

Fasteners: Primary fasteners shall be socketed and pinned tam-

perproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see specific product

installation/specifications).

Installation Time: DB - Approx. 8 man hours

SM - Approx. 6 man hours

Concrete Req.: Approx. 3.56 cu. ft. Weight: DB - 235 lbs.

SM - 222 lbs.

Installation Instructions

1) (Direct Bury) Dig footings as shown.

- 2) Insert metallophone legs into bar base tubes. Measurement from center to center of each leg should be 59" (1500 mm). With legs in correct position, drill through holes in bar base tubes and into metallophone legs with a ¹/₄" or "F" (only) drill bit. Insert ¹/₄" x ³/₈" drive rivets into holes and hammer rivet pins in until flush with head. Refer to sheet 2.
- 3) (Direct Bury) Place metallophone legs into footing holes. With metallophone legs propped in plumb and final position, pour concrete footings. Allow concrete footings to cure for a minimum of 24 hours before completing assembly. NOTE: See back of sheet 1 for an example of Vivo Metallophone assembly propped in final position.

(Surface Mount) With metallophone legs in plumb position, drill $^{1}/_{2}$ " x 3" deep holes through metallophone leg plates using hammer drill and $^{1}/_{2}$ " masonry bit. Tap expansion anchors into drilled holes. Fasten metallophone leg plates to expansion anchors using $^{1}/_{2}$ " standard hex nuts with $^{1}/_{2}$ " flat washers.


- Place node spring caps on each end of tube pins. Attach tubes and mallets to tube base as shown. Refer to the Tube Assembly Detail.
- Attach cradle bracket to tube base. Refer to the Cradle Bracket Attachment Detail.
- 6) Attach metallo tube Permalene bottom to tube base. Refer to the Permalene® Bottom Attachment Detail.
- Attach mallet cradles to cradle bracket, as shown. Refer to the Mallet Cradle Assembly Detail.
- Attach metallo bar Permalene top to metallophone tube base, as shown.
 Refer to the Metallo Tube Permalene Top Attachment Detail.







216988



Sensory Play

214443 Goblet Drum

Iandscape structures

Sensory Play 214443 Goblet Drum

Parts List

Part#	Description	Qty.
213936	Drum Leg, (DB), Specify Color	1
204402	Drum Leg, (SM), Specify Color	
211062	Goblet Drum Top Assembly, Specify Color	
203966	Goblet Drum Head	1
204398	Permalene Trim, Specify Color	1
210433	8" Drum Screen, Specify Color	
217006	Goblet/Kundu Drum Hardware Package	1
216760	#14 x ³ / ₄ " BHCS Torx, SST	10
100195	³ / ₈ " x ⁵ / ₈ " BHCS w/Pin, SST	10
113027	³ / ₈ " x 1 ³ / ₈ " BHCS w/Pin, SST	3
100365	³ / ₈ " SAE Flat Washer, SST	
128296	³ / ₈ " Hex Jam Nut, SST	
133368	¹ / ₄ " Nylon Washer, SST	10
156962	⁵ / ₈ " O.D. x ¹ / ₂ " Long, SST	3
127463	T-27 TPP Hex Bit (Torx), SST	
100611	¹ / ₄ " x ³ / ₈ " Drive Rivet, AL/SST	3
121348	4-Hole Surface Mount Hardware Package	1
100266	¹ / ₂ " x 2 ³ / ₄ " Standard Hex Nut, SST	4
100322	¹ / ₂ " Standard Hex Nut, SST	4
100363	¹ / ₂ " Flat Washer, SST	4
DB = Direct Bury	y ·	
SM = Surface Mo	ount	

Specifications

Drum Leg: Made from 3.500" (88,9 mm) O.D. RS20 (.125")(3,17 mm) wall galvanized steel tubing. Finish: ProShield®, color specified.

Top Assembly: Weldment comprised of 3.500" (88,9 mm) O.D. RS20 (.125")(3,17 mm) wall galvanized steel tubing, 11

GA. (.120")(3,05 mm) flat steel and ½" (3,17 mm) thick HRPO steel sheet. Finish: ProShield®, color

specified.

Trim: Permalene®, color specified.

Screen: Made from 11 GA. (.125")(3,17 mm) thick aluminum

sheet. Finish: ProShield®, color specified.

Drum Head: Translucent, UV stabilized polycarbonate with a

matte textured surface on one side.

Fasteners: Primary fasteners shall be socketed and pinned tam-

perproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see specific product

installation/specifications).

Installation Time: DB - Approx. 3 man hours

SM - Approx. 2 1/2 man hours

Concrete Req.: **DB** - Approx. 1.78 cu. ft.

Weight: DB - 59 lbs.

SM - 53 lbs.

Installation Instructions

- (Direct Bury) Dig footing as shown.
- 2) (Direct Bury) With lower portion of drum leg plumb and in final position, pour concrete footing. Allow concrete footing to cure for a minimum of 24 hours before attaching drum assembly, drum head and trim to drum leg.

(Surface Mount) Drill $^{1}/_{2}$ " x 3" deep holes through drum mount post plate using hammer drill and $^{1}/_{2}$ " masonry bit. Tap expansion anchors into drilled holes. Fasten drum mount post plate to expansion anchors using $^{1}/_{2}$ " standard hex nuts with $^{1}/_{2}$ " flat washers.

- 3) Place drum onto leg. Drill through holes in drum assembly and into drum leg with a ¹/₄" or "F" (only) drill bit. Insert ¹/₄" x ³/₈" drive rivets into holes and hammer rivet pins in until flush with head.
- Attach drum head and trim to top assembly, as shown. Refer to the Drum Assembly Detail.
- Attach screen to drum top assembly. Refer to the Screen Attachment Detail.








216989

DETAILSURFACE MOUNT



Iandscape structures

Sensory Play 214444 Kundo Drum

Parts List

Part#	Description	Qty.
213936	Drum Leg, (DB), Specify Color	1
204402	Drum Leg, (SM), Specify Color	
204403	Kundu Drum Top Assembly, Specify Color	
203967	Kundu Drum Head	1
204401	Permalene Trim, Specify Color	
210434	10" Drum Screen, Specify Color	1
217006	Goblet/Kundu Drum Hardware Package	1
216760	#14 x ³ / ₄ " BHCS Torx, SST	
100195	³ / ₈ " x ⁵ / ₈ " BHCS w/Pin, SST	10
113027	³ / ₈ " x 1 ³ / ₈ " BHCS w/Pin, SST	
100365	³ / ₈ " SAE Flat Washer, SST	23
128296	³ / ₈ " Hex Jam Nut, SST	
133368	1/4" Nylon Washer, SST	10
156962	⁵ / ₈ " O.D. x ¹ / ₂ " Long, SST	3
127463	T-27 TPP Hex Bit (Torx), SST	1
100611	¹ / ₄ " x ³ / ₈ " Drive Rivet, AL/SST	
121348	4-Hole Surface Mount Hardware Package	1
100266	¹ / ₂ " x 2 ³ / ₄ " Standard Hex Nut, SST	4
100322	1/2" Standard Hex Nut, SST	
100363	¹ / ₂ " Flat Washer, SST	
DR = Direct R		

Specifications

SM = Surface Mount

Drum Leg: Made from 3.500" (88,9 mm) O.D. RS20 (.125")(3,17

mm) wall galvanized steel tubing. Finish: ProShield®,

color specified.

Top Assembly: Weldment comprised of 3.500" (88,9 mm) O.D. RS20

(.125")(3,17 mm) wall galvanized steel tubing, 11 GA. (.120")(3,05 mm) flat steel and $\frac{1}{8}$ " (3,17 mm) thick HRPO steel sheet. Finish: ProShield*, color

specified.

Trim: Permalene®, color specified.

Screen: Made from 11 GA. (.125")(3,17 mm) thick aluminum

sheet. Finish: ProShield®, color specified.

Drum Head: Translucent, UV stabilized polycarbonate with a

matte textured surface on one side.

Fasteners: Primary fasteners shall be socketed and pinned tamperproof in design, stainless steel (SST) per ASTM F

879 unless otherwise indicated (see specific product

installation/specifications).

Installation Time: DB - Approx. 3 man hours

SM - Approx. 2 1/2 man hours

Concrete Req.: DB - Approx. 1.78 cu. ft.

Weight: DB -54 lbs.

SM -49 lbs.

Installation Instructions

- 1) (Direct Bury) Dig footing as shown.
- 2) (Direct Bury) With lower portion of drum leg plumb and in final position, pour concrete footing. Allow concrete footing to cure for a minimum of 24 hours before attaching drum assembly, drum head and trim to drum leg.

(Surface Mount) Drill $^{1}/_{2}$ " x 3" deep holes through drum mount post plate using hammer drill and $^{1}/_{2}$ " masonry bit. Tap expansion anchors into drilled holes. Fasten drum mount post plate to expansion anchors using $^{1}/_{2}$ " standard hex nuts with $^{1}/_{2}$ " flat washers.

- 3) Place drum onto leg. Drill through holes in drum assembly and into drum leg with a ¹/₄" or "F" (only) drill bit. Insert ¹/₄" x ³/₈" drive rivets into holes and hammer rivet pins in until flush with head.
- 4) Attach drum head and trim to top assembly, as shown. Refer to the Drum Assembly Detail.
- Attach screen to drum top assembly. Refer to the Screen Attachment Detail.




DETAIL





216990

DETAILSURFACE MOUNT



Sensory Play

214445 Kettle Drum



Sensory Play 214445 Kettle Drum

Parts List

Part#	Description	Qty
213935	Kettle Drum Leg, DB, Specify Color	1
204405	Kettle Drum Mount Post, SM, Specify Color	
211950	Kettle Drum Assembly, Specify Color	1
203968	Drum Head	1
204404	Kettle Drum Permalene Trim, Specify Color	1
217004	Kettle Drum Hardware Package	1
100195	³ / ₈ " x ⁵ / ₈ " BHCS w/Pin, SST	
100365	³ / ₈ " SAE Flat Washer, SST	
128296	³ / ₈ " Hex Jam Nut, SST	
216760	#14 x ³ / ₄ " BHCS Torx, SST	20
133368	1/4" NylonWasher, SST	20
127463	T-27 TPP Hex Bit (Torx), SST	
100611	¹ / ₄ " x ³ / ₈ " Drive Rivet, AL/SST	3
121348	4-Hole Surface Mount Hardware Package	1
100266	¹ / ₂ " x 2 ³ / ₄ " Standard Hex Nut, SST	4
100322	1/2" Standard Hex Nut, SST	4
100363	1/2" Flat Washer, SST	
DR = Direct Rur	v	

Specifications

Concrete Req.:

Weight:

SM = Surface Mount

Permalene®, color specified. Drum Leg: Made from 3.500" (88,9 mm) O.D. RS20 (.125")(3,17 mm) wall galvanized steel tubing. Finish: ProShield®, color specified. **Drum Assembly:** Weldment comprised of 3.500" (88,9 mm) O.D. RS20 (.125")(3,17 mm) wall galvanized steel tubing and 11 GA. (.120")(3,05 mm) flat steel. Finish: ProShield[®], color specified. Drum Head: Translucent, UV stabilized polycarbonate with a matte textured surface on one side. Primary fasteners shall be socketed and pinned tamperproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see specific product installation/specifications). **DB** - Approx. 3 man hours **SM** - Approx. 2 1/2 man hours **Installation Time:**

DB - Approx. 1.78 cu. ft.

DB -66 lbs.

SM - 59 lbs

Installation Instructions

- (Direct Bury) Dig footing as shown.
- (Direct Bury) With lower portion of drum leg plumb and in final position, pour concrete footing. Allow concrete footing to cure for a minimum of 24 hours before attaching drum assembly, drum head and trim to drum leg.
 - (Surface Mount) Drill ¹/₂" x 3" deep holes through drum mount post plate using hammer drill and 1/2" masonry bit. Tap expansion anchors into drilled holes. Fasten drum mount post plate to expansion anchors using $\frac{1}{2}$ " standard hex nuts with $\frac{1}{2}$ " flat washers.
- Place drum onto leg/post with drain hole at lowest point. Drill through holes in drum assembly and into drum leg/post with a $^{1}/_{4}$ " or "F" (only) drill bit. Insert 1/4" x 3/8" drive rivets into holes and hammer rivet pins in until flush with head.
- Attach drum head and trim to drum assembly, as shown. Refer to the Drum Assembly Detail.







SAFETY NOTE

Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM F1487.)

17827400

Loose Fill Protective Surfacing Log Crawl Tunnel 31" 43" 1090 Finished Grade Loose Fill **DETAIL** Protective. **END VIEW** Surfacing Level Subgrade **Unitary Surfacing** Log Crawl Tunnel 37" 939 Log Crawl 43" 090 Unitary Tunnel Surfacing 2"/51 A 64 Concrete Fork Pock-Slab Crushed Rock NOTE: If pour in place surfacing is used, blend surfacing to cover 60" fork pockets. 1520

30"
760

Log Crawl Tunnel

Protective Surfacing

Play Naturally™

More Fun

173594 Log Crawl Tunnel



More Fun 173594 Log Crawl Tunnel

Parts List

Part# Qty. Description 175710 Log Crawl Tunnel..

Specifications

Log Crawl

Tunnel Assembly:

Weldment comprised of 1.900" (48,26 mm) O.D. RS20 (.090"-.100") (2,29 mm-2,54 mm) wall galvanized steel tubing, $^3/_{16}$ " HRPO steel plate and 7" x 3" x $^3/_{16}$ " (178 mm x 76 mm x 4,75 mm) wall rectangular tube. (Log Crawl Tunnel assembled) Glass reinforced wet cast solid pour concrete product. Finish: Latex paint made for concrete, natural colors.

Installation Time: Approx. ¹/₄ man hour

Weight: 2000 lbs. Min. Use Zone: 6' (1830 mm)

Log measures 60" long x 43" high **Actual Size:**

(1520 mm x 1090 mm high)

Fall Height: 41" (1040 mm) Max.

Installation Instructions

- The log crawl tunnel must be installed over an area of firm stable soil.
 - Warning: Never crawl under any part of The Log Crawl Tunnel especially when it is only supported by a forklift.
- To unload the log crawl tunnel, a "Lull" type material handler with at least an 4,000 lb. capacity is recommended. Maximum fork extension size is $2^{1/2}$ " high x $6^{1/2}$ " wide with no maximum length. **NOTE:** At least 2 people are recommended for the log crawl tunnel installation. One person to operate the material handling equipment and one person to spot for the operator.
- The log crawl tunnel should be placed on firm stable soil. Pick up the log crawl tunnel by inserting the material handling forks into the forklift pockets. Be very careful to keep the log crawl tunnel level to the ground when raising or lowering. Do not contact the concrete face of the log crawl tunnel with material handler forks, chipping can occur.
- Install protective surfacing before users are allowed to play on the structure.
- NOTE: After installation if Touch-up/Repairs are needed, contact Landscape Structures at 1-888-574-4678.



DETAIL LOG STEPPER SPACING






SAFETY NOTE

Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM

20070000



Play Naturally™

173907 8" Height (Shown) 173908 18" Height 173909 28" Height

Climbers

Log Steppers

Than 4"/100 Or Greater Than 11"/275

Surfacing





Parts List

Part#	Description	Qty.
200691	8" Log Stepper (DB), Natural	*
200692	18" Log Stepper (DB), Natural	*
200693	28" Log Stepper (DB), Natural	*
DD - Direct 1	Dunny	

DB = Direct Bury

Specifications

Log Stepper Assy.: (Footer Post) Weldment comprised of 5" O.D. x 11

GA. (.120") wall galvanized steel tubing and $\frac{3}{16}$ HRPO steel plate. Finish: ProShield, color specified. (Log Stepper-fully assembled) Glass reinforced wet cast solid pour concrete product. Finish: Latex paint

made for concrete, natural colors.

Approx. ¹/₂ man hour each Approx. 1.78 cu. ft. each **Installation Time: Concrete Req.:**

8" - 162 lbs. 18" - 230 lbs. Weight:

28" - 424 lbs.

Installation Instructions

- 1) (Direct Bury) Dig footing as shown. See your Plan View/Footing Layout.
- To unload the log steppers and place in footing holes, a "Lull" type material handler and strap are recommended. Position log steppers in footing holes at dimensions shown, and prop in plumb position. With log steppers and handrail plumb, pour concrete footings. Allow concrete footings to cure for a minimum of 72 hours before users are allowed to play on the structure.
- Install protective surfacing before users are allowed to play on the structure.

^{* =} Qunatity Determined By Your Order








SAFETY NOTE


Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM 54187)

17221500



PLAN VIEW/FOOTING LAYOUT

(Layout Varies - See Your Plan)



171568 8" Height (Shown) 171569 10" Height 171570 16" Height 171571 20" Height 171572 24" Height 171573 30" Height

Play Naturally™

Climbers

Mushroom Steppers



Climbers Mushroom Steppers

Parts List

Part#	Description	Qty.
206827	GFRC Mushrrom 8"-16" (DB)	*
206828	GFRC Mushrrom 20"-24" (DB)	*
206829	GFRC Mushrrom 30"-32" (DB)	*
DD D:4	D	

DB = Direct Bury

Specifications

GFRC Mushroom

(Support) Comprised of 2 ³/₈" O.D. RS40 (.130"-.140" Assembly:

wall) galvanized steel tubing. Finish: ProShield®. (Mushroom Stepper) Glass reinforced wet cast solid pour concrete product. Finish: Latex paint made for

concrete, natural colors.

Installation Time: Approx. 3/4 man hour each Approx. 1.78 cu. ft. each 8" - 333 lbs. 10" - 333 lbs. **Concrete Req.:** Weight:

16" - 333 lbs. 20" - 337 lbs. 24" - 337 lbs. 30" - 342 lbs.

Installation Instructions

- 1) (Direct Bury) Dig footing as shown. Refer to your Site Plan For Footing Locations.
- To unload the Mushroom Stepper and place in footing hole, a "Lull" type material handler and strap are recommended. Position Mushroom Stepper in footing hole, and prop in plumb position. With Mushroom Stepper plumb, pour concrete footing. Allow concrete footings to cure for a minimum of 72 hours before users are allowed to play on the structure.
- Install protective surfacing before users are allowed to play on the structure.
- NOTE: After installation if Touch-up/Repairs are needed, contact Landscape Structures at 1-888-574-4678.

^{* =} Quantity Determined By Your Order








SAFETY NOTE

Choose a protective surfacing material that has a Critical Height Value of at least the height of the Highest Accessible Part/Fall Height of the adjacent equipment. (Ref. ASTM F1487.)

17559300

PLAN VIEW/FOOTING LAYOUT



Play Naturally™

Sports & Fitness 173596 Log Balance Beam

Iandscape structures

Sports & Fitness 173596 Log Balance Beam

Parts List

D + #	D. I. d.	0.
Part#	Description	Qty
175712	Log Balance Beam	1
175706	Leg, SM, Brown	4
175707	Leg, DB, Brown	
175717	Log Balance Beam Hardware Package	1
100353	³ / ₈ " Flange Nut w/Pin, SST	8
116942	³ / ₈ " x 2" Threaded Rod, SST	
111392	2-Hole (SM) Hardware Package	4
100266	¹ / ₂ " x 2 ³ / ₄ " Expansion Anchor	8
100322	¹ / ₂ " Standard Hex Nut, SST	8
100363	¹ / ₂ " Flat Washer, SST	
DB = Direct Bury		

Specifications

SM = Surface Mount

Log Balance Beam

Assembly:

Weldment comprised of 1.900" O.D. RS20 (.090"-.100" wall) galvanized steel tubing and 2.375" O.D. RS20 (.095"-.105" wall) galvanized steel tubing. Finish: ProShield, brown in color. (Log-fully assembled) Glass reinforced wet cast solid pour concrete product. Finish: Latex paint made for concrete, natural colors.

made for concrete, natural colors

Leg: Fabricated from 2.375" O.D. RS20 (.095"-.105"

wall) galvanized steel tubing. Finish: ProShield,

brown in color.

Fasteners: Primary fasteners shall be socketed and pinned

tamperproof in design, stainless steel (SST) per ASTM F 879 unless otherwise indicated (see

specific product installation/specifications).

Installation Time: Approx. 2 man hours Approx. 3.66 cu. ft.

Weight: 387 lbs.

Min. Use Zone: 6' (1830 mm)

Actual Size: Log measures 98" long x 42" wide

(2490 m x 1070 mm wide)

Fall Height: 12" (200 mm)


Installation Instructions

(Direct Bury) - Dig footing holes, spaced as shown. Attach legs to log balance beam, using ³/₈" x 2" threaded rods and ³/₈" flange nuts with pin. Place log balance beam in footing holes and temporarily brace in plumb and level position. Pour concrete footings and let cure for a minimum of 72 hours before users are allowed to play on the structure.

(Surface Mount) - Attach legs to log balance beam, using $^{3}/_{8}$ " x 2" threaded rods and $^{3}/_{8}$ " flange nuts with pin. Set log balance beam in proper position and mark anchor bolt locations on concrete slab through holes in anchor plates. Move log balance beam aside and drill $^{1}/_{2}$ " x 3" deep holes in marked locations on concrete slab using $^{1}/_{2}$ " masonry bit and hammer drill. Reposition log balance beam over drilled holes and tap expansion anchors into holes. Fasten using and $^{1}/_{2}$ " standard hex nuts with $^{1}/_{2}$ " flat washers.

- Install protective surfacing before users are allowed to play on the structure.
- 3) NOTE: After installation if Touch-up/Repairs are needed, contact Landscape Structures at 1-888-574-4678.

APPENDIX B PRELIMINARY GAZEBO STRUCTURE DRAWINGS



Shelter Systems Inc

DISTINCTIVE STEEL SHELTERS
WWW.ICONSHELTERS.COM
COPYRIGHT 2004, ICON SHELTER
SYSTEMS, INC.

1455 LINCOLN AVE. HOLLAND MI, 49423

616.396.0919 800.748.0985 616.396.0944 FX

Elevation

DRAWN BY:

ACP DATE:

6/27/2016

JOB NO.:

STANDARD REVISION:

BUILDING TYPE: HX30TM2C-P4

PROJECT NAME:

SHEET



THESE FOUNDATION LOADS ARE FOR ESTIMATING PURPOSE ONLY. THE ACTUAL LOADS WILL BE DETERMINED IN THE FINAL ENGINEERING

LOADS TO FOUNDATION					CL1
(KIPS, IN-KIPS)	FOUNDATION LOADS				
LOAD COMBINATION	AXIAL (Fx)	SHEAR (Fy)	SHEAR (Fz)	MOMENT (My)	MOMENT (Mz)
DL	4.02	0.00	0.16	-5.62	0.00
SL	2.68	0.00	0.23	-8.90	0.13
W-UPLIFT	-4.25	-0.35	-0.50	5.63	-13.44
W-FY	-2.70	-0.59	-0.17	-5.49	-14.49
W-FZ	-2.95	-0.54	-0.63	23.63	-7.64
E-FY	0.00	-0.80	0.00	0.00	-26.15
E-Z	-0.61	0.00	-1.02	43.37	0.00

NOTES:


- TABLE SHOWS UNFACTORED SERVICE LOADS

- A FOUNDATION DESIGN HAS NOT BEEN PERFORMED BY ICON SHELTER SYSTEMS INC.

- A LICENSED ENGINEER FAMILIAR WITH SOIL CONDITIONS AT CONSTRUCTION SITE MUST PERFORM A FOUNDATION DESIGN.

- THE STRUCTURE HAS BEEN ENGINEERED AS AN OPEN STRUCTURE.
 CONSULT ICON SHELTER SYSTEMS INC. IF THE STRUCTURE IS TO BE ENCLOSED.
 COORDINATES ARE LOCAL TO THE COLUMN

DEFINITIONS:
DL = SERVICE LEVEL DEAD LOAD REACTION WITH THE GREATEST AXIAL LOAD
SL = SERVICE LEVEL SNOW LOAD REACTION WITH THE GREATEST AXIAL LOAD W-UL = SERVICE LEVEL WIND LOAD REACTION WITH THE GREATEST UPLIFT LOAD W-Y = SERVICE LEVEL WIND LOAD REACTION WITH THE GREATEST MAGNITUDE OF SHEAR IN THE LOCAL Y DIRECTION
W-Z = SERVICE LEVEL WIND LOAD REACTION WITH THE GREATEST SHEAR VALUE ACTING IN THE SAME DIRECTION AS THE DL SHEAR LOAD E-Y = SERVICE LEVEL SEISMIC LOAD REACTION WITH THE GREATEST MAGNITUDE OF SHEAR IN THE LOCAL Y DIRECTION E-Z = SERVICE LEVEL SEISMIC LOAD REACTION WITH THE GREATEST MAGNITUDE OFSHEAR IN THE LOCAL Z DIRECTION



PRELIMINARY: NOTH DISTING

Shelter Systems Inc

DISTINCTIVE STEEL SHELTERS WWW.ICONSHELTERS.COM COPYRIGHT 2004, ICON SHELTER

> 1455 LINCOLN AVE. HOLLAND MI, 49423

> > 616 396 0919 800.748.0985 616.396.0944 FX

> > > nok p nchor

DRAWN BY:

DATE:

ACP

6/27/2016

JOB NO.: STANDARD

REVISION:

BUILDING TYPE:

HX30TM2C-P4

PROJECT NAME:

SHEET

COLUMN TYPE: B (SURFACE MOUNT W/ COVERS)

3/4" ANCHOR BOLT

W/ 3/4" NUTS (4) PLCS

CONCRETE FOOTING
NOT TO SCALE


DRAWINGS

ACTUAL FOOTING DESIGN

SHOWN ON INSTALLATION

BASE COVERS

OPTIONAL




PRELIMINARY: NOT FOR

PRELIMINARY: NOT FOR

PRELIMINARY: NOT FOR

OF THE PROPERTY OF THE PROPE



ALL STRUCTURAL COMPONENTS WILL BE:

TUBE: ASTM A500 GRADE B

PLATE: ASTM A36 BOLTS: ASTM A325 NUTS: ASTM A563 WELDING: GMAW

<u>NOTE:</u>

COLUMN SIZE: HSS 6x6x3/16

Shelter Systems Inc

DISTINCTIVE STEEL SHELTERS WWW.ICONSHELTERS.COM COPYRIGHT 2004, ICON SHELTER

> 1455 LINCOLN AVE. HOLLAND MI, 49423

> > 616.396.0919 800.748.0985 616.396.0944 FX

> > > Frame

DRAWN BY:

DATE:

ACP

6/27/2016 JOB NO.:


STANDARD

REVISION:

BUILDING TYPE: HX30TM2C-P4

PROJECT NAME:





- ATTACH WITH 2" DECK SCREWS


12" O.C. STAGGERED


NAILER BOARD

12" O.C. AT BOTTOM

ATTACH WITH 2" DECK SCREWS

PRELIMINARY: NOT FOR INDICATION IN PROPERTY OF THE PROPERTY OF THE





TONGUE & GROOVE
PRIMARY ROOF NOT IN CONTRACT

Shelter Systems Inc.

Shelter Systems Inc

DISTINCTIVE STEEL SHELTERS
WWW.ICONSHELTERS.COM
COPYRIGHT 2004, ICON SHELTER

1455 LINCOLN AVE. HOLLAND MI, 49423

> 616.396.0919 800.748.0985 616.396.0944 FX

> > Roof Layout

DRAWN BY:

ACP

DATE: 6/27/2016

JOB NO.:

STANDARD REVISION:

.


BUILDING TYPE: HX30TM2C-P4


PROJECT NAME:

SHEET

SHEET

Sheering \(\text{COMPRETB} \)





NOTE: STANDARD DETAILS SHOWN

ACTUAL BUILDING MAY VARY

PRELIMINARY: NOTH CC



SHEET

SHEET

Cogineering \Accession(300 \text{\text{\$\congression}} \text{\text{\$\con

Shelter Systems Inc

DISTINCTIVE STEEL SHELTERS
WWW.ICONSHELTERS.COM
COPYRIGHT 2004, ICON SHELTER
SYSTEMS, INC.

1455 LINCOLN AVE. HOLLAND MI, 49423

> 616.396.0919 800.748.0985 616.396.0944 FX

> > Roof

DRAWN BY:

DATE:

6/27/2016

JOB NO.:

STANDARD

REVISION:

BUILDING TYPE:

HX30TM2C-P4


PROJECT NAME:

— CONTRACT DRAWINGS—

SENSORY TRAIL IMPROVEMENTS WATCHUNG RESERVATION


BOROUGH OF MOUNTAINSIDE UNION COUNTY, NEW JERSEY


SEPTEMBER 2016
UNION COUNTY PROJECT NO.: 2016-006, BA NO.: 5-2017





INDEX OF DRAWINGS


Sheet No.	Description
1	COVER & INDEX SHEET
2	EXISTING CONDITIONS & DEMOLITION PLAN
3	OVERALL SITE PLAN
4	SITE & LANDSCAPE PLAN ENLARGEMENTS
5	GRADING & DRAINAGE PLAN
6	SOIL EROSION & SEDIMENT CONTROL PLAN & DETAILS
7	SOIL EROSION & SEDIMENT CONTROL NOTES & DETAILS
8	CONSTRUCTION DETAILS (1 OF 2)
9	CONSTRUCTION DETAILS (2 OF 2)
10	LANDSCAPE NOTES & DETAILS











给 UN LOG BENCH, 6' LONG UN ACORN_SÉAT UN DECORATIVE TABLE UN FIRE WOOD STORAGE RACK WITH COVER SF ENGINEERED WOOD FIBER SAFETY MULCH, 6" THICK LE CONCRETE DEPRESSED CURB $\times 425.37$

EXISTING OUTDOOR CLASSROOM AREA

SCALE: 1" = 10' - 0"

CONTRACTOR SHALL PROVIDE A MINIMUM OF SIX (6)
INCHES OF SCREENED TOPSOIL WITHIN ALL PLANTING
AREAS. ANY AREAS OF COMPACTED FILL OR SUBGRADE
SHALL BE TILLED AND LOOSENED PRIOR TO THE
INSTALLATION OF THE TOPSOIL.

LF Concrete Depressed Curb

SY Concrete Paver Patio, including Sub-base SF Engineered Wood Fiber Safety Mulch, 6" Thick UN Raised Garden Planter

SEE SHEET 10 OF 10 FOR PLANT SCHEDULE AND

INSTALLATION NOTES AND DETAILS


CONSTRUCT

MAIN SENSORY GATHERING SPACE

OUTDOOR CLASSROOM AREA (NEAR EXISTING DEER MANAGEMENT STUDY AREA) SCALE: 1" = 20'-0"

> - LIMITS OF CONTINUOUS MULCHED BED (TYP.)

 $\times 438.44$



 $\times 441.89$

UN Raised Garden Planter
UN Gazebo, 30' Wide, including Concrete Foundations
PR Chitter—Chatter Noodle, including Concrete Foundations
UN Sensory Play Center, including Concrete Foundations
UN Log Crawl Tunnel, including Concrete Foundations
UN Log Balance Beam, including Concrete Foundations
UN Log Stepper, including Concrete Foundation
UN Mushroom Stepper, including Concrete Foundation
UN Goblet Drum, including Concrete Foundation
UN Kundo Drum, including Concrete Foundation
UN Kettle Drum, including Concrete Foundation
UN Vivo Metallophone, including Concrete Foundations
UN Log Bench, 6' Long, including Concrete Foundations
UN Acorn Seat, including Concrete Foundation
UN Decorative Table, including Concrete Foundations
UN Fire Pit Kit, including Sub—base
UN Fire Wood Storage Rack with Cover, including 4" Thick C UN Fire Wood Storage Rack with Cover, including 4" Thick Concrete Pad

REVISED DATE FOR REBID 1/6/17 SEL SEL DATE DRAWN CHECKE DESCRIPTION OF REVISION BOROUGH OF MOUNTAINSIDE UNION COUNTY, NEW JERSEY SENSORY TRAIL IMPROVEMENTS WATCHUNG RESERVATION SITE & LANDSCAPE PLAN ENLARGEMENTS CONSULTING AND MUNICIPAL ENGINEERS

— 3141 BORDENTOWN AVENUE, PARLIN, NEW JERSEY 08869 —— 1460 ROUTE 9 SOUTH, HOWELL, NEW JERSEY 07731-1194 — JOHN H. ALLGAIR P.E., P.P. (1983-2001) DAVID J. SAMUEL P.E., P.P. JOHN J. STEFANI P.E., L.S. & P.P. NU PE UC NO. 25838 NU FP UC NO. 2455 NU FE IS UC NO. 24271 NJ FP LIC NO. 2007 JAY B. CORNELL P.E., P.P. MICHAEL J. McCLELLAND P.E., P.P. GREGORY R. VALESI P.E., P.P. NU FP LIC NO. 3770 NJ PE LIC NO. 34458 **AS SHOWN**

NJ. LIC. 34458

SEP 2016

MAIN SENSORY GATHERING SPACE LANDSCAPE PLAN

SCALE: 1" = 10'-0"

PARKING ---BOARDWALK STRUCTURE TO BE ELEVATED TO PREVENT ANY DISRUPTION WOODED AREA TO EXISTING DRAINAGE PATTERNS (TYP.) LOT 4 BLOCK 2 LS EARTHWORK AND SUBGRADE PREPARATION NOTE:

THE CONTRACTOR IS ADVISED THE PROJECT SITE IS WITHIN A PUBLIC PARK. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO ENSURE SAFETY OF PARK USERS DURING CONSTRUCTION.

NOTE:

CONTRACTOR IS ADVISED MINIMAL DISTURBANCE IS ANTICIPATED ALONG THE ENTIRE LENGTH OF THE SENSORY TRAIL. CONTRACTOR SHALL MAINTAIN EXISTING GRADING OF THE TRAIL AND SURROUNDING AREAS, UNLESS OTHERWISE NOTED ON THE PLAN SET.

<u>NO72</u>

THE CONTRACTOR SHALL BE REQUIRED TO RESTORE ALL AREAS OF DISTURBANCE AROUND THE PERIMETER OF THE IMPROVEMENTS AND ANY DISTURBANCE CAUSED BY CONSTRUCTION OPERATIONS OR STAGING. CONTRACTOR SHALL ANTICIPATE THE INSTALLATION OF TOPSOIL, FERTILIZER AND SEED IN THESE AREAS.

NOTE:

UNLESS OTHERWISE NOTED, THE TRAIL SHALL NOT EXCEED FIVE (5) PERCENT RUNNING SLOPE AND TWO (2) PERCENT CROSS SLOPE.

NOTE:


THE CONTRACTOR SHALL ENSURE FINAL CONSTRUCTION OF THE TRAIL AND BOARDWALK STRUCTURES COMPLY WITH ADA REQUIREMENTS FOR AN ACCESSIBLE TRAIL.

CONSTRUCT

1 LS Earthwork and Subgrade Preparation, including all Cuts, Fills, Import Fill, Compaction, Grading, Removal of Excess/Unsuitable Soils, and all Incidental Work

2	REVIS	SED DATE FOR REBID		1/6/17	SEL	SEL
No.	DESC	RIPTION OF REVISION		DATE	DRAWN	CHECKED
	BOROUGH OF MOUNTAINSIDE UNION COUNTY, NEW JERSEY SENSORY TRAIL IMPROVEMENTS WATCHUNG RESERVATION					GRADE
	GRA	ADING & DRAINAGE P	LAN			
	ASSOCIATES CONSULTING AND MUNICIPAL ENGINEERS 3141 BORDENTOWN AVENUE, PARLIN, NEW JERSEY 08869 — 1460 ROUTE 9 SOUTH, HOWELL, NEW JERSEY 07731-1194					DEWNING No.: 5U
JOH	IN H. ALLGAIR P.E., P.P. (1903-2001)	DAVID J. SAMUEL P.E., P.P. NU PE UC NO. 25830 NU PE UC NO. 2485	JOHN J. STEF	'ANI P.E., L.S. & P.I 71 NIF	P. UC NO. 2007	
	B. CORNELL P.E., P.P. UC NO. 32962 NU PP UC NO. 3874	MICHAEL J. McCLELLAND P.E., P.P. NJ PEUC NO. 32344 NJ PP UC NO. 3770	NJ PE LIC NO. 34458		LIC NO. 4361] =
NE	REGORY R. VAL		DESIGNED BY	240' CHECKED BY DGP SHEET 5	DGP TT OF 10	TEN: UN206.0

THE INTENT OF THE INSTALLATION OF THIS SENSORY TRAIL IS TO PROUDE MINIMUM DISTURBANCE TO THE EXISTING WOODED AREA. THE CONTRACTOR SHALL PAY SPECIFIC ATTENTION TO THE OVERALL WIDTH OF THE TRAIL AND MINIMIZE DISTURBANCE THROUGHOUT THE INSTALLATION. AT NO TIME SHALL THE CONTRACTOR DISTURB AN AREA GREATER THAN TEN (10) FEET WIDE UNLESS OTHERWISE NOTED ON THE PLAN SET. ANY DISTURBANCE OR DAMAGED TREES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR AND/OR REMOVE AT NO ADDITIONAL COST TO THE COUNTY. SHOULD THE EXCESS DISTURBANCE RESULT IN ANY FINES, PENALTIES OR ADDITIONAL WORK REQUIRED BY ANY REGULATING AGENCIES, THIS ALSO SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR AT NO ADDITIONAL COST TO THE COUNTY.



SOIL EROSION AND SEDIMENT CONTROL NOTES:

- . The Somerset-Union Soil Conservation District shall be notified in writing 48 hours in advance of any land disturbing activity.
- All Soil Erosion and Sediment Control practices shall be installed prior to any major soil sturbances, or in their proper sequence and maintained until permanent protection is established.
- Any Disturbed areas that will be left exposed more than 30 Days and not subject to construction traffic, will immediately receive a temporary seeding. If the season prevents the establishment of a temporary cover, the disturbed areas will be mulched with straw, or equivalent material, at a rate of two (2) tons per acre, according to NJ State Standards.
- 4. Permanent Vegetation shall be seeded or sodded on all exposed areas within ten (10) days after final grading. Mulch will be used for protection until seeding is established.
- 5. All work shall be done in accordance with the NJ State Standards for Soil Erosion and Sediment
- 6. A sub-base course will be applied immediately following rough grading and installation of improvements in order to stabilize streets, roads, driveways and parking areas. In areas where no utilities are present, the sub-base shall be installed within 15 days or preliminary grading.
- Immediately following initial disturbance or rough grading all critical areas subject to erosion (i.e.: steep slopes, roadway embankments) will receive a temporary seeding in combination with straw mulch or a suitable equivalent, at a rate of two (2) tons per acre, according to the NJ State Standards.
- 8. Any steep slopes receiving pipeline installation will be backfilled and stabilized daily, as the installation proceeds (i.e.: slopes areater that 3:1).
- 9. Traffic control Standards require the installation of a 50 x30 x6"pad of 1 1/2" or 2" stone, at all construction driveways, immediately after initial site disturbance.
- 10. At the time when the site preparation for permanent vegetative stabilization is going to be accomplished, any soil that will not provide a suitable environment to support adequate vegetative ground cover, shall be removed or treated in such a way that will permanently adjust the soil conditions and render it suitable for vegetative ground cover. If the removal or treatment of the soil will not
- 11. In that NJSA 4:24-39 et seq., requires that no Certificate of Occupancy be issued before the provisions of the Certified Plan for Soil Erosion and Sediment Control have been complied with for permanent measures, all site work for site plans and all work around individual lots in subdivisions, will

nave to be completed prior to the District issuing a Report of Compliance for the issuance of a

ertificate of Occupancy by the Municipality.

- 12. Conduit Outlet Protection must be installed at all required outfalls prior to the drainage system
- 13. Any changes to the Certified Soil Erosion and Sediment Control Plan will require the submission of revised Soil Erosion and Sediment Control Plans to the District for recertification. The revised plans must meet all current NJ State Soil Erosion & Sediment Control Standards.
- 14. The Somerset-Union Soil Conservation District shall be notified of any changes in ownership.
- 15. Mulching to the NJ Standards is required for obtaining a Conditional Report of Compliance Conditionals are only issued when the season prohibits seeding.
- 16. Contractor is responsible for keeping all adjacent roads clean during life of construction project
- 17. The developer shall be responsible for remediating any erosion or sediment problems that arise as a result of ongoing construction at the request of the Somerset—Union Soil Conservation District. 18. Hydro seeding is a two— step process. The first step includes seed, fertilizer, lime, etc., along with minimal amounts of mulch to promote consistency, good seed to soil contact, and give a visual indication of coverage. Upon completion of seeding operation, hydromulch should be applied at a rate of 1500 lbs. per acre in second step. The use of hydromulch, as opposed to straw, is limited to optimum
- 19. Unfiltered dewatering is not permitted. Necessary precautions must be taken during all dewatering operations to minimize soil transfer. Any dewatering methods used must be in accordance with the Standard for Dewatering. a Certificate of Occupancy or Temporary Certificate of Occupancy, respectively

STANDARD FOR PERMANENT VEGETATIVE COVER FOR SOIL STABILIZATION

<u>Methods and Materials</u>

1. Site Preparation

- A. Grade as needed and feasible to permit the use of conventional equipment for seedbed preparation, seeding, mulch application, and mulch anchoring. All grading should be done in accordance with Standard for Land Grading.
- B. Immediately prior to seeding and topsoil application, the subsoil shall be evaluated for compaction in accordance with the Standard for Land Grading.
- C. Topsoil should be handled only when it is dry enough to work without damaging the soil structure. A uniform application to a depth of 5 inches (unsettled) is required on all sites. Topsoil shall be amended with organic matter, as needed, in accordance with the Standard for Topsoiling.
- D. Install needed erosion control practices or facilities such as diversions, grade—stabilization structures, channel stabilization measures, sediment basins,

. Seedbed Preparation

- A. Uniformly apply ground limestone and fertilizer to topsoil which has been spread and firmed, according to soil test recommendations such as offered by Rutgers Co-operative Extension Soil sample mailers are available from the local Rutgers Cooperative Extension offices (http://njaes.rutgers.edu/county/). Fertilizer shall be applied at the rate of 500 pounds per acre or 11 pounds per 1,000 square feet of 10-10-10 or equivalent with 50% water insoluble nitroger unless a soil test indicates otherwise and incorporated into the surface 4 inches. If fertilizer is not incorporated, apply one-half the rate described above during seedbed preparation and repeat another one—half rate application of the same fertilizer within 3 to 5 weeks after seeding.
- B. Work lime and fertilizer into the topsoil as nearly as practical to a depth of 4 inches with a disc, spring—tooth harrow, or other suitable equipment. The final harrowing or disking operation should be on the general contour. Continue tillage until a reasonable uniform seedbed is prepared.
- C. High acid producing soil. Soils having a pH of 4 or less or containing iron sulfide shall be covered with a minimum of 12 inches of soil having a pH of 5 or more before initiating seedbed reparation. See Standard for Management of High Acid-Producing Soils for specific requirements.

- A. Select a mixture from Table 4–3 or use a mixture recommended by Rutgers Cooperative Extension or Natural Resources Conservation Service which is approved by the Soil Conservation District. Seed germination shall have been tested within 12 months of the planting date. No seed shall be accepted with a germination test date more than 12 months old unless retested.
- 1. Seeding rates specified are required when a report of compliance is requested prior to actual establishment of permanent vegetation. Up to 50% reduction in rates may be used when permanent vegetation is established prior to a report of compliance inspection. These rates apply to all methods of seeding. Establishing permanent vegetation means 80% vegetative coverage with the specified seed mixture for the seeded area and mowed once.
- 2. Warm—season mixtures are grasses and legumes which maximize growth at high temperatures, generally 85oF and above. Planting rates for warm-season grasses shall be the amount of Pure Live Seed (PLS) as determined by germination testing results.
- 3. Cool—season mixtures are grasses and legumes which maximize growth at temperatures below 85oF. Many grasses become active at 65oF. See Table 4-3, mixtures 7&14. Adjustment of planting rates to compensate for the amount of PLS is not required for cool season grasses.
- B. Conventional Seeding is performed by applying seed uniformly by hand, cyclone (centrifugal) seeder, drop seeder, drill or cultipacker seeder. Except for drilled, hydroseeded or cultipacked seedings, seed shall be incorporated into the soil within 24 hours of seedbed preparation to a depth of 1/4 to 1/2 inch, by raking or dragging. Depth of seed placement may be 1/4 inch deeper on coarse-textured soil.
- C. After seeding, firming the soil with a corrugated roller will assure good seed—to—soil contact, restore capillarity, and improve seedling emergence. This is the preferred method. When performed on the contour, sheet erosion will be minimized and water conservation on site will be maximized.
- D. Hydroseeding is a broadcast seeding method usually involving a truck, or trailer—mounted tank, with an agitation system and hydraulic pump for mixing seed, water and fertilizer and spraying the mix onto the prepared seedbed. Mulch shall not be included in the tank with seed. Short-fibered mulch may be applied with a hydroseeder following seeding. (also see Section 4-Mulching below). Hydroseeding is not a preferred seeding method because seed and fertilizer are applied to the surface and not incorporated into the soil. When poor seed to soil contact occurs, there is a reduced seed germination and

(See Mulching Specification for Permanent and Temporary Vegetative Cover for Soil Stabilization)

5. Irrigation (where feasible)

If soil moisture is deficient supply new seeding with adequate water (a minimum of 1/4 inch applied up to twice a day until vegetation is well established). This is especially true when seedings are made in abnormally dry or hot weather or on droughty sites.

Since soil organic matter content and slow release nitrogen fertilizer (water insoluble) are prescribed in Section 2A - Seedbed Preparation in this Standard, no follow-up of topdressing is mandatory. An exception may be made where gross nitrogen deficiency exists in the soil to the extent that turf failure may develop. In that instance, topdress with 10-10-10 or equivalent at 300 pounds per acre or 7 pounds per 1,000 square feet every 3 to 5 weeks until the gross nitrogen deficiency in the turf is ameliorated.

7. Establishing Permanent Vegetative Stabilization

The quality of permanent vegetation rests with the contractor. The timing of seeding, preparing the seedbed, applying nutrients, mulch and other management are essential. The seed application rates in Table 4–3 are required when a Report of <u>Compliance</u> is requested prior to actual establishment of permanent vegetation. Up to 50% reduction in application rates may be used when permanent vegetation is established prior to requesting a Report of Compliance from the district. These rates apply to all methods of seeding. Establishing permanent vegetation means 80% vegetative cover (of the seeded species) and mowed once. Note this designation of mowed once does not guarantee the permanency of the turf should other maintenance factors be neglected o otherwise mismanaged. ulch shall not be mixed in the tank with seed. Use is limited to flatter slopes and during optimum seeding periods in spring and fall.

TABLE 4-3 (SELECTIONS AND RECOMMENDATIONS FROM TABLE 4-3)

PERMANENT SEED IN DETENTION BASIN MIXTURE: PERMANENT SEED MIXTURE:

- 130 LBS/ACRE STRONG CREEPING RED FESCUE 50 LBS/ACRE KENTUCKY BLUEGRASS PERENNIAL RYE GRASS OR 20 LBS/ACRE 10 LBS/ACRE REDTOP _5 LBS/ACRE PLUS WHITE CLOVER 215 LBS/ACRE
- CONSISTING OF: (COOL SEASON SEED MIXTURE #7) CONSISTING OF: (COOL SEASON SEED MIXTURE #14) 265 LBS/ACRE TALL FESCUE 20 LBS/ACRE KENTUCKY BLUEGRASS (BLEND) 20 LBS/ACRE PERENNIAL RYE GRASS (BLEND)
- . SEED MIX SHALL BE FRESH, CLEAN, NEW-CROP SEED WITH A GUARANTEED STATEMENT OF COMPOSITION.
- . SEED TO BE PLANTED IN ACCORDANCE WITH THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL
- I. SEED TO BE PLANTED TO ITS OPTIMUM DEPTH OF 1/2".

5. SEEDING DATES: MARCH 1 - NOVEMBER 15.

STANDARD FOR TEMPORARY VEGETATIVE COVER FOR SOIL STABILIZATION

Methods and Materials

1. Site Preparation

- A. Grade as needed and feasible to permit the use of conventional equipment for seedbed preparation, seeding, mulch application, and mulch anchoring. All grading should be done in accordance with Standards for Land Grading.
- B. Install needed erosion control practices or facilities such as diversions, grade stabilization structures, channel stabilization measures, sediment basins,
- C. Immediately prior to seeding, the surface should be scarified 6" to 12" where there has been soil compaction. This practice is permissible only where there is no danger to underground utilities (cables, irrigation systems, etc.).

2. Seedbed Preparation

- A. Apply ground limestone and fertilizer according to soil test recommendations such as offered by Rutgers Co-operative Extension. Soil sample mailers are available from the local Rutgers Cooperative Extension offices. Fertilizer shall be applied at the rate of 500 pounds per acre or 11 pounds per 1,000 square feet of 10-20-10 or equivalent with 50% water insoluble nitrogen unless a soil test indicates otherwise. Apply limestone at the rate of 2 tons/acre unless soil testing indicates otherwise. Calcium carbonate is the equivalent and standard for measuring the ability of liming materials to neutralize soil acidity and supply calcium and magnesium to grasses and
- B. Work lime and fertilizer into the soil as nearly as practical to a depth of 4 inches with a disc, springtooth harrow, or other suitable equipment. The final harrowing or disking operation should be on the general contour. Continue tillage until a reasonable uniform seedbed is prepared.
- C. Inspect seedbed just before seeding. If traffic has left the soil compacted, the area must be retilled in accordance with the above.
- D. Soils high in sulfides or having a pH of 4 or less refer to Standard for Management of High Acid Producing Soils.

- A. Select seed from recommendations in Table 7-2.
- B. Conventional Seeding. Apply seed uniformly by hand, cyclone (centrifugal) seeder, drop seeder, drill or cultipacker seeder. Except for drilled, hydroseeded or cultipacked seedings, seed shall be incorporated into the soil. to a depth of 1/4 to 1/2 inch, by raking or dragging. Depth of seed placement may be 1/4 inch deeper on coarse textured soil.
- C. Hydroseeding is a broadcast seeding method usually involving a truck or trailer mounted tank, with an agitation system and hydraulic pump for mixing seed, water and fertilizer and spraying the mix onto the prepared seedbed. Mulch shall not be included in the tank with seed. Short fibered mulch may be applied with a hydroseeder following seeding. (also see Section IV Mulching) Hydroseeding is not a preferred seeding method because seed and fertilizer are applied to the surface and not incorporated into the soil. Poor seed to soil contact occurs reducing seed germination and growth. Hydroseeding may be used for areas too steep for conventional equipment to traverse or too obstructed with rocks, stumps, etc.
- D. After seeding, firming the soil with a corrugated roller will assure good seed-to-soil contact, restore capillarity, and improve seedling emergence This is the preferred method. When performed on the contour, sheet erosion will be minimized and water conservation on site will be maximized.

(See Mulching Specification for Permanent and Temporary Vegetative Cover for Soil Stabilization)

TABLE 7-2 (SELECTION AND RECOMMENDATIONS FROM TABLE 7-2)

- TEMPORARY SEED MIXTURE: . CONSISTING OF PERENNIAL RYEGRASS (COOL SEASON GRASS #1) AT A RATE OF 1 LB/1000 S.F.
- . SEED MIX SHALL BE FRESH, CLEAN, NEW-CROP SEED WITH A GUARANTEED STATEMENT OF
- 5. SEED TO BE PLANTED IN ACCORDANCE WITH THE STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL IN NEW JERSEY.
- 4. SEED TO BE PLANTED TO ITS OPTIMUM DEPTH OF 1/2".
- 5. SEEDING DATES: MARCH 1 MAY 15 AND AUGUST 15 OCTOBER 1

MULCHING SPECIFICATION FOR PERMANENT AND TEMPORARY VEGETATIVE COVER FOR SOIL STABILIZATION

- Mulching is required on all seeding. Mulch will insure against erosion before grass is established and will promote faster and earlier establishment. The existence of vegetation sufficient to control soil erosion shall be deemed compliance with this mulching requirement.
- A. Straw or Hay. Unnrotted small grain straw, hay free of seeds, applied at the rate of 1-1/2 to 2 tons per acre (70 to 90 pounds per 1,000 square feet), except that where a crimper is used instead of a liquid mulch—binder (tackifying or adhesive agent), the rate of application is 3 tons per acre. Mulch chopper—blowers must <u>not</u> grind the mulch. Hay mulch is not recommended for establishing fine turf or lawns due to the presence of weed seed.
- olication. Spread mulch uniformly by hand or mechanically so that approximately 85%-95% of the soil surface will be covered. For uniform distribution of hand-spread mulch, divide area into approximately 1,000 square feet sections and distribute 70 to 90 pounds within each section.
- Anchoring shall be accomplished immediately after placement to minimize loss by wind or water. This may be done by one of the following methods, depending upon the size of the area, steepness of

1. Peg and Twine. Drive 8 to 10 inch wooden pegs to within 2 to 3 inches of the soil surface every 4 feet in all directions. Stakes may be driven before or after applying mulch. Secure mulch to soil surface by stretching twine between pegs in a cris—cross and a square pattern. Secure twine around each peg with two or more round turns.

2. Mulch Nettings. Staple paper, jute, cotton, or plastic nettings to the soil surface. Use a degradable netting in areas to be mowed.

3. Crimper (mulch anchoring tool). A tractor-drawn implement, somewhat like a disc harrow, especially designed to push or cut some of the broadcast long fiber mulch 3 to 4 inches into the soil so as to anchor it and leave part standing upright. This technique is limited to areas traversable by a tractor, which must operate on the contour of slopes. Straw mulch rate must be 3 tons per acre. No tackifying or adhesive agent is required.

4. Liquid Mulch—Binders. — May be used to anchor hay or straw mulch.

a. Applications should be heavier at edges where wind may catch the mulch, in valleys, and at crests of banks. The remainder of the area should be uniform in appearance.

b. Use one of the following:

other products.

(1) Organic and Vegetable Based Binders - Naturally occurring, powder based, hydrophilic materials when mixed with water formulates a gel and when applied to mulch under satisfactory curing conditions will form membraned networks of insoluble polymers. The vegetable gel shall be physiologically harmless and not result in a phytotoxic effect or impede growth of turfgrass. Use at rates and weather conditions as recommended by the manufacturer to anchor mulch materials. Many new products are available, some of which may need further evaluation for use in this state.

(2) Synthetic Binders — High polymer synthetic emulsion, miscible with water when diluted and following application to mulch, drying and curing shall no longer be soluble or dispersible in water. It shall be applied at rates recommended by the manufacturer and remain tacky until germination of grass.

Note: All names give above are registered trade names. This does not constitute a commendation of these products to the exclusion of

- B. Wood-fiber or paper-fiber mulch. Shall be made from wood, plant fibers or paper containing no growth or germination inhibiting materials, used at the rate of 1,500 ponds per acre (or as recommended by the project manufacturer) and may be applied by a hydroseeder. This mulch shall not be mixed in the tank with seed. Use is limited to flatter slopes and during optimum seeding periods in spring and fall.
- C. Pelletized mulch. Compressed and extruded paper and/or wood fiber product, which may contain co-polymers, tackifiers, fertilizers and coloring agents. The dry pellets, when applied to a seeded area and watered, forma mulch mat. Pelletized mulch shall be applies in accordance with the manufacturers recommendations Mulch may be applied by hand or mechanical spreader at the rate of 60-75 lbs./1,000 square feet and activated with 0.2 to 0.4 inches of water. This material has bee found to be beneficial for use on small lawn or renovation greas. seeded areas where weed-seed free mulch is desired or on sites where straw mulch and tackifier agent are not practical or desirable. Applying the full 0.2 to 0.4 inches of water after spreading pelletized mulch on the seed bed is extremely important for sufficient activation and expansion of the mulch to provide soil

STANDARD FOR STABILIZATION WITH MULCH ONLY

METHODS AND MATERIALS:

- A. GRADE AS NEEDED AND FEASIBLE TO PERMIT THE USE OF CONVENTIONAL EQUIPMENT FOR SEEDBED PREPARATION, SEEDING, MULCH APPLICATION. AND MULCH ANCHORING. ALL GRADING SHOULD BE DONE IN ACCORDANCE WITH STANDARDS FOR LAND GRADING.
- B. INSTALL NEEDED EROSION CONTROL PRACTICES OR FACILITIES SUCH AS DIVERSIONS. GRADE STABILIZATION MEASURES. SEDIMENT BASINS, AND WATERWAYS.

2. PROTECTIVE MATERIALS

- A. UNROTTED SMALL-GRAIN STRAW, OR SALT HAY AT 2.0 TO 2.5 TONS PER ACRE IS SPREAD UNIFORMLY AT 90 TO 115 POUNDS PER 1000 SQUARE FEET AND ANCHORED WITH A MULCH ANCHORING TOOL, LIQUID MULCH BINDERS, OR OR NETTING TIE DOWN. OTHER SUITABLE MATERIALS MAY BE USED IF APPROVED BY THE SOIL CONSERVATION DISTRICT
- B. SYNTHETIC OR ORGANIC SOIL STABILIZERS MAY BE USED UNDER SUITABLE CONDITIONS
- AND IN QUANTITIES AS RECOMMENDED BY THE MANUFACTURER. C. WOOD-FIBER OR PAPER FIBER MULCH AT THE RATE OF 1.500 POUNDS PER ACRE (OR ACCORDING TO THE MANUFACTURER'S REQUIREMENTS) MAY BE
- D. MULCH NETTING, SUCH AS PAPER JUTE, EXCELSIOR, COTTON, OR PLASTIC, MAY BE USED. E. WOODCHIPS APPLIED UNIFORMLY TO A MINIMUM DEPTH OF 2 INCHES MAY BE USED. WOODCHIPS WILL NOT BE USED ON AREAS WHERE FLOWING WATER COULD WASH THEM
- F. GRAVEL, CRUSHED STONE, OR SLAG AT THE RATE OF 9 CUBIC YARDS PER 1000 SQ. FT. APPLIED UNIFORMLY TO A MINIMUM DEPTH OF 3 INCHES MAY BE USED. SIZE 2 OR 3 (ASTM C-33) IS RECOMMENDED.
- 3. MULCH ANCHORING- SHOULD BE ACCOMPLISHED IMMEDIATELY AFTER PLACEMENT OF HAY OR STRAW MULCH TO MINIMIZE LOSS BY WND AND EATER. THIS MAY BE DONE BY ONE OF THE FOLLOWING METHODS, DEPENDING UPON THE SIZE OF THE AREA AND THE STEEPNESS OF SLOPES.
- A. PEG AND TWINE-DRIVE 8 TO 10 INCH WOODEN PEGS TO WITHIN 2 TO 3 INCHES OF THE SOIL SURFACE EVERY 4 FEET IN ALL DIRECTIONS. STAKES MAY BE DRIVEN BEFORE OR AFTER APPLYING MULCH. SECURE MULCH TO SOIL SURFACE BY STRETCHING TWINE BETWEEN PEGS IN A CRISSCROSS AND A SQUARE PATTERN.
- SECURE TWINE AROUND EACH PEG WITH TWO OR MORE ROUND TURNS. B. MULCH NETTINGS- STAPLE PAPER, COTTON, OR PLASTIC NETTINGS OVER MULCH. USE A DEGRADABLE NETTING IN AREAS TO ME MOWED. NETTING IS USUALLY AVAILABLE IN ROLLS 4 FEET WIDE AND UP TO 300 FEET LONG.
- C. CRIMPER MULCH ANCHORING COULTER TOOL A TRACTOR-DRAWN IMPLEMENT ESPECIALLY DESIGNED TO PUNCH AND ANCHOR MULCH INTO THE SOIL SURFACE. THIS PRACTICE AFFORDS MAXIMUM EROSION CONTROL. BUT ITS USE IS LIMITED TO THOSE SLOPES UPON WHICH THE TRACTOR CAN OPERATE SAFELY. SOIL PENETRATION SHOULD BE ABOUT 3 TO 4 INCHES. ON SLOPING LAND, THE OPERATION SHOULD BE ON THE CONTOUR.

D. LIQUID MULCH-BINDERS

- 1. APPLICATIONS SHOULD BE HEAVIER AT EDGES WHERE WIND CATCHES THE MULCH, IN VALLEYS, AND AT CRESTS OF BANKS. REMAINDER OF AREA
- SHOULD BE UNIFORM IN APPEARANCE. 2. USE ONE OF THE FOLLOWING:
- a. ORGANIC AND VEGETABLE BASED BINDERS NATURALLY OCCURRING, POWDER BASED, HYDROPHILIC MATERIALS THAT MIXED WITH WATER FORMULATES A GEL AND WHEN APPLIED TO A MULCH UNDER SATISFACTORY CURING CONDITIONS WILL FORM MEMBRANED NETWORKS OF INSOLUBLE POLYMERS. THE VEGETABLE GEL SHALL BE PHYSIOLOGICALLY HARMLESS AND NOT RESULT IN A PHYTOTOXIC EFFECT OR IMPEDE GROWTH OF TURFGRASS. VEGETABLE BASED GELS SHALL BE APPLIED AT RATES AND WEATHER CONDITIONS RECOMMENDED BY THE MANUFACTURER.
- SYNTHETIC BINDERS— HIGH POLYMER SYNTHETIC EMULSION, MISCIBLE WITH WATER WHEN DILUTED AND FOLLOWING APPLICATION TO MULCH, DRYING AND CURING SHALL NO LONGER BE SOLUBLE OR DISPERSIBLE IN WATER. IT SHALL BE APPLIED AT RATES AND WEATHER CONDITIONS RECOMMENDED BY THE MANUFACTURER AND REMAIN TACKY UNTIL GERMINATION OF GRASS.

STANDARD FOR PERMANENT STABILIZATION WITH SOD <u>Methods and Materials</u>

- 1. High quality cultivated sod is preferred over native or pasture sod.
- 2. Sod should be free of broadleaf weeds and undesirable coarse and fine weed grasses.
- 3. Sod should be of uniform thickness, typically 5/8 inch, plus or minus 1/4 inch, at time of cutting (excludes top growth.) 4. Sod should be vigorous and dense and be able to retain its own shape and weight when suspended
- uneven ends will not be acceptable. 5. For droughty sites, a sod of turf-type tall fescue or turf-type tall fescue mixed with Kentucky bluegrass is preferred over a 100% Kentucky bluegrass sod. Although not widely available, a sod of fine escue is also acceptable for droughty sites.

vertically with a firm grasp from the upper 10 percent of the strip. Broken pads and rolls or torn and

6. Only moist, fresh, unheated sod should be used. Sod should be harvested, delivered, and installed within a period of 24 hours or less during summer months.

STANDARD FOR PERMANENT STABILIZATION WITH SOD 1. Site Preparation

- A. Grade as needed and feasible to permit the use of conventional equipment fo liming, fertilizing, incorporation of organic matter, and other soil preparation procedures. All grading should be done in accordance with Standard for Land
- B. Topsoil should be handled only when it is dry enough to work without damaging the soil structure. A uniform application to a depth of 6 inches (unsettled) is required on all sites. See the Standard for Topsoiling for topsoil and amendment
- C. Install needed erosion control practices or facilities such as diversions, grade stabilization structures, channel stabilization measures, sediment basins, and

2. Soil Preparation

3. Sod Placement

- A. Uniformly apply ground limestone, and fertilizer according to soil test recommendations such as offered by Rutgers Co-operative Extension. Soil sample mailers are available from the local Rutgers Cooperative Extension offices (http://njaes.rutgers.edu/county/). Fertilizer shall be applied at the rate of 500 pounds per acre or 11 pounds per 1,000 square feet using 10-10-10 or equivalent with 50% water insoluble nitrogen unless a soil test indicates otherwise and incorporated into the surface 4 inches. If fertilizer is not incorporated, apply ½ the rate described above during seedbed preparation and repeat another ½ rate application of the same fertilizer within 3 to 5 weeks after seeding. Apply limestone at the rate of 2 tons/acre unless soil testing indicates otherwise. Calcium carbonate is the equivalent and standard for measuring the ability of liming materials to neutralize soil acidity and supply calcium and magnesium to grasses and legumes.
- B. Work lime, and fertilizer into the topsoil as nearly as practical to a depth of 4 inches with a disc, springtooth harrow, or other suitable equipment. The final harrowing or disking operation should be on the general contour. Continue tillage until a reasonably uniform, fine seedbed is prepared.
- C. Remove from the surface all objects that would prevent good sod to topsoil contact and remove all other debris, such as wire, cable, tree roots, pieces of concrete, clods, lumps, or other unsuitable material.

D. Inspect site just before sodding. If traffic has left the soil compacted, the area must be retilled and firmed in accordance with the above

- A. Sod strips should be laid on the contour, never up and down the slope, starting at the bottom of the slope and working up. On steep slopes, the use of ladders wil facilitate the work and prevent damage to the sod. During periods of high temperature, lightly irrigate the soil immediately prior to laying the sod
- B. Place sod strips with snug, even joints (seams) that are staggered. Open spaces
- C. Lightly roll or tamp sod immediately following placement to insure solid contact of root mat and soil surface. Do not overlap sod. All joints should be butted tightly to
- D. On slopes greater than 3 to 1, secure sod to surface soil with wood pegs, wire staples biodegradable plastic spikes, or split shingles (8 to 10 inches long by 3/4

prevent voids which would cause drying of the roots and invasion of weeds.

- E. Surface water cannot always be diverted from flowing over the face of the slope, but a capping strip of heavy jute or plastic netting, properly secured, along the crown of the slope and edges will provide extra protection against lifting and undercutting of sod. The same technique can be used to anchor sod in water—carrying channels and other critical areas. Wire staples must be used to anchor netting in channel
- F. Immediately following installation, sod should be watered until water penetrates the soil layer beneath sod to a depth of 1 inch. Maintain optimum water for at least two
- 4. Topdressing Since soil organic matter and slow release nitrogen fertilizer (water insoluble) are prescribed in Sections 1 and 2in this Standard, a follow-up topdressing is not mandatory, except where gross nitrogen deficiency exists in the soil to the extent that turf failure may develop, topdressing shall then be applied. Topdress with 10-0-10 or equivalent at 400 pounds per acre or 7 pounds per 1,000 square feet every 3 to 5 weeks until the gross nitrogen deficiency in the turf is ameliorated.

REVEGATATION MATTING INSTALLATION

ALL AREAS SO DESIGNATED WILL BE COVERED WITH MIRAMAT OR APPROVED FOLIVALENT REVEGATATION MATTING REFORE HYDROSEFDING OR PLANTING THE MAT SHALL BE INSTALLED

- UNROLL REVEGETATION MAT FROM TOP OF SLOPE TO THE BASE WITH OUT STRETCHING MAT.
- 2. BURY EDGES OF MAT WITH 3" OF SOIL TO PREVENT UNDERCUTTING OF THE SOIL.
- OVERLAP BY A MINIMUM OF 3" WITH THE LATERALLY
- A LOOPED FASHION, 6" BELOW THE FINISHED GRADE. PEG ALL OVERLAPPED AREAS WITH 1" x 3" NOMINAL WOOD PEGS CUT TO 8" LONG TRIANGULAR SECTIONS, OR 8"

LONG METAL PINS WITH 1-1/2" WASHERS RETAINED AT

OVERLAP BY A MINIMUM OF 3' WITH THE END OF ANY ROLL.

THE TERMINAL ENDS OF EACH STRIP SHALL BE BURIED IN

THE TOP OF THE PINS.

JUTE MATTING SPECIFICATION JUTE MAT SHALL BE OF CLOTH OF A UNIFORM PLAIN WEAVE WITH UNDYED AND UNBLEACHED SINGLE JUTE YARN, 48 INCHES IN WIDTH PLUS OR MINUS 1 INCH AND WEIGHING AN AVERAGE OF 1.2 BS/LINEAR YARD OF CLOTH WITH A TOLERANCE OF PLUS OR MINUS 5% WITH APPROXIMATELY 78 WRAP ENDS PER WIDTH OF CLOTH AND 41 WEFT ENDS PER LINEAR YARD OF CLOTH. THE YARN SHALL BE OF A LOOSELY TWISTED CONSTRUCTION HAVING AN AVERAGE TWIST OF NOT

LESS THAN 1.6 TURNS/INCH AND SHALL NOT VARY IN THICKNESS BY

- 2. EXCELSIOR MAT SHALL BE WOOD EXCELSIOR, 48 INCHES IN WIDTH PLUS OR MINUS 1 INCH AND WEIGHING 0.8 LBS/SQUARE YARD PLUS OR MINUS 10 PERCENT. THE EXCELSIOR MATERIAL SHALL BE COVERED MITH A NETTING TO FACILITATE HANDLING AND TO INCREASE STRENGTH
- 3. STAPLES STAPLES FOR ANCHORING SOIL STABILIZATION MATTING SHALL BE MADE OF 12 TO 20 INCHES IN LENGTH OF NO. 8 PLAIN

MORE THAN ONE HALF OF ITS NORMAL DIAMETER.

STANDARD FOR DUST CONTROL WHERE APPLICABLE, THE FOLLOWING METHODS, OR OTHER METHODS AS APPROVED BY THE SOIL CONSERVATION DISTRICT, ARE TO BE USED FOR

- MULCHING AS PER SPECIFICATION LISTED.
- 2. VEGETATIVE COVER AS PER TEMPORARY AND PERMANENT SPECIFICATION LISTED.
- SPAY-ON ADHESIVES ON MINERAL SOILS (NOT EFFECTIVE ON MUCK SOILS). KEEP TRAFFIC OFF THESE AREAS.

SEQUENCE OF CONSTRUCTION:

- 1. INSTALL TEMPORARY SEDIMENT CONTROL BARRIERS AND TREE PROTECTION FENCE WHERE INDICATED: STABILIZE CONSTRUCTION ENTRANCES. (2 WEEKS)
- 2. PERFORM TREE CLEARING / PRUNING (ABOVE GRADE). (2 WEEKS)
- 3. CLEAR AND STRIP TOPSOIL IN AREA OF CONSTRUCTION. STABILIZE STOCKPILES. (3 WEEKS)

4. CONSTRUCT STONE DUST WALKWAY AND OUTDOOR CLASSROOMS AS PER PLANS. (4 WEEKS)


- 5. CONSTRUCT CONCRETE PAVER WALKWAY, PATIO, AND MAIN SENSORY GATHERING SPACE AS PER PLANS. (4 WEEKS)
- 6. REMOVE TEMPORARY SEDIMENT CONTROL BARRIERS AND TREE PROTECTION FENCE. (2 WEEK) 7. REMOVE STABILIZED CONSTRUCTION ENTRANCE.

8. TOTAL AREA OF DISTURBANCE: 1.18 ACRES

<u>SECTION</u> Ground R.O.W. 20' Wide 2 1/2' Clean Crushed Stone 6" Thick

STABILIZED CONSTRUCTION ENTRANC

<u>PLAN</u>




TOPSOIL STOCKPILE DETAIL.

SHALL BE STABILIZED.

- 2. THE STOCKPILE SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE
- 3. ALL SILT FENCE SHALL BE PROVIDED IN ACCORDANCE WITH THE SILT FENCE DETAIL. SILT FENCE SHALL BE PROVIDED ON THE DOWNHILL SIDE OF ANY AND ALL DISTURBANCE.
- 4. ANY DISTURBED AREA REMAINING DISTURBED FOR MORE THAN 30 DAYS

STOCKPILE DETAIL




DATE DRAWN CHECKE DESCRIPTION OF REVISION BOROUGH OF MOUNTAINSIDE UNION COUNTY, NEW JERSEY SENSORY TRAIL IMPROVEMENTS WATCHUNG RESERVATION SOIL EROSION & SEDIMENT CONTROL NOTES & DETAILS CONSULTING AND MUNICIPAL ENGINEERS — 3141 BORDENTOWN AVENUE, PARLIN, NEW JERSEY 08859 —— 1460 ROUTE 9 SOUTH, HOWELL, NEW JERSEY 07731-1194 — JOHN H. ALLGAIR P.E., P.P. DAVID J. SAMUEL P.E., P.P. JOHN J. STEFANI P.E., L.S. & P.P. (1963 - 2001) W PE UC NO. 25830 NJ FP UC NO. 2455 NJ PELS LIC NO. 24271 NJ FP LIC NO. 2007 JAY B. CORNELL P.E., P.P. MICHAEL J. McCLELLAND P.E., P.P. **GREGORY R. VALESI P.E., P.P.** NU PP UC NO. 3770 NU PE LIC NO. 34458 NU PP UC NO. 496 AS SHOWN 7 OF 10 SEP 2016


N.J. LIC. 34458


1/6/17 | SEL | SEL


ONAL ENGINEER

REVISED DATE FOR REBID










DECIDUOUS TREE PLANTING DETAIL

TREE SHALL BE PLANTED ON UNDISTURBED SUB-SOIL TO PREVENT SETTLING.



CONIFER TREE PLANTING DETAIL

